
## **Beaufort** Sea Utqiagvik Chukchi for Sea Seward Peninsula Sound Strategi Bering Sea Aleutian Islands Alaska ponse Location of NE-31 Map & Photo esi Legen eographic Landlocked Bay, DV 02, View Northeast Free-oil Containment Exclusion EX and Recovery, Shallow **Booming** Water Diversion Shore-seal Boom Booming Shoreside **Passive** Recovery Recovery Protected-water **Snare or Sorbent Boom** 1000000 Boom

**Northeast** 

## Landlocked Bay, NE-31



	T						D D	
ID	Location and Description	Response Strategy	Implementation	Response Resources	Staging Area	Site Access	Resources Protected (months)	Special Considerations
NE-31-01	Landlocked Bay	Free-oil Recovery	Deploy free-oil recovery strike teams	Multiple nearshore free-oil recovery	Valdez Harbor	Via marine	Same as NE-31-02	Vessel master should have local
		1100 011 11000 (01)	upwind and up current of	strike teams as required to maximize	1111001	waters	Outile us 1 (E 51 6	knowledge.
~	Nearshore waters in the general	Maximize free-oil recovery in the	Landlocked Bay.	interception of oil before it impacts		Waters		inio wicage.
(FO.S)	area of:	offshore & nearshore environment	Landrocked Day.	sensitive areas.		Chart 16708-1		Use extreme caution, shoal waters
(FO-5)	area of.	of Landlocked Bay depending on	Use aerial surveillance to locate	sensitive areas.		Chart 10700 1		with numerous reefs and rocks.
	Lat. 60° 49.09' N	spill location and trajectory.	incoming slicks.					with fighter one rees and rees.
	Lon. 146° 35.88' W	op== == ===============================						
NE-31-02	Landlocked Bay	Divert and Collect	Deploy anchors and boom with skiffs	Deployment Equipment	Vessel platform	Via marine	Fish- intertidal spawning-	Vessel master should have local
			(class 6).	1200 ft. protected-water boom	1	waters.	salmon (May-Sept.), herring	knowledge.
	Lat. 60° 51.22' N	Divert oil to a shoreside collection		200 ft. tidal-seal boom			spawning (April-May)	
DV	Lon. 146° 34.42' W	area in Landlocked Bay.	Place 50 ft. sections of tidal-seal	7 ea. anchor systems		Chart 16708-1		Site surveyed: 09/02/10
			boom on each shore. Complete with	4 ea. anchor stakes			Birds-waterfowl	
			1200 ft. protected-water boom in	1 ea. shore-side collection unit			concentration,	Tested: 10/16/12 SERVS
			chevron pattern at the proper angle	Vessels				Deployment
			to divert the majority of incoming oil	2 ea. class 3/4			Marine mammals- seals	
			to the north shoreside collection	1 ea. class 6				During testing, channel depth at
			sites. If necessary place passive	Personnel/Shift			Human use- commercial	apex of chevron was greater than
			recovery on the south.	5 ea. vessel crew			fishing, high recreation use,	115 feet. Configure anchors to be
				2 ea. response techs			subsistence.	used at the apex of the boom to
			Set up collection site and tend	Tending Vessels				include trip lines greater than 120
			throughout the tide. If oil is not	1 ea. class 3/4			Habitat- marsh, sheltered	feet in length.
			collecting in significant amounts, use	1 ea. class 6 Personnel/Shift			tidal flats	
			sorbent materials to collect the oil.	3 ea. vessel crew				On southern shore, bedrock
				2 ea. response techs				shoreline limits anchor options. A
								permanently installed shore anchor
NE 24 02	T 11 1 1 D	T	D 1 1 11 11 11 11 11 11 11 11 11 11 11 1	5 1 5	XX 1 1 C	T7'	0 NE 04 00	is recommended.
NE-31-03	Landlocked Bay	Exclusion	Deploy anchors and boom with skiffs	Deployment Equipment	Vessel platform	Via marine	Same as NE-31-02	Vessel master should have local
	a. Lat. 60° 51.14' N	Elade all forces increasing the	(class 6) at high tide.	150 ft. protected-water boom 250 ft. tidal-seal boom		waters		knowledge.
EX	a. Lat. 60 31.14 N Lon. 146° 31.31' W	Exclude oil from impacting the identified stream and intertidal area	Ear (a) place two (2) 50 ft sections of	4 ea. small anchor systems		Chart 16708-1		Title 41 permitting required from
EA	Lon. 140 31.31 W	in Landlocked Bay.	For (a) place two (2) 50 ft. sections of tidal-seal boom on each shore.	8 ea. anchor stakes		Chart 10/06-1		ADNR.
	b. Lat. 60° 51.32' N	III Landiocked Day.	Complete the exclusion with 150 ft.	Vessels/Personnel/Shift Same as				ADIVIC.
	Lon. 146° 31.61' W		of protected-water boom in a	NE-31-02				Several partially submerged rocks
	Boll 110 31.01 W		chevron formation at the identified	Tending Vessels/Personnel/Shift				are present on the east and west
			location.	Same as NE-31-02				shores near the creek. Vessel
								operators need to be cautious.
			For (b) place 150 ft. of tidal-seal					^
			boom across the stream mouth.					Tested:
			Alternately, place 50 foot sections of					a. 10/16/12 SERVS Deployment
			tidal-seal on either shore and 100 feet					b. 10/18/12 SERVS Deployment
			of protected-water boom across the					
			stream mouth.					
			m					
NIE 24 0 1	I II I I D	D : D	Tend throughout the tide.	D. I.	77 1 1 . C	<b>T</b> T: .	C NE 24 02	1
NE-31-04	Landlocked Bay	Passive Recovery	On a flooding tide, use skiffs (class 6)	Deployment Equipment	Vessel platform	Via marine	Same as NE-31-02	Use snare line for persistent oils and
	a. Lat. 60° 51.14' N	Place passive recovery across the	and place and anchor two (2) 200 ft.	400 ft. snare line or sorbent boom		waters		sorbent boom for non-persistent
77.7	Lon. 146° 31.31' W	channels of the streams in the back	of snare line or sorbent boom across	2 ea. small anchor systems		Chart 1(700 1		oils.
PR	b. Lat. 60° 51.32' N	of Landlocked Bay.	the streams that enter Landlocked	8 ea. anchor stakes Vessels/Personnel/Shift		Chart 16708-1		Title 41 permitting required from
	Lon. 146° 31.61' W		Bay.	Same as NE-31-02				Title 41 permitting required from ADNR.
	LOII. 140 31.01 W		Replace as necessary to maximize the	Tending Vessels/Personnel/Shift				ADINK.
			recovery.	Same as NE-31-02				Tested: not yet
	. <b>L</b>	<u> </u>	1 2000 .02).	00 10110101			<u> </u>	1 2000000 1000 1000