Site Assessment Pitkas Point School Site Pitkas Point, Alaska ADEC File ID: 2444.57.001

January 2016



Excellence. Innovation. Service. Value. *Since 1954*.

Submitted To:

Alaska Department of Environmental Conservation
Spill Prevention and Response
555 Cordova Street
Anchorage, Alaska 99501

By: Shannon & Wilson, Inc. 5430 Fairbanks Street, Suite 3 Anchorage, Alaska 99518

# TABLE OF CONTENTS

			Page
ACR	ONYM	S AND ABBREVIATIONS	iii
ACR	ONYM	S AND ABBREVIATIONS (continued)	iv
1.0		ODUCTION	
2.0	SITE	AND PROJECT DESCRIPTION	1
3.0	BAC	KGROUND	2
4.0	SHA	NNON AND WILSON SITE CHARACTERIZATION ACTIVITIES	3
	4.1	Scope Modifications	
	4.2	Impacted Soil Delineation	3
	4.3	Visual Inspection of Former School Tank Farm	
	4.4	Soil Stockpiles and Super-sacks	6
	4.5	Debris Inventory and Property-Wide Contamination Assessment	6
	4.6	Investigation Derived Waste	
5.0	SUBS	SURFACE CONDITIONS	
6.0		ORATORY ANALYSIS	
7.0		USSION OF RESULTS	
	7.1	Soil Samples	
	7.2	Quality Assurance Summary	
8.0	HAZ	ARDOUS MATERIALS ASSESSMENT	
	8.1	Asbestos-Containing Materials	
	8.2	Lead-Containing Materials	
	8.3	PCB- and Mercury- Containing Materials	
	8.4	Other Hazardous Materials	
	8.5	Fungal Growth	
9.0		JCTURAL INTEGRITY ASSESSMENT	
,.0	9.1	TH1 and TH2 Structures	
	9.2	SB Structure	
10.0		CEPTUAL SITE MODEL	
10.0	10.1	Soil – Direct Contact	
	10.2	Groundwater	
	10.3	Air	
	10.4	Surface Water	
	10.5	Other	
	10.6	CSM Summary	
11.0		COSTS	
11.0	11.1	Hazardous Materials Abatement ROM Cost Summary	
	11.2	Structural Repair ROM Cost Summary	
	11.3	Soil Remediation ROM Cost	
12.0		CLUSIONS	
12.0	12.1	Site Assessment/Characterization	
	12.1	HMA	
	12.2	SIA	
	12.3	Data Gaps	
13.0		SURE/LIMITATIONS	
15.0	CLU		/

# SHANNON & WILSON, INC.

# **TABLES**

1	Sample Locations and Descriptions
2	Summary of Analytical Results
	FIGURES
1	Vicinity Map
2	Site Plan
3	Area PPS1/PPS11 Soil Sample Locations
4	Area PPS10 Soil Sample Locations
5	Area PPS12 Soil Sample Locations
6	Area PPS13 Soil Sample Locations
7	Debris Inventory and Property-Wide Assessment Soil Sample Locations
	APPENDICES
A	Field Notes
В	Site Photographs
C	Results of Analytical Testing By SGS North America Inc. of Anchorage, Alaska and ADEC Laboratory Data Review Checklists
D	EHS-Alaska, Inc., Hazardous Materials Assessment – Pitkas Point School Site Hazmat Survey
E	Coffman Engineers, Pitka's Point School – Structural Integrity Assessment
F	Conceptual Site Model
G	Important Information About Your Geotechnical/ Environmental Report

#### SHANNON & WILSON, INC.

#### ACRONYMS AND ABBREVIATIONS

AAC Alaska Administrative Code ACM Asbestos-Containing Materials

ADEC Alaska Department of Environmental Conservation

AK Alaska Method

AST Aboveground Storage Tank

bgs Below ground surface

BTEX Benzene, Toluene, Ethylbenzene, and Xylenes

CBC Community Basketball Court
CFR Code of Federal Regulations
City Pitkas Point Community
COC Contaminant of Concern
CSM Conceptual Site Model
CW Community Washeteria

DBAC DEC Brownfield Assessment and Cleanup

DEED Department of Education and Early Development

DCCED Department of Commerce, Community, and Economic Development

DQO Data Quality Objective
DRO Diesel Range Organics
EHS EHS-Alaska, Inc.

EPA Environmental Protection Agency

FH Fire House

GB Generator Building

GPS Global Positioning System
GRO Gasoline Range Organics
HID High-intensity Discharge

HMA Hazardous Materials Assessment IDW Investigation Derived Waste

LBP Lead-Based Paint

LCS/LCSD Laboratory Control Sample/Laboratory Control Sample Duplicates

LDRC Laboratory Data Review Checklist
LYSD Lower Yukon School District
mg/cm<sup>2</sup> Milligram per centimeter squared

mg/kg Milligram per kilogram

MS/MSD Matrix Spike/Matrix Spike Duplicate

MTG Migration to Groundwater
PCBs Polychlorinated bi-phenyls
PID Photoionization detector

ppm Parts per million

Property Pitkas Point Elementary School Complex

#### SHANNON & WILSON, INC.

# ACRONYMS AND ABBREVIATIONS (CONTINUED)

ROM Rough Order of Magnitude RPD Relative Percent Difference

SB Pitkas Point Elementary School Building

SIA Structural Integrity Assessment

RSE Restoration Science and Engineering, LLC

SCA Secondary Containment Area SGS SGS Environmental Services, Inc.

SSB School Shop Building

TF Tank Farm

TH1 Teacher Housing Building #1TH2 Teacher Housing Building #2VOC Volatile Organic Compounds

XRF X-Ray Fluorescence

# SITE ASSESSMENT PITKAS POINT SCHOOL SITE PITKAS POINT, ALASKA ADEC FILE ID: 2444.57.001

#### 1.0 INTRODUCTION

This report presents the results of Shannon & Wilson's site assessment conducted at the Pitkas Point Elementary School Complex (Property) in Pitkas Point, Alaska. The Department of Commerce, Community, and Economic Development (DCCED) requested assistance from the Alaska Department of Environmental Conservation (ADEC) through the DEC Brownfield Assessment and Cleanup (DBAC) Program to assess what portions of the Property can be safely used by the Pitkas Point Community (City). The specific objectives of this site characterization are to assess the integrity of on-site structures and determine how much (if any) contamination is present in the Property's soil.

This project was conducted under Shannon & Wilson's ADEC Hazardous Substance Spill Prevention and Cleanup Term Contract 18-8036-03. ADEC authorization to proceed was received on August 10, 2015 with Notice to Proceed Number 18-8036-03-032. The work was conducted in scope with our September 3, 2015 ADEC-approved work plan.

#### 2.0 SITE AND PROJECT DESCRIPTION

The Property can be found near the confluence of the Yukon and Andreafsky Rivers, 5 miles southwest of St. Mary's on the Yukon-Kuskokwim Delta, and 3 miles by road from the St. Mary's airport. The Property is located at 61°01'54" N and 163°17'13" W (WGS84) in USGS Quadrangle "Kwiguk (A-3)," Alaska, Township 22 North, Range 76 West, Seward Meridian. A vicinity map is provided as Figure 1.

The Property comprises multiple structures as shown on Figure 2, including the Pitkas Point Elementary School Building (SB), five teacher housing units (TH), the School Shop Building (SSB), the Community Basketball Court (CBC), the Community Washeteria (CW), the Firehouse (FH), the Generator Building (GB), and a Tank Farm (TF). The structures are vacant and in various states of deterioration. The CW is partially demolished and building debris is stored within and around the building foundation walls. The TF is not operational and the chain-link fence around the TF area is in a state of disrepair.

The site assessment included structural integrity assessments (SIA) and hazardous materials assessments (HMA) of Teacher Housing Building #1 (TH1), Teacher Housing Building #2 (TH2), and the SB; characterizing residual contamination at a diesel spill site that was not addressed during the 2004 cleanup activities; conducting a visual assessment of the former school tank farm; attempting to locate and characterize stockpiled soil and super-sacks generated

during the 2000 and 2004 site assessment efforts; and performing a debris inventory and property-wide assessment of speculated contamination and debris.

EHS-Alaska, Inc. (EHS) of Eagle River, Alaska provided the HMA. Coffman Engineers (Coffman) provided the SIA. SGS North America, Inc. (SGS) of Anchorage, Alaska performed the laboratory testing of analytical soil samples. EHS, SGS, and Coffman were subcontracted to Shannon & Wilson.

Mr. Elia, Lower Yukon School District (LYSD) representative, identified and provided access to the locked SB, TH1, and TH2 to allow for EHS and Coffman to perform the HMA and SIA of the buildings on September 16, 2015.

#### 3.0 BACKGROUND

In 1984 the state issued a 55-year lease to the Department of Education & Early Development (DEED) to construct, operate, and maintain a school. DEED subsequently issued a permit to the LYSD to use the land for the school. The school closed in 2013 but will remain under the jurisdiction of DEED and the LYSD until it is determined that the site does not pose an unacceptable risk to human health and the environment.

Two previous environmental assessments were conducted on the Property in 2000 and 2004. Results of the first study are documented in the Restoration Science & Engineering, LLC (RSE) report, *Diesel Spill Site Assessment and Water Quality Sampling, Pitkas Point, Alaska, 2000.* According to the report, an approximate 55-gallon spill of diesel fuel released from a flexible coupling on a fuel transfer pipe occurred in 2000. The spill was located approximately 25 feet north of the northeast corner of the SB. Approximately 8 cubic yards of diesel fuel-impacted soil were excavated from the spill site and stockpiled near the school TF. Confirmation soil samples collected from beneath the spill site identified concentrations of diesel range organics (DRO) up to 223,000 milligrams per kilograms (mg/kg) which exceeds the ADEC's Method 2 migration to groundwater (MTG) and human health ingestion/inhalation cleanup levels. Additional soil samples collected along aboveground water and fuel piping at the areas identified as PPS1/PPS11, PPS10, PPS12, and PPS13 also contained DRO concentrations greater than the ADEC's MTG and/or human health ingestion/inhalation cleanup levels but were not further investigated.

The second report, *Corrective Action Report*, *Pitkas Point Alaska*, by RSE documents the 2004 excavation of 102 cubic yards of DRO-impacted soil at the diesel fuel release near the flexible coupling identified in 2000. Excavated soil was placed in super-sacks and temporarily stored adjacent to the excavation. Confirmation soil samples collected from the excavation base beneath the failed flexible coupling did not contain target analyte concentrations greater than ADEC Method 2 cleanup levels. However, RSE reported that based upon photoionization

detector (PID) screening, soil above the ADEC Method 2 cleanup level may remain in the excavation sidewalls.

#### 4.0 SHANNON AND WILSON SITE CHARACTERIZATION ACTIVITIES

A Shannon & Wilson representative visited the Property on September 15 through 19, 2015 to further delineate soil contamination along the fuel and water supply lines at the diesel spill site, the former school tank farm, soil stockpiles and supersacks, and speculated contamination and debris. Field work was conducted by an ADEC-Qualified Environmental Professional as defined by 18 Alaska Administrative Code (AAC) 75.330, who collected field screening and analytical soil samples, and coordinated with the project laboratory for sample testing.

Project sample locations, screening results, and soil descriptions are summarized in Table 1. Field notes taken during the site activities are included in Appendix A. Swing-tie measurements and global position system (GPS) coordinates of soil sample locations are included in the field notes. However, the swing-tie measurements are considered to be more accurate than the GPS coordinates due to the GPS accuracy reported range of 12 to 30 feet. Photographs of the sampling activities are included in Appendix B.

# 4.1 Scope Modifications

The following change to the scope presented in the work plan was implemented due to conditions encountered in the field:

- The work plan included a visual assessment of the former school TF for indications of contamination. During the visual assessment, a sheen was observed on the surface water ponded within the containment area near the southeast corner. Therefore, after receiving ADEC approval, two soil samples were collected outside the TF containment area, targeting areas where fluids would likely flow given a breach of the containment area. The soil samples were collected from an area downgradient of the south side of the TF.
- The work plan included a task to identify and locate the stockpiled soil and super-sacks generated during the 2000 and 2004 site assessment activities and collect soil samples. An interview of an LYSD representative regarding the location of the removed soil and locations shown in the RSE reports was conducted, but the stockpiled soil and super-sacks could not be located.

# 4.2 Impacted Soil Delineation

On September 15 through 19, 2015, 17 test pits were advanced in the vicinity of the former RSE sample locations PPS1/PPS11, PPS10, PPS12, and PPS13 to evaluate the vertical and horizontal extent of soil contamination. In general, one test pit was advanced near the original RSE sample

at each location, with three or four additional test pits positioned radially outward to delineate the lateral extent of impacted soil. Four test pits were advanced in the area of PPS1/PPS11, five test pits in the area of PPS10, five test pits in the area of PPS12, and four test pits in the area of PPS13. The approximate locations of the test pits are shown on Figures 3 through 6, and Photos 2 through 6. Each test pit was advanced by hand using a 3-inch diameter steel bucket auger to a depth of 2 feet below ground surface (bgs). Plastic sheeting was placed on the surface at each test pit location and soil removed from the test pit was placed on the plastic sheeting. Field screening and analytical soil samples were collected with a clean stainless steel spoon from undisturbed soil at the base of the test pit at depths of 0.5, 1.0, 1.5, and 2.0 feet bgs. The sampling equipment and hand auger were decontaminated between each sample location. At the completion of the test pits, soil placed on the plastic sheeting was used to backfill the corresponding test pit.

Each sample was "screened" for volatile organic compounds (VOCs) using a PID and ADEC-approved headspace screening techniques. Screening samples were placed in a resealable plastic bag to approximately one-half capacity using a clean stainless steel spoon. The samples were then warmed for at least 10 minutes, but not more than one hour. The temperature of the samples were at least 40 degrees Fahrenheit prior to screening. To screen, the sample was agitated for about 15 seconds, the seal of the bag was opened slightly, the instrument probe was inserted into the air space above the soil, and the bag held closed around the probe. The maximum ionization response as the PID draws vapor from the sample bag was recorded. The PID was calibrated before use daily with 100 parts per million (ppm) isobutylene in air standard gas.

Sixteen field screening samples were collected from four test pits in the vicinity of Area PPS1/PPS11. Based on the highest headspace screening results and selection of one sample in the original RSE sample area (2.1 ppm and 4.6 ppm), two analytical soil samples (Samples PPS1/PP11-B and PPS1/PP11-3-A) were collected from the test pits.

Twenty field screening samples were collected from five test pits in the vicinity of Area PPS10. Based on the highest headspace screening results ranging from 5.3 ppm to 260 ppm, one sample in the original RSE sample area, and spatial representation, six analytical soil samples, including one field duplicate (Samples PPS10-D, PPS10-1-B, PPS10-2-D, PPS10-3-DX [duplicate of PPS10-3-D], and PPS10-4-B) were collected from the test pits.

Twenty field screening samples were collected from five test pits in the vicinity of Area PPS12. Based on the highest headspace from each test pit, screening results ranging from 1.9 ppm to 270 ppm, selection of one sample in the original RSE sample area, and spatial representation, four analytical soil samples, including a field duplicate (Samples PPS12-C, PPS12-2-A, PPS12-3-C, and PPS12-3-CX [duplicate of PPS12-3-C]) were collected from the test pits.

Twelve field screening samples were collected from four test pits in the vicinity of Area PPS13. Based on the highest headspace screening results from each test pit ranging from 2.7 ppm to 8.1 ppm, selection of one sample in the original RSE sample area, and spatial representation, three analytical soil samples (Samples PPS13-C, PPS13-1-A, and PPS13-2-B) were collected from the test pits.

Fifteen analytical soil samples, including 2 duplicates, were collected at the Property near the former RSE sample locations of PPS1/PPS11, PPS10, PPS12, and PPS13 areas.

Analytical soil samples were collected by quickly and completely filling the laboratory-provided jars. Soil samples for laboratory analysis were collected in laboratory-supplied jars in decreasing order of volatility. For each volatile sample, at least 25 grams of soil, but no more than what could be completely submerged with 25 milliliters of methanol, were placed into a pre-weighted, 4-ounce jar with a septa lid. A 25-milliliter aliquot of methanol containing laboratory-added surrogates was added to the sample jar to submerge the soil sample. For each non-volatile sample, the laboratory-supplied jar was completely filled with soil taking care to remove gravel and debris. Sample jars were filled using decontaminated stainless steel spoons, placed in coolers with ice packs, and transferred to the laboratory using chain-of-custody procedures.

# 4.3 Visual Inspection of Former School Tank Farm

Shannon & Wilson's field representative visually assessed the former school tank farm to document the presence or absence of fuel storage tanks, stockpiled soil, vegetation, sheen(s), stained soil, or other indications of potential contamination.

Five out-of-service tanks (three horizontal and two vertical) with estimated capacities ranging from 2,000 to 6,000 gallons were observed at the tank farm. In addition, nine 55-gallon drums were stored within the tank farm's bermed containment area. There was no evidence of stockpiled soils or stressed vegetation (i.e., localized areas of small grasses and moss were observed) within or adjacent to the tank farm. The two former school's tanks identified in the RSE 2000/2004 reports were removed from the wood support structure, and removed from the site (Photo 7). The secondary containment area (SCA) liner appeared to be mostly intact (small tears were noted at several locations) and functioning to contain water inside the SCA. A sheen was observed (Photo 8) on the surface water near the southeast corner of the containment area. Although the SCA appears appropriately constructed for its containment function, if sufficient water accumulates in the SCA, the lowest point where water would exit is at two locations on the southern berm (Photo 9). Other debris observed in the SCA included wood pallets, steel piping and flex couplers, and flex hosing.

## 4.4 Soil Stockpiles and Super-sacks

Shannon & Wilson's field representative attempted to locate the stockpiled soil and super-sacks generated during the 2000 and 2004 site assessment activities that were removed or disposed off-site. The soil stockpile and super-sacks were not observed during our visual assessment.

Shannon & Wilson's field representative, Trevor Crosby, interviewed Mr. Elia, LYSD representative, on September 16, 2015 about the locations of the soil stockpiles and super-sacks. Mr. Elia was aware of the 2000 and 2004 site assessment activities, but unable to provide details on the current location of the soil stockpile or super-sacks.

#### 4.5 Debris Inventory and Property-Wide Contamination Assessment

Shannon & Wilson's field representative created an inventory of the debris and conducted a visual assessment of aboveground piping and associated debris to document the nature, quantity, and location of the abandoned/unused debris, and its potential impact to soil and groundwater. In general, field screening and analytical soil samples were collected at low-lying areas, along drainage pathways where contaminants would likely accumulate, beneath and around the various debris and abandoned piping, or at representative debris storage locations.

Sixteen field screening samples were collected near or beneath aboveground storage tanks (ASTs), aboveground piping runs, 55-gallon drums, and miscellaneous debris (Photos 10 through 14) at various locations throughout the site, as shown on Figure 7. The soil samples were collected from approximately 0.4 to 1.0 foot bgs using a 3-inch diameter steel bucket auger. Each soil sample was "screened" for VOCs using the method described above. Based on the highest headspace screening results (ranging from 0.8 ppm to 114 ppm) eight analytical soil samples, including one field duplicate (Samples TF1, TF2, AST4, AST4X [duplicate of AST4], AST8, AST9, AST10, and PR3), were collected. Two of the analytical soil samples, Samples TF1 and TF2, were collected south of the former school tank farm beyond the bermed area, where a large spill would likely flow at the approximate locations shown in Figure 7.

#### 4.6 Investigation Derived Waste

Investigation derived waste (IDW) generated during the site assessment included the excavated soil, plastic liners, and gloves. At the completion of the test pits, soil placed on the plastic sheeting was used to backfill the corresponding test pits. The disposable sampling materials were disposed as unregulated solid waste in a refuse dumpster.

#### 5.0 SUBSURFACE CONDITIONS

The site was generally consisted of low to high grasses and medium sized trees (alders) on eastern side of the property. The surface soil in the top 2 feet bgs at the site generally consisted

of light to dark brown silt with organics, and/or Peat with silt. Groundwater was not observed in the test pits during the September 2015 site characterization activities.

#### 6.0 LABORATORY ANALYSIS

The project soil samples were submitted to SGS in chilled coolers using chain-of-custody procedures. The 23 soil samples, including three field duplicates, were analyzed for gasoline range organics (GRO) by Alaska Method (AK) 101; DRO by AK 102; RRO by AK 103; and benzene, toluene, ethylbenzene, and xylenes (BTEX) by EPA Method 8021B. In addition, due to high organic content of many of the samples, five samples were also analyzed for DRO/RRO using a silica gel extraction. For quality control purposes, two trip blanks were included in the sampling program and analyzed for GRO by AK 101 and BTEX by EPA Method 8021B. The analytical sample results are summarized in Table 2 and the laboratory reports are included in Appendix C.

A typical sample identification, as delivered to the laboratory, is "17741-PPS1/PPS11-1-A". The sample identification includes the Shannon & Wilson job number "17741" as a prefix, "-PPS1/PPS11" indicates the former RSE sample area, "-1" is the uniquely numbered test pit, and "A" represents the depth of the sample collected (0.5-foot). The samples were identified with "A", "B", "C", or "D" following the sample location ("PPS1/PPS11-1") which corresponds to depths of 0.5, 1.0, 1.5, and 2.0 feet bgs, respectively. The job number prefix "17741" has been left out in the body of this report for brevity.

#### 7.0 DISCUSSION OF RESULTS

The reported analyte concentrations in the project soil samples are compared to the cleanup levels listed in the Oil and Other Hazardous Substances Pollution Control Regulations (18 AAC 75, Section 341). The soil cleanup criteria are based on the most stringent ADEC Method 2 exposure pathway listed in Tables B1 and B2 for the "under 40-inch (precipitation) zone". The summary analytical results and applicable cleanup levels are listed in Table 2.

# 7.1 Soil Samples

Multiple samples contained DRO concentrations above the ADEC's MTG cleanup level, as detailed below. The remaining analytes were either not detected, or were measured at concentrations of less than ADEC Method 2 cleanup levels in the test pit samples.

Based on screening and analytical samples, the soil at Areas PPS1/PPS11 and PPS13 is not impacted above ADEC Method 2 cleanup levels.

DRO-impacted soil with concentrations above ADEC Method 2 MTG cleanup level, is present in four of the five test pits in Area PPS10. The concentrations are less than the human health

cleanup levels for direct contact and outdoor air inhalation. The extent of DRO-impacted soil is not defined laterally or vertically.

Based on field screening and analytical samples, DRO-impacted soil above ADEC Method 2 cleanup levels is present in one of the five test pits advanced in Area PPS12. The samples are less than the human health cleanup levels for direct contact and outdoor air inhalation. These results suggest the extent of DRO-impacted soil at Area PPS12 is limited to shallow soil adjacent to the northeast side of the FH.

DRO silica gel extraction for Samples PPS12-3-C and PPS13-C were detected at concentrations less than the ADEC Method 2 cleanup level of 250 mg/kg. By inspection of Table 2, DRO results before and after silica gel extraction, the high ratio of non-polar DRO to total DRO suggests the presence of anthropogenic (fuel) hydrocarbons.

DRO-impacted soil with concentrations above ADEC Method 2 MTG cleanup level, is present at Areas TF2, AST4, AST9, and AST10. The samples are less than the human health cleanup levels for direct contact and outdoor air inhalation. The lateral and vertical extent of impacted soil is not defined in these areas.

# 7.2 Quality Assurance Summary

The project laboratory implements on-going quality assurance/quality control procedures to evaluate conformance to applicable ADEC and EPA data quality objectives (DQOs). Internal laboratory quality controls for this project included surrogates, method blanks, laboratory control sample/laboratory control sample duplicates (LCS/LCSD), and matrix spike/matrix spike duplicates (MS/MSD). If a DQO for one of the controls is not met, the laboratory provides a brief explanation in the case narrative of their report (See Appendix C).

External quality controls include two trip blanks and three field duplicate samples. Field logs and records were checked for completeness and accuracy. The relative percent difference (RPD) between the project sample and associated duplicate results is a measure of precision affected by matrix heterogeneity, sampling technique, and laboratory analyses. The ADEC recommends an RPD of less than 50 percent for field duplicates. The RPD for total xylenes is greater than 50 percent (104 percent) in Samples AST4 and AST4X; however, the contaminant concentrations in both samples are below cleanup levels therefore the RPD non-conformance does not impact data usability for the objectives of this project. The RPDs for DRO Silica Gel and RRO Silica Gel is greater than 50 percent (64 percent) in Samples PPS12-3-C and PPS12-3-CX. Because the RRO Silica Gel concentration in both samples are less than the most stringent ADEC cleanup level, the RRO data are considered usable. However, the DRO Silica Gel concentration in the primary sample (PPS12-3-C; 155 mg/kg) is less than the ADEC Method 2 cleanup level while the duplicate sample (PPS12-3-CX; 301 mg/kg) is above than the ADEC Method 2 cleanup level potentially impacting the use of the data to determine if DRO Silica Gel concentrations in soils at

PPS12-3-C are above cleanup levels. Since the primary sample (PPS12-3-C) result is potentially biased low due to hold time exceedance the duplicate sample DRO Silica Gel result will be used to characterize the soil at this location.

Laboratory-prepared trip blank samples accompanied the project sample jars from the laboratory to the site during sampling activities and back again to SGS. The trip blanks did not contain detectable GRO or BTEX concentrations.

GRO, toluene, and total xylenes were detected at estimated concentrations in laboratory method blanks. Affected project samples are qualified with a B-flag in Table 2 (see Laboratory Data Review Checklist (LDRC) in Appendix C for details). There is no adverse impact to data usability, as the B-flagged data are at least an order of magnitude less than ADEC cleanup levels.

Shannon & Wilson reviewed the SGS data deliverables and completed an ADEC LDRC for the work orders for this project. The laboratory reports and data review checklists are included in Appendix C.

#### 8.0 HAZARDOUS MATERIALS ASSESSMENT

On September 16 and 17, 2015, EHS-Alaska, Inc. performed an HMA of the SB, TH1, and TH2 structures. Findings are presented in the November 16, 2015 draft report titled *Hazardous Materials Assessment*, *Pitkas Point School Site Hazmat Survey*, *Pitkas Point*, *Alaska*, which is included as Appendix D. In addition to the November 16, 2016 draft report, EHS provided asbestos sampling results and a brief summary from a previous HMA survey conducted at the SB in July 2011. Potential hazardous materials were identified in each of the three structures surveyed. Those materials include asbestos-containing materials (ACM), lead, polychlorinated bi-phenyls (PCBs), mercury, and radioactive materials. In addition, these materials may be found in other buildings that are present on the subject Property. The key findings are summarized below. Note these are subject to the limitations in the EHS report (Appendix D).

#### 8.1 Asbestos-Containing Materials

Eighteen, 23, and 15 discrete samples were collected from the SB, TH1, and TH2 during the September 2015 HMA, respectively. In addition, 55 discrete samples were collected from the SB in July 2011. The samples were analyzed using polarized light microscopy by Environmental Protection Agency (EPA) Method 600/M4-82-020. The 18 discrete samples collected from SB in September 2015 did not detect ACM. Nine of the samples collected from the SB (July 2011), two of the samples from the TH1 (2015), and two samples from the TH2 (2015) were found to contain asbestos (defined as having over 1 percent asbestos content) and included the following materials:

• Sink undercoating (white) in the SB;

- Sheet vinyl and mastic, SV-2 grey pebble mosaic in the SB;
- Floor tile and mastic, FT1 12x12 white with/ grey streaks in the SB;
- Window glazing, grey in the SB;
- Floor tile and mastic, FT-1 in the SB;
- Stair tread, tan vinyl in the SB;
- Black undercoating for stainless steel sink in the TH1 and TH2; and,
- Grey gummy window glazing compound in the TH1 and TH2.

A comprehensive list of ACM identified in the September 2015 and July 2011 HMAs, along with additional materials that were/are assumed to contain asbestos, is included in the Appendix D report. Tables 1A, 1B, 1C, and 1D of the report contains a summary of the ACMs and their locations in the building.

According to EHS, ACM in the SB, TH1, and TH2, including floor tiles, sheet vinyl, flange gaskets and valve packing, boiler gaskets and sealants, are not considered friable in present condition, but may become friable if damaged. ACM present in the floor tile mastics, stair tread, window glazing, sink undercoating, high temperature wire insulation is classified as non-friable, but are typically in poor condition. The EPA requires that a trained asbestos worker remove all ACM that would be disturbed by the proposed demolition. Additionally, the owner's (or owner's contractor) may need to develop a pre-demolition work plan.

Settled and concealed dusts were examined by EHS's field inspector but analytical sampling of the dust was not conducted. Based on visual inspection and experience from similar buildings, the inspector opined that the settled and concealed dusts likely contain less than 1 percent asbestos and are not ACM.

#### **8.2** Lead-Containing Materials

Forty-six, 15, and 14 discrete sample locations were tested in SB, TH1, and TH2 structures during the September 2015 HMA, respectively for lead-based paint (LBP). In addition, 35 discrete samples were collected from the SB in July 2011. The discrete locations were tested in-place using an x-ray fluorescence (XRF) lead paint analyzer. A lead analysis summary and sampling locations are provided in Appendix D of the EHS report.

EHS did not identify LBP in TH1 and TH2 during the September 2015 HMA. EHS identified LBP (paint containing more than 1.0 mg/cm² of lead) in the SB on painted metal piping in the kitchen and mechanical room. It is anticipated that other metal piping or equipment may be painted with LBP. Concentrations of lead were found in the glazing of ceramic plumbing fixtures, glazing of older ceramic sinks, and hand dryers. However, EHS noted that the concentrations of lead in ceramic glazing compounds should not be compared to LBP criteria, as the glazing is inherently less likely to cause lead to be present in dusts or on surfaces, where it can be ingested. Concentrations of lead were found in plastic components at the SB, such as

"Formica" plastic laminate panels. However, EHS noted the concentrations of lead in plastic compounds should not be compared to lead-based paint criteria. Although EHS concludes that LBP likely does not present a hazard to demolition workers in accordance with safe work practices, Federal and the State of Alaska regulations (29 Code of Federal Regulations [CFR] 1926.62 and 8 Alaska Administrative Code [AAC] Chapter 61) require lead-trained personnel, personal protective procedures, and air monitoring at work sites where employees may be exposed to lead until exposure levels can be verified and site-specific safe work practices are established.

# **8.3** PCB- and Mercury- Containing Materials

A limited visual inspection of light fixture ballasts was conducted by the EHS field inspector to identify PCB ballasts. According to the EHS report, fluorescent light fixtures with PCB-containing ballasts were found in TH2. Only fluorescent light fixtures marked "No PCBs" were found in the SB and TH1. EHS notes that all ballasts, including those associated with high-intensity discharge lights, should be inspected during removal. If they are not marked "No PCBs," either the manufacturer should be contacted to determine the presence of PCBs or it should be assumed the ballasts contain PCBs. If any PCB-materials are discovered, they must be handled in accordance with regulation 40 CFR Part 761 by personnel trained and certified as outlined in regulations 29 CFR 1910.120 and 8 AAC 61.

The only mercury-containing materials identified by the EHS survey are fluorescent lamps, thermostats, and high-intensity discharge (HID) lights in the SB, TH1, and TH2. The HID fixtures on the exterior of the SB were broken. EHS recommends all mercury-containing items removed from the SB be disposed of as hazardous waste or recycled.

#### 8.4 Other Hazardous Materials

Additional hazardous materials including smoke detectors containing radioactive materials, and ozone-depleting refrigerants (air conditioning unit found in the server room in the SB). EHS's field representative assumed that the existing heating system is assumed to contain glycol. EHS recommended that glycol removed from the heating system be removed and properly disposed of or recycled. All construction workers who are required to handle the above materials must be properly trained and certified as required by regulations 29 CFR 1910.120 and 8 AAC 61.

## 8.5 Fungal Growth

EHS's field inspector performed a visual examination of the buildings for suspected fungal growth. TH1 and TH2 were both in disrepair, with strong moldy and musky odors and visible fungal growth on nearly all surfaces and materials interior to the units. EHS was able to access the interior of the TH1 and TH2 with the use of a respirator. The SB was generally in fair condition with visible areas of water damage. Roof leaks in the mechanical room have resulted

in damage to the mechanical room, the kitchen, and an adjacent classroom. Multiple trash cans or buckets were placed in the mechanical room to catch the water but have overflowed. There was also water damage in the gym where daylight was visible through cracks in the gypsum board wall and ceiling. The cracks appear to have been caused by building settling and a lack of exterior siding or other protection. In several areas in the SB, water infiltration has damaged a variety of building components including ceilings, walls, floors, and light fixtures, resulting in suspected fungal growth, although no visible fungal growth was observed.

#### 9.0 STRUCTURAL INTEGRITY ASSESSMENT

On September 16 and 17, 2015, Coffman performed a SIA of the SB, TH1, and TH2 structures. Findings are presented in a November 16, 2015 draft report titled *Pitka's Point School – Structural Integrity Assessment – Draft*, which is included as Appendix E. The overall purpose of the SIA is to determine if the buildings are safe for re-use in their existing condition, can be repaired, and/or should be demolished. The key findings are summarized below, but are subject to the limitations in Appendix E.

#### 9.1 TH1 and TH2 Structures

TH1 and TH2 are one story wood framed buildings with footprints of 24 feet by 38 feet (approximately 912 square feet). The buildings were only observed from the exterior due to the presence of extreme mold growth on the interior. Per EHS's direction, the buildings were not to be entered without the use of a respirator, therefore Coffman's representative was unable to enter the buildings for interior observation. The buildings were only observed from the exterior by Coffman's representative, and based on the interior observations according to EHS, there were no major areas of water damage along the walls, ceiling, or floor. Coffman noted that TH1 and TH2 appear to be structurally sound. Coffman recommended to bring the building up to a livable condition the entire interior of the unit would need to be remediated due to the presence of extreme mold infestation, and re-constructed using new interior architectural finishes. New windows and exterior doors are also recommended.

Coffman recommends that based on the estimated cost of repair, and considering the additional cost of remediation (refer to EHS-Alaska's findings), that TH1 and TH2 be demolished. In the interim period, the buildings should remain condemned from occupation.

#### 9.2 SB Structure

According to Coffman, the SB consists of an original high school building designed and built around 1979-1980; a major addition around 1984, and two smaller additions. During the September 2015 site visit, the building was observed from the exterior and interior. Based on

observation, the building appears to be in good overall structural condition, with a few areas of local damage and settlement.

Based on their visual observations, Coffman concludes the main school building appears to be in good overall structural condition and re-use of the building is an option. However, Coffman recommends deficiencies noted in the Appendix E report be addressed to convert the building for re-purposing. Coffman also recommends the cold storage room be removed/demolished or releveled and strengthened with new piles/girders.

#### 10.0 CONCEPTUAL SITE MODEL

A conceptual site model (CSM) was prepared to identify known and potential exposure pathways at the Property. The CSM was developed in general accordance with the ADEC's *Policy Guidance on Developing Conceptual Site Models* (October 2010), using the ADEC's CSM Human Health Graphic and Scoping Forms. The ADEC forms are included in Appendix F, with discussions of the potential exposure pathways provided below. The narrative includes descriptions of site-specific considerations that increase or decrease the viability of each pathway at this site.

Petroleum hydrocarbon-impacted soil is present on the Property. The contamination is a result of a known diesel spill identified in 2000, as well as probable undocumented and/or incidental spills, leaks, and drips from the former school's heating oil tanks and piping systems.

#### **10.1** Soil – Direct Contact

Direct contact with impacted soil comprises the incidental ingestion and dermal absorption exposure routes. Due to the presence of petroleum hydrocarbon constituents, the direct contact exposure pathway is complete for current and/or future on-site commercial workers, site visitors, trespassers, residents, and construction workers. There is no documentation of compounds that permeate the skin (listed in Appendix B of the ADEC CSM guidance), therefore, the dermal absorption pathway is incomplete. All present soil concentrations are below ingestion and direct contact cleanup levels.

#### 10.2 Groundwater

ADEC guidance stipulates that ingestion of groundwater be considered a potentially complete exposure pathway unless a groundwater use determination is conducted in accordance with 18 AAC 75.350, and that determination finds that the groundwater is not "currently of reasonable expected future source of drinking water." Therefore, ingestion of contaminants in groundwater is considered a potentially complete pathway for future on-site commercial workers, site visitors,

trespassers, residents, and construction workers. We have no knowledge of any on-site wells on the Property.

#### 10.3 Air

Volatile contaminants of concern (COCs) have the potential to impact receptors through outdoor and indoor air inhalation. Volatile COCs including DRO, GRO, RRO, benzene, ethylbenzene, toluene, and total xylenes have been documented in the site surface soil. Due to these compounds, coupled with the presence of ACM in TH1, TH2, and SB, and the presence of visible fungal growth in TH1 and TH2, indoor air inhalation is considered a potentially complete exposure pathway. Inhalation of both outdoor air and indoor air are considered potentially complete pathways for current and/or future residents, commercial workers, site visitors, trespassers, and construction workers. Note that the building are elevated above the ground surface. Based on the construction of the buildings, the exposure pathway for inhalation of indoor air is likely mitigated based on the airflow between the building and ground surface. All present soil concentrations are below outdoor air cleanup levels and vapor intrusion is typically not considered an unacceptable risk for petroleum hydrocarbons if DRO is the only COC present at concentrations greater than ADEC MTG levels.

#### 10.4 Surface Water

The former school's drinking water source is from a surface water source (pond), located on the southeastern corner of the Property (Figure 2). In addition, the Property is located adjacent to the Yukon River, approximately 200 feet south. While no surface water analytical samples were collected, ingestion of contaminants in surface water is considered a potentially complete exposure pathway for current and/or future residents, commercial workers, site visitors, trespassers, construction workers, and ecological receptors.

#### **10.5** Other

Other impacted media, including biota, were not identified at the site.

#### 10.6 CSM Summary

Currently complete or potentially complete exposure pathways have been identified at the site. Based on exposure scenarios and COC concentrations, the migration to surface water, possibly direct contact, and outdoor air and indoor air inhalation due to mold and ACM exposure pathways likely are the primary risk drivers. It is also recognized that changes in the site use or other site conditions may affect the viability of potential exposure pathways. In particular, the CSM will need to be re-evaluated and revised as necessary if new buildings are constructed at the site or if a change in land use occurs.

#### 11.0 ROM COSTS

#### 11.1 Hazardous Materials Abatement ROM Cost Summary

EHS prepared a ROM cost to remove and dispose of the hazardous building materials from TH1, TH2, and the SB of \$304,413 (Appendix D) combined for all three units. EHS noted that replacement costs are not included, only abatement of hazards. Further assumptions included in the cost estimate are included in the Appendix D report.

EHS also noted that TH1 and TH2 are in disrepair and should not be entered by unprotected workers. EHS observed extensive fungal growth within TH1 and TH2 caused by various forms of water intrusion noted in the HMA. Due to the extensive fungal growth EHS proposed two options for the TH:

- 1. Demolish the unit(s); or
- 2. Renovate the unit(s) by removing all existing equipment, finishes, plywood subfloor, plywood ceiling, roofing, etc.

EHS noted that the SB is generally in fair condition with only a few areas of water damage and a few areas of damaged ACMs noted. EHS recommended that, prior to building re-occupancy, the following minimum actions should be addressed:

- Repair sources of water intrusion from various locations on the roof, exterior siding, and leaking piping; and,
- Abate damaged asbestos-containing materials.

#### 11.2 Structural Repair ROM Cost Summary

Coffman prepared ROM costs to structurally repair TH1 and TH2 which are estimated to be approximately \$267,000 for each building including a 25 percent contingency. However, Coffman recommended that based on the estimated cost of repair, and additional cost of remediation/abatement (refer to EHS's findings), that TH1 and TH2 be demolished. Coffman estimated the repair ROM cost for the SB to be approximately \$773,000. Coffman noted in the Appendix E report that the SB cost estimate includes a 50 percent contingency based on unknown conditions that may have not been observed during the September 2015 SIA. Coffman recommended that based on their visual observations, the SB appears to be in good overall structural condition and suitable for re-use. Additional recommendations for the building repairs are included in Appendix E.

#### 11.3 Soil Remediation ROM Cost

We did not provide costs for soil remediation, due to the continued data gaps regarding delineation of impacted soil, and uncertainties in intended future use. These considerations drive

the level of mitigation that may be required to protect human health or the environment, and therefore dictate the cost of remedial action, if any.

#### 12.0 CONCLUSIONS

Our conclusions and recommendations based on the 2015 assessment activities are presented below.

#### 12.1 Site Assessment/Characterization

Shannon and Wilson's site assessment activities conducted at the Property consisted of advancing and sampling test pits, visually assessing the former school tank farm, and attempting to locate and sample the soil stockpiles and super-sacks. The current and historical site characterization data were used to continue to delineate soil contamination at the Property.

Seven soil samples collected from test pits in the PPS10 and PPS12 areas contained DRO concentrations greater than ADEC Method 2 MTG cleanup levels but less than human health cleanup levels. The lateral and vertical extent of DRO-impacted soil at these locations is not known. The soil samples collected from the PPS1/PPS11 and PPS13 areas did not contain concentrations of target analytes above the most stringent ADEC Method 2 cleanup levels. In addition to these areas, soil impacted with DRO concentrations greater than the most stringent ADEC cleanup level for MTG was identified in sample locations TF2, AST4, AST9, and AST10. The lateral and vertical extent of DRO-impacted soil at these locations is not known.

Horizontal and vertical tanks, 55-gallon drums, and various piping were observed within the former school tank farm bermed containment area. The former school aboveground dual storage tanks were removed from the tank farm area prior to our site assessment activities. The liner appeared to be mostly intact (small tears were noted in various locations) and functioning to contain water inside the secondary containment area. A sheen was observed on the surface water near the southeast corner of the containment area.

The stockpiled soil and supersacks generated during the 2000 and 2004 site assessment activities were not located during the 2015 site assessment.

#### 12.2 HMA

On September 16 and 17, 2015, EHS performed a HMA of the SB, TH1, and TH2. Multiple hazardous building materials including ACM, LBP, PCB- and mercury-containing materials, radioactive materials, and ozone-depleting refrigerants, glycol, and fungal growths were identified in one or more of the structures. In addition, these materials may be found in other buildings that are present on the subject Property. These materials will require special handling practices prior to building repair and/or during demolition.

#### 12.3 SIA

On September 16 and 17, 2015, Coffman performed a SIA of the SB, TH1, and TH2 to determine if the structures could be used as residential buildings in their current state. According to Coffman, based on the estimated cost of repair, and additional cost of remediation (refer to HMA), it is recommend that TH1 and TH2 be demolished. In the interim period, the buildings should remain condemned from occupation. The SB appears to be in comparatively good overall structural condition and re-use of the building. However, it is recommended that deficiencies noted in the SIA be addressed to convert the building re-purposing. In addition, these repairs may be needed in other buildings that are present on the subject Property.

### 12.4 Data Gaps

Based on current and historical data, the following data gaps may require additional investigation to evaluate the lateral and vertical extent of DRO-impacted soil:

- The PPS10 Area, southeast and northwest of the SB and CW (partially demolished), respectively;
- The PPS12 Area, northeast of the FH;
- Southeast of the former school tank farm bermed containment area; and,
- Near or beneath AST4, AST9, and AST10.

The vertical extent of DRO-impacted soil was not included in the assessment. The nearby surface drinking water source was not included in the assessment in order to determine if the surface water has been impacted by the petroleum releases.

When the impacted areas are delineated and data gaps addressed, the Property may be eligible for Cleanup Complete with Institutional Controls status.

#### 13.0 CLOSURE/LIMITATIONS

This report was prepared for the exclusive use of our client and their representatives in the study of this site. The findings we have presented within this report are based on the limited sampling and analyses that we conducted. They should not be construed as definite conclusions regarding the site's soil quality, and it is possible that our soil tests missed higher levels of petroleum hydrocarbon constituents. As a result, the analysis and sampling performed can only provide you with our professional judgment as to the environmental characteristics of this site, and in no way guarantees that an agency or its staff will reach the same conclusions as Shannon & Wilson. The data presented in this report should be considered representative of the time of our site assessment. Changes in site conditions can occur over time, due to natural forces or human activity. In addition, changes in government codes, regulations, or laws may occur. Because of such changes beyond our control, our observations and interpretations may need to be revised.

You are advised that various state and federal agencies (ADEC, EPA, etc.) may require the reporting of this information. Shannon & Wilson does not assume the responsibility for reporting these findings and therefore will not disclose the results of this study, except with your permission or as required by law.

Shannon & Wilson has prepared the attachment in Appendix G "Important Information About Your Geotechnical/Environmental Report" to assist you and others in understanding the use and limitations of our report.

Copies of documents that may be relied upon by our client are limited to the printed copies (also known as hard copies) that are signed or sealed by Shannon & Wilson with a wet, blue ink signature. Files provided in electronic media format are furnished solely for the convenience of the client. Any conclusion or information obtained or derived from such electronic files shall be at the user's sole risk. If there is a discrepancy between the electronic files and the hard copies, or you question the authenticity of the report please contact the undersigned.

We appreciate this opportunity to be of service and your continued confidence in our firm. If you have questions or comments concerning this report, please call the undersigned at (907) 561-2120.

Sincerely,

SHANNON & WILSON, INC.

Prepared by:

Trevor Crosby

**Environmental Scientist** 

Approved by:

Matthew S. Hemry, P.E. Vice President

	ъ.	Sample Location	Depth	Headspace	g 15 14
Sample Number^^	Date	(See Figures 2 through 7)	(feet**)	( <b>ppm</b> ) ^	Sample Description
Former RSE Sample P	PPS1/PPS11	<u>Area</u>			
PPS1/PPS11-A	9/16/2015	As close as practicable to RSE Sample PPS1/PPS11	0.5	2.0	Light to dark brown, Silt with organics; moist
* PPS1/PPS11-B	9/16/2015	As close as practicable to RSE Sample PPS1/PPS11	1.0	2.1	Dark brown, Peat trace silt; moist
PPS1/PPS11-C	9/16/2015	As close as practicable to RSE Sample PPS1/PPS11	1.5	2.0	Dark brown, Peat trace silt; moist
PPS1/PPS11-D	9/16/2015	As close as practicable to RSE Sample PPS1/PPS11	2.0	1.6	Brown, Silt with organics; moist
PPS1/PPS11-1-A	9/16/2015	Approximately 10 feet northeast of PPS1/PPS11	0.5	1.6	Brown, Silt with organics; moist
PPS1/PPS11-1-B	9/16/2015	Approximately 10 feet northeast of PPS1/PPS11	1.0		Brown, Silt with organics; moist
PPS1/PPS11-1-C	9/16/2015	Approximately 10 feet northeast of PPS1/PPS11	1.5	1.3	Brown, Silt with organics; moist
PPS1/PPS11-1-D	9/16/2015	Approximately 10 feet northeast of PPS1/PPS11	2.0	1.5	Brown, Silt with organics; moist
PPS1/PPS11-2-A	9/16/2015	Approximately 6 feet east of PPS1/PPS11	0.5	1.5	Dark brown, Peat with silt; moist
PPS1/PPS11-2-B	9/16/2015	Approximately 6 feet east of PPS1/PPS11	1.0	2.2	Brown, Silt with organics; moist
PPS1/PPS11-2-C	9/16/2015	Approximately 6 feet east of PPS1/PPS11	1.5	2.5	Brown, Silt with organics; moist
PPS1/PPS11-2-D	9/16/2015	Approximately 6 feet east of PPS1/PPS11	2.0	2.8	Brown, Silt with organics; moist
* PPS1/PPS11-3-A	9/16/2015	Approximately 9 feet northwest of PPS1/PPS11	0.5	4.6	Brown, Silt with organics; moist
PPS1/PPS11-3-B	9/16/2015	Approximately 9 feet northwest of PPS1/PPS11	1.0		Brown, Silt with organics; moist
PPS1/PPS11-3-C	9/16/2015	Approximately 9 feet northwest of PPS1/PPS11	1.5	2.9	Brown, Silt with organics; moist
PPS1/PPS11-3-D	9/16/2015	Approximately 9 feet northwest of PPS1/PPS11	2.0	2.5	Brown, Silt with organics; moist

- \* = Sample analyzed by the project laboratory (See Table 2 and Appendix C)
- \*\* = Feet below ground surface
- ^ = Field screening instrument was a Thermo Environmental Instruments 580B photoionization detector (PID)
- = Measurement not recorded or not applicable
- ppm = Parts per million
- ^^ = Sample numbers preceded by "17747-" on the chain-of-custody
- RSE = Restoration Science and Engineering

Commis Number A	Date	Sample Location (See Figures 2 through 7)	Depth (feet**)	Headspace (ppm) ^	Sample Description
Sample Number^^	Date	(See Figures 2 tinough 7)	(leet ···)	(ppin)	Sample Description
Former RSE Sample F	PS10 Area				
PPS10-A	9/15/2015	As close as practicable to RSE Sample PPS10	0.5	1.0	Dark brown, Peat with silt and gravel; moist
PPS10-B	9/15/2015	As close as practicable to RSE Sample PPS10	1.0	1.5	Dark brown, Peat with silt and gravel; moist
PPS10-C	9/15/2015	As close as practicable to RSE Sample PPS10	1.5	2.3	Dark brown, Peat with silt and gravel; moist
* PPS10-D	9/15/2015	As close as practicable to RSE Sample PPS10	2.0	170	Brown to gray, Silt with organics; moist; hydrocarbon odor
PPS10-1-A		Approximately 8.5 feet north of PPS10	0.5	3.1	Dark brown, Peat with silt; moist; organic odor
* PPS10-1-B	9/16/2015	Approximately 8.5 feet north of PPS10	1.0	24	Dark brown, Peat with silt; moist; organic odor
PPS10-1-C	9/16/2015	Approximately 8.5 feet north of PPS10	1.5	10	Dark brown, Peat with silt and sand; moist
PPS10-1-D	9/16/2015	Approximately 8.5 feet north of PPS10	2.0	12	Dark brown to gray, Silt with organics; moist
PPS10-2-A	9/16/2015	Approximately 9 feet east of PPS10	0.5	2.4	Dark brown, Peat with silt; moist
PPS10-2-B	9/16/2015	Approximately 9 feet east of PPS10	1.0	1.9	Dark brown, Peat with silt; moist
PPS10-2-C	9/16/2015	Approximately 9 feet east of PPS10	1.5	8.1	Dark brown, Peat with silt; moist
* PPS10-2-D	9/16/2015	Approximately 9 feet east of PPS10	2.0	160	Brown, Silt with organics; moist; hydrocarbon odor
PPS10-3-A	9/16/2015	Approximately 7 feet southwest of PPS10	0.5	12	Brown to light brown, Silt with organics; moist
PPS10-3-B	9/16/2015	Approximately 7 feet southwest of PPS10	1.0	5.0	Brown to light brown, Silt with organics; moist
PPS10-3-C	9/16/2015	Approximately 7 feet southwest of PPS10	1.5	200	Brown to light brown, Silt with organics; moist; hydrocarbon odor
* PPS10-3-D	9/16/2015	Approximately 7 feet southwest of PPS10	2.0	260	Brown to light brown, Silt with organics; moist; hydrocarbon odor
* PPS10-3-DX	9/16/2015	Duplicate of Sample PPS10-3-D	2.0	260	Brown to light brown, Silt with organics; moist; hydrocarbon odor
PPS10-4-A	9/16/2015	Approximately 6 feet west of PPS10	0.5	3.9	Light brown, Silt with organics; moist
* PPS10-4-B	9/16/2015	Approximately 6 feet west of PPS10	1.0	5.3	Light brown, Silt with organics; moist
PPS10-4-C	9/16/2015	Approximately 6 feet west of PPS10	1.5	2.8	Light brown, Silt with organics; moist
PPS10-4-D	9/16/2015	Approximately 6 feet west of PPS10	2.0	4.2	Light brown, Silt; moist

- \* = Sample analyzed by the project laboratory (See Table 2 and Appendix C)
- \*\* = Feet below ground surface
- ^ = Field screening instrument was a Thermo Environmental Instruments 580B photoionization detector (PID)
- = Measurement not recorded or not applicable
- ppm = Parts per million
- ^^ = Sample numbers preceded by "17747-" on the chain-of-custody
- RSE = Restoration Science and Engineering

Sample Number^^	Date	Sample Location (See Figures 2 through 7)	Depth (feet**)	Headspace (ppm) ^	Sample Description
Former RSE Sample P	PS12 Area		,		<u> </u>
PPS12-A		As close as practicable to RSE Sample PPS12	0.5	1.8	Brown, Silt with sand and organics; moist
PPS12-B	9/16/2015	As close as practicable to RSE Sample PPS12	1.0		Dark brown, <i>Peat</i> ; moist
* PPS12-C	9/16/2015	As close as practicable to RSE Sample PPS12	1.5	1.9	Dark brown, Peat; moist
PPS12-D	9/16/2015	As close as practicable to RSE Sample PPS12	2.0	1.9	Brown, Silt with organics; 3/4-inch rounded gravels; moist
PPS12-1-A	9/16/2015	Approximately 11 feet northeast of PPS12	0.5	1.8	Brown, Silt with organics; 1/2 to 3/4-inch rounded gravels; moist
PPS12-1-B	9/16/2015	Approximately 11 feet northeast of PPS12	1.0	2.6	Brown, Silt with organics; 1/2 to 3/4-inch rounded gravels; moist
PPS12-1-C	9/16/2015	Approximately 11 feet northeast of PPS12	1.5	3.2	Brown, Peat with silt; moist
PPS12-1-D	9/16/2015	Approximately 11 feet northeast of PPS12	2.0	2.6	Brown, Peat with silt; moist
* PPS12-2-A	9/16/2015	Approximately 8 feet southeast of PPS12	0.5	4.9	Brown, Silt with organics; 1/2-inch rounded gravels; moist
PPS12-2-B	9/16/2015	Approximately 8 feet southeast of PPS12	1.0	3.8	Brown, Silt with organics; 1/2-inch rounded gravels; moist
PPS12-2-C	9/16/2015	Approximately 8 feet southeast of PPS12	1.5	2.8	Brown, Silt with Sand; moist
PPS12-2-D	9/16/2015	Approximately 8 feet southeast of PPS12	2.0	2.2	Brown, Silt with Sand; moist
PPS12-3-A	9/16/2015	Approximately 9 feet southwest of PPS12	0.5	2.3	Dark brown, Peat with silt; moist
PPS12-3-B	9/16/2015	Approximately 9 feet southwest of PPS12	1.0	5.7	Dark brown, Peat with silt and sand; moist; hydrocarbon odor
* PPS12-3-C	9/16/2015	Approximately 9 feet southwest of PPS12	1.5	270	Dark brown, Peat with silt and sand; moist; hydrocarbon odor
* PPS12-3-CX	9/16/2015	Duplicate of Sample PPS12-3-C	1.5	270	Dark brown, Peat with silt and sand; moist; hydrocarbon odor
PPS12-3-D	9/16/2015	Approximately 9 feet southwest of PPS12	2.0	54	Dark brown, Peat; moist; hydrocarbon odor
PPS12-4-A	9/16/2015	Approximately 9 feet northwest of PPS12	0.5	3.5	Brown, Peat with silt; moist
PPS12-4-B	9/16/2015	Approximately 9 feet northwest of PPS12	1.0	1.3	Brown, Peat with silt; moist
PPS12-4-C	9/16/2015	Approximately 9 feet northwest of PPS12	1.5	1.8	Brown, Silt with organics; moist
PPS12-4-D	9/16/2015	Approximately 9 feet northwest of PPS12	2.0	2.4	Brown, Silt with organics; moist

- \* = Sample analyzed by the project laboratory (See Table 2 and Appendix C)
- \*\* = Feet below ground surface
- ^ = Field screening instrument was a Thermo Environmental Instruments 580B photoionization detector (PID)
- = Measurement not recorded or not applicable
- ppm = Parts per million
- ^^ = Sample numbers preceded by "17747-" on the chain-of-custody
- RSE = Restoration Science and Engineering

Sample Number^^	Date	Sample Location (See Figures 2 through 7)		Headspace (ppm) ^	Sample Description
Former RSE Sample PPS13 Area					
PPS13-A	9/16/2015	As close as practicable to RSE Sample PPS13	0.5	2.0	Dark brown, Peat; moist
PPS13-B	9/16/2015	As close as practicable to RSE Sample PPS13	1.0	1.6	Brown, Peat with silt; moist
* PPS13-C	9/16/2015	As close as practicable to RSE Sample PPS13	1.5	2.7	Brown, Silt with peat; moist
PPS13-D	9/16/2015	As close as practicable to RSE Sample PPS13	2.0	1.5	Brown, Silt with peat; moist
* PPS13-1-A	9/16/2015	Approximately 25 feet northeast of PPS13	0.5	3.8	Brown, Silt with gravel and organics; 3/4 to 1.5-inch gravels; moist
PPS13-1-B	9/16/2015	Approximately 25 feet northeast of PPS13	1.0	2.0	Brown, Silt with gravel and organics; 3/4 to 1-inch gravels; moist
PPS13-1-C	9/16/2015	Approximately 25 feet northeast of PPS13	1.5	2.4	Brown, Silt with gravel and organics; 3/4 to 1-inch gravels; moist
PPS13-2-A	9/16/2015	Approximately 24 feet east of PPS13	0.5	4.2	Brown, Silt with gravel and organics; 3/4 to 1-inch gravels; moist
* PPS13-2-B	9/16/2015	Approximately 24 feet east of PPS13	1.0	8.1	Brown, Silt with organics and gravel; moist; hydrocarbon odor
PPS13-3-A	9/16/2015	Approximately 20 feet southeast of PPS13	0.5	1.6	Brown, Silt with organics and gravel; moist
PPS13-3-B	9/16/2015	Approximately 20 feet southeast of PPS13	1.0	1.9	Brown, Silt with organics and gravel; moist
PPS13-3-C	9/16/2015	Approximately 20 feet southeast of PPS13	1.5	1.3	Brown, Silt with organics and gravel; moist

- \* = Sample analyzed by the project laboratory (See Table 2 and Appendix C)
- \*\* = Feet below ground surface
- ^ = Field screening instrument was a Thermo Environmental Instruments 580B photoionization detector (PID)
- = Measurement not recorded or not applicable
- ppm = Parts per million
- ^^ = Sample numbers preceded by "17747-" on the chain-of-custody
- RSE = Restoration Science and Engineering

Sample Number^^	Date	Sample Location (See Figures 2 through 7)	Depth (feet**)	Headspace (ppm) ^	Sample Description
Debris Inventory and			(===== )	41	s marpe 2 total process
* TF1		Downgradient of the southeast corner of the existing tank farm	0.8	3.8	Dark brown, Peat with silt; moist
* TF2		Downgradient of the middle portion of the existing tank farm	0.9		Dark brown, <i>Peat with silt</i> ; moist
AST2		Beneath fill valve	0.7	1.4	Dark brown, Organics with silt and gravel; moist
* AST4	9/17/2015	Beneath 90 degree joints of 3 pipes adjacent to the AST	0.6	110	Brown to gray; Silt with organics and gravel, moist; hydrocarbon odor
* AST4X		Duplicate of Sample AST4	0.6	110	Brown to gray; Silt with organics and gravel, moist; hydrocarbon odor
* AST8	9/17/2015	Adjacent to an AST northeast of Teacher Housing Building 1	1.0	17	Brown to gray; Silt with organics and gravel, moist; hydrocarbon odor
* AST9	9/17/2015	Adjacent to an AST northeast of Teacher Housing Building 2	0.7	95	Brown, Silt with organics; wet; hydrocarbon odor
AST5	9/17/2015	Adjacent to an AST north of the School Complex	0.5	4.4	Brown, Silt with gravel; wet
* AST10	9/17/2015	Adjacent to an AST west of the Former Teacher Housing	0.7	6.2	Brown, Organics with silt; moist
AST11	9/17/2015	Adjacent to an AST west of the Former Teacher Housing	1.0	3.1	Gray, Gravel with sand and organics; wet
AST7	9/17/2015	Adjacent to an AST east of the Former School Shop Building	0.4	1.7	Brown, Organics with silt and gravel; moist
DR1	9/18/2015	Near a 55-gallon drum in the northwest corner of the property	0.4	0.8	Dark brown, Peat; moist
DR2	9/18/2015	Near a 55-gallon drum in the northwest corner of the property	0.7	1.0	Dark brown, Peat; moist
PR1	9/18/2015	Beneath a flex coupler near the northwest corner of the property	0.6	0.8	Brown, Organics with silt; moist
PR2	9/18/2015	East of the Old School Building near the middle of the property	1.0	0.9	Brown, Organics with silt; moist
* PR3	9/18/2015	East of the Generator Building near the eastern edge of the proper	0.8	1.2	Gray; Sand; moist
Quality Control					
* TB1	9/17/2015	Trip Blank	-	_	Ottawa sand with methanol added in the laboratory
* TB2	9/18/2015	•	-		Ottawa sand with methanol added in the laboratory

- = Sample analyzed by the project laboratory (See Table 2 and Appendix C)
- = Feet below ground surface \*\*
- = Field screening instrument was a Thermo Environmental Instruments 580B photoionization detector (PID)
- = Measurement not recorded or not applicable
- = Parts per million ppm
- = Sample numbers preceded by "17747-" on the chain-of-custody = Restoration Science and Engineering
- RSE

TABLE 2 SUMMARY OF ANALYTICAL RESULTS

			Sample ID Number^ and Collection Depth in Feet bgs (See Table 1 and Figures 3 and 4)						
					Impac	ted Soil Deline	ation		
		Cleanup Level	PPS1/PPS11-B	PPS1/PPS11-3-A	PPS10-D	PPS10-1-B	PPS10-2-D	PPS10-3-D	PPS10-3-DX~
Parameter Tested	Method*	(mg/kg)**	1.0	0.5	2.0	1.0	2.0	2.0	2.0
PID Headspace Reading - ppm	580B OVM	-	2.1	4.6	170	24	160	260	260
Gasoline Range Organics (GRO) - mg/kg	AK 101	300	<4.94 B	<3.85 B	64.3 J+	<5.93 B	<4.53 B	20.5 J+	10.2 J+B
Diesel Range Organics (DRO) - mg/kg	AK 102	250	50.6	11.4 J	9,430	1,800	2,500	888	1,180
DRO Silica Gel (non-polar) - mg/kg	AK 102	250	-	-	-	-	-	795	1,100
Residual Range Organics (RRO) - mg/kg	AK 103	10,000	316	123	61.1	1,560	110	63.7	35.9 J
RRO Silica Gel (non-polar) - mg/kg	AK 103	10,000	-	-	-	-	-	30.3 J	35.4 J
Aromatic Volatile Organics (BTEX)									
Benzene - mg/kg	EPA 8021B	0.025	< 0.0124	< 0.00965	< 0.00800	< 0.0149	< 0.00850	< 0.00665	< 0.00585
Toluene - mg/kg	EPA 8021B	6.5	< 0.0247	<0.0385 B	0.255	< 0.0296	< 0.0171	< 0.0133	< 0.0118
Ethylbenzene - mg/kg	EPA 8021B	6.9	0.0237 J	< 0.0193	0.117	< 0.0296	< 0.0171	0.0536	0.0277
Xylenes - mg/kg	EPA 8021B	63	0.0326 J	0.0258 J	5.55	0.122 J	0.0900	0.643	0.314

= See Appendix C for compounds tested, methods, and laboratory reporting limits.

\*\* = Soil cleanup level is the most stringent Method 2 standard listed in Table B1 or B2, 18 AAC 75, for the "under 40-inch (precipitation) zone" (June 2015)

= Sample ID No. preceded by "17747-" on the chain-of-custody form

ppm = Parts per million

mg/kg = Milligrams per kilogram
bgs = Below ground surface
- Not tested or not applicable

< 4.94 = Analyte not detected; laboratory reporting limit is 4.94 mg/kg

**50.6** = Analyte detected at a concentration less than the applicable ADEC cleanup level

9,430 = Analyte detected at a concentration above the applicable ADEC cleanup level

B = Reported concentration potentially affected by method blank detection. See ADEC Laboratory Data Review Checklist (LDRC) in Appendix C for details.

J = Estimated concentration less than the limit of quantitation. See the SGS laboratory report in Appendix C for more details.

 $\label{eq:J+} J+ \qquad = Analytical \ result \ is \ potentially \ biased \ high. \ \ See \ ADEC \ LDRC \ in \ Appendix \ C \ for \ details.$ 

TABLE 2 SUMMARY OF ANALYTICAL RESULTS

			Sample ID Number^ and Collection Depth in Feet bgs (See Table 1 and Figures 4 and 5)					
				]	Impacted Soil	Delineation		
		Cleanup Level	PPS10-4-B	PPS12-C	PPS12-2-A	PPS12-3-C	PPS12-3-CX~	PPS13-C
Parameter Tested	Method*	(mg/kg)**	1.0	1.5	0.5	1.0	1.0	1.5
PID Headspace Reading - ppm	580B OVM	-	5.3	1.9	4.9	270	270	2.7
Gasoline Range Organics (GRO) - mg/kg	AK 101	300	<3.38 B	<4.46 B	<3.79 B	<2.27	<4.20 B	<2.36
Diesel Range Organics (DRO) - mg/kg	AK 102	250	<11.9	27.1	19.0 J	317 J-	510	27.3 J
DRO Silica Gel (non-polar) - mg/kg	AK 102	250	-	-	-	155 J-	301	18.7 J
Residual Range Organics (RRO) - mg/kg	AK 103	10,000	64.5	230	155	488 J-	631	232
RRO Silica Gel (non-polar) - mg/kg	AK 103	10,000	-	-	-	86.5 J-	167	81.7
Aromatic Volatile Organics (BTEX)								
Benzene - mg/kg	EPA 8021B	0.025	< 0.00845	< 0.0112	< 0.00950	< 0.0114	< 0.0105	< 0.0118
Toluene - mg/kg	EPA 8021B	6.5	< 0.0169	< 0.0223	< 0.0189	< 0.0226	< 0.0210	< 0.0236
Ethylbenzene - mg/kg	EPA 8021B	6.9	< 0.0169	< 0.0223	< 0.0189	< 0.0226	< 0.0210	< 0.0236
Xylenes - mg/kg	EPA 8021B	63	< 0.0507	< 0.0669	< 0.0569	< 0.0679	< 0.0630	< 0.0706

- \* = See Appendix C for compounds tested, methods, and laboratory reporting limits.
- \*\* = Soil cleanup level is the most stringent Method 2 standard listed in Table B1 or B2, 18 AAC 75, for the "under 40-inch (precipitation) zone" (June 2015)
- ^ = Sample ID No. preceded by "17747-" on the chain-of-custody form

ppm = Parts per million

mg/kg = Milligrams per kilogram bgs = Below ground surface

= Duplicate of preceding sample
 = Not tested or not applicable

< 0.00585 = Analyte not detected; laboratory reporting limit is 0.00585 mg/kg

10.2 = Analyte detected at a concentration less than the applicable ADEC cleanup level = Analyte detected at a concentration above the applicable ADEC cleanup level

B = Reported concentration potentially affected by method blank detection. See ADEC Laboratory Data Review Checklist (LDRC) in Appendix C for details.

J = Estimated concentration less than the limit of quantitation. See the SGS laboratory report in Appendix C for more details.

J- = Analytical result is potentially biased low due to hold time exceedance. See ADEC LDRC in Appendix C for details.

J+ = Analytical result is potentially biased high. See ADEC LDRC in Appendix C for details.

TABLE 2 SUMMARY OF ANALYTICAL RESULTS

			Sample ID Number^ and Collection Depth in Feet bgs (See Table 1 and Figures 6 and 7)					
			Impacted So	il Delineation	Debris Inventory and Property-Wide Assessmen			
Parameter Tested	Method*	Cleanup Level (mg/kg)**	PPS13-1-A 0.5	PPS13-2-B 1.0	TF1 0.8	TF2 0.9	AST4 0.6	AST4X~ 0.6
PID Headspace Reading - ppm	580B OVM	-	3.8	8.1	3.8	2.2	110	110
Gasoline Range Organics (GRO) - mg/kg	AK 101	300	<6.15 B	<3.12 B	<6.51 B	<4.57 B	30.6	20.8
Diesel Range Organics (DRO) - mg/kg	AK 102	250	18.7 J	<12.8	19.5 J	849	6,300	6,740
DRO Silica Gel (non-polar) - mg/kg	AK 102	250	-	-	-	-	-	-
Residual Range Organics (RRO) - mg/kg	AK 103	10,000	189	67.8	141	164	3,560 J+	3,630 J+
RRO Silica Gel (non-polar) - mg/kg	AK 103	10,000	-	-	-	-	-	-
Aromatic Volatile Organics (BTEX)								
Benzene - mg/kg	EPA 8021B	0.025	< 0.0154	< 0.00780	< 0.0163	< 0.0114	< 0.0201	< 0.0211
Toluene - mg/kg	EPA 8021B	6.5	< 0.0308	< 0.0156	< 0.0325	< 0.0229	<0.0806 B	< 0.0423
Ethylbenzene - mg/kg	EPA 8021B	6.9	< 0.0308	< 0.0156	< 0.0325	< 0.0229	0.0492 J	< 0.0423
Xylenes - mg/kg	EPA 8021B	63	< 0.0923	< 0.0467	< 0.0975	< 0.0687	1.21	0.378 B

- \* = See Appendix C for compounds tested, methods, and laboratory reporting limits.
- \*\* = Soil cleanup level is the most stringent Method 2 standard listed in Table B1 or B2, 18 AAC 75, for the "under 40-inch (precipitation) zone" (June 2015)
- ^ = Sample ID No. preceded by "17747-" on the chain-of-custody form

ppm = Parts per million

mg/kg = Milligrams per kilogram bgs = Below ground surface

= Duplicate of preceding sample
 = Not tested or not applicable

<2.36 = Analyte not detected; laboratory reporting limit is 2.36 mg/kg

27.3 = Analyte detected at a concentration less than the applicable ADEC cleanup level

B = Reported concentration potentially affected by method blank detection. See ADEC Laboratory Data Review Checklist (LDRC) in Appendix C for details.

**849** = Analyte detected at a concentration above the applicable ADEC cleanup level

J = Estimated concentration less than the limit of quantitation. See the SGS laboratory report in Appendix C for more details.

J+ = Analytical result is potentially biased high. See ADEC LDRC in Appendix C for details.

TABLE 2 SUMMARY OF ANALYTICAL RESULTS

			Sample ID Number^ and Collection Depth in Feet bgs (See Table 1 and Figure 7)						
			Debris Inv	entory and Prope	rty-Wide Ass	essment	Trip I	Trip Blanks	
		Cleanup Level	AST8	AST9	AST10	PR3	TB1	TB2	
Parameter Tested	Method*	(mg/kg)**	1.0	0.7	0.7	0.8	-	-	
PID Headspace Reading - ppm	580B OVM	-	17	95	6.2	1.2	-	-	
Gasoline Range Organics (GRO) - mg/kg	AK 101	300	<6.30 B	<4.45 B	<6.98 B	<1.59	<1.25	<1.25	
Diesel Range Organics (DRO) - mg/kg	AK 102	250	126	5,330	288	<12.2	-	-	
Residual Range Organics (RRO) - mg/kg	AK 103	10,000	507	248	1,180	57.2	-	-	
Aromatic Volatile Organics (BTEX)									
Benzene - mg/kg	EPA 8021B	0.025	< 0.0158	< 0.0112	< 0.0174	< 0.00795	< 0.00630	< 0.00625	
Toluene - mg/kg	EPA 8021B	6.5	< 0.0315	< 0.0223	< 0.0349	< 0.0159	<0.0251 B	< 0.0126	
Ethylbenzene - mg/kg	EPA 8021B	6.9	< 0.0315	< 0.0223	< 0.0349	< 0.0159	< 0.0126	< 0.0126	
Xylenes - mg/kg	EPA 8021B	63	< 0.0945	< 0.0668	< 0.105	< 0.0476	<0.0629 B	< 0.0377	

\* = See Appendix C for compounds tested, methods, and laboratory reporting limits.

\*\* = Soil cleanup level is the most stringent Method 2 standard listed in Table B1 or B2, 18 AAC 75, for the "under 40-inch (precipitation) zone" (June 2015)

^ = Sample ID No. preceded by "17747-" on the chain-of-custody form

ppm = Parts per million

mg/kg = Milligrams per kilogram bgs = Below ground surface

- Not tested or not applicable

< 0.0211 = Analyte not detected; laboratory reporting limit is 0.0211 mg/kg

**20.8** = Analyte detected at a concentration less than the applicable ADEC cleanup level


5,330

= Analyte detected at a concentration above the applicable ADEC cleanup level

B = Reported concentration potentially affected by blank detection. See ADEC Laboratory Data Review Checklist (LDRC) in Appendix C for details.

J = Estimated concentration less than the limit of quantitation. See the SGS laboratory report in Appendix C for more details.

J+ = Analytical result is potentially biased high. See ADEC LDRC in Appendix C for details.




APPROXIMATE SCALE IN FEET

SHANNON & WILSON, INC.


Geotechnical & Environmental Consultants


Fig. 1



Sample ID	Depth	GRO, mg/kg	DRO, mg/kg	RRO,	Benzene,	Toluene,	Ethylbenzene, mg/kg	Total Xylenes, mg/kg		LEGEND
PPS1/PPS11-B	(ft), bgs	mg/kg ND	50.6	mg/kg 316	mg/kg ND	mg/kg ND	0.0237 J	0.0326 J		Approximate location of test pit installed by Shannon & Wilson on September 15th-19th, 2015
PPS/PPS11-3-A	0.5	ND	11.4 J	123	ND	ND	ND	0.0258 J		Red = Sample with DRO concentration greater that the most stringent ADEC Method Two cleanup levels
										Green = Sample with DRO concentration less that the most stringent ADEC Method Two cleanup levels
									Approximate Location of	Black = No analytical sample collected at this location
			I	PPS	1/PF	PS11-		PF	Water Supply Line 1/PPS11-1	bgs = below ground surface mg/kg = milligrams per kilogram  ND = analyte not detected (see Table 2 for laboratory reporting limits)  J = Estimated concentration
						-				
										1
						PPS	61/PPS	<del>∫</del> 311-B(	PS1/PPS11-2	
CO	N/IN/I	INII	TV \	۸۱۵۹	SHET	ERI/				
	IVIIVI		mol				`//			
									FIRE HOUSE	
										0 5 10 20
						4				APPROXIMATE SCALE IN FEET
										PITKAS POINT SCHOOL SITE
							`		1	Pitkas Point, Alaska

32-I-17747-001 FIG. 3





_											
	Sample ID	Depth (ft), bgs	GRO, mg/kg	DRO, mg/kg	DRO Sillica Gel, mg/kg	RRO, mg/kg	RRO Sillica Gel, mg/kg	Benzene, mg/kg	Toluene, mg/kg	Ethylbenzene, mg/kg	Total Xylenes, mg/kg
	PPS13-C	1.5	ND	27.3 J	18.7 J	232	81.7	ND	ND	ND	ND
	PPS13-1-A	0.5	ND	18.7 J	-	189	-	ND	ND	ND	ND
	PPS13-2-B	1.0	ND	ND	-	67.8	-	ND	ND	ND	ND



Approximate Location of Water Supply Line



PPS13-2-B

PPS13-C

PPS13-3

#### **LEGEND**

Approximate location of test pit installed by Shannon & Wilson on September 15th-19th, 2015

Red = Sample with DRO concentration greater than the most stringent ADEC Method Two cleanup levels

Green = Sample with DRO concentration less than the most stringent ADEC Method Two cleanup levels

Black = No analytical sample collected at this location


M Approximate location of infiltration gallery

bgs = below ground surface mg/kg = milligrams per kilogram

ND = analyte not detected (See Table 2 for laboratory reporting limits)

= estimated concentration

= Not tested for or not applicable



PITKAS POINT SCHOOL SITE PITKAS POINT, ALASKA


AREA PPSI3 SOIL SAMPLE LOCATIONS

JANUARY 2016

SHANNON & WILSON, INC. Geotechnical & Environmental Consultants

32-I-I7747-00I

FIG. 6



# SHANNON & WILSON, INC.

**APPENDIX A** 

FIELD NOTES

# FIELD ACTIVITIES DAILY LOG

Date	9/15/15
Sheet	
· · · · · · · · · · · · · · · · · · ·	2-1-7747-001
Project Name: Ditkas Point	2 1 1 1 1 7 2 1
Field activity subject:	
Description of daily activities and events:	
0930 Arrive P Anchorage Intl. Airport-check-in al RAYN aleska for flight-	l-ó
St. Marys	
2 13:00 Arrive in St. Marys; collect field gear from RAUN cargo; plu vehicle fr	rom
Matty's car restal (parked at RAUN); excelsion check in @ Androafs	
loyde; stop by Pithas School site for quick observation.	•
15:30 Site Recon @ Pithas school site - Attempted to contact Robert Reed,	LY50.
no answer-off vorcement	
SITE OBSERVATIONS.	,
1) community washeteria- building Lenglished / footing-	naterial
still intect-good for measurement points	
3) hence plator of soil surple larching from PPSI, PPSIO,	POS 17 . PO 13
3) photos of tenk form decemented - if tenks were romoned	
Several tanks still in form-lines placed below tenks: S	
	No
stockpill of Supersacles found in linear tenk farm.	.00
AND THE PROPERTY OF THE PROPER	<u> </u>
	1.66
complex or onsite	
16:20 Contested : Robert Read , LYSD, Him and Flia will plan to be onsite 9/1	41.6
@ 2 pm	
16:50 Advanced Hand dug test pit a approximate Location of PPS-10; Init	0/1
storted Hole of shovel - and completed hole to 2' bys of hengrange-	-(-0
hand arger weekspeet works pretty good in sift organis / silty netained	
collect field sidening samples	
PPS10-015 = 1.0 ppm; PPS10-1.0'=1.5ppm; PPS10-15'= 2.3 ppm	<i>2</i>
	e collected
to key - will collect 916/15)	
= Advanced "trial" test pit in other areas to determine if hand	lauson
is bast method-Appears to be-	
Soil profile - generally top 2" - topsoil, grasses; 2-4" gravel with sound Layer;	4-1.2
organics [ pecty meterial- ; 1.2-20' brown, gray sitt some organics	
Visitors on site: None	
All the second of the second by the second b	
Changes from plans/specifications and other special orders and important decisions:	
None: No Stockpiles or Supersacks located Q the site the tenh form	
hus tennes and linex secondary containment	
Weather conditions:	<u>·</u>
Important telephone calls: Perticily Cloudy, SOPF NONE	
Personnel on site: Timor assig	
Signature: Date: 9/15	115

# FIELD ACTIVITIES DAILY LOG

Date 9/16/15
Sheet / of /
Project No. <u>32-1-/7-74</u> 7
Project Name: Dithas Point
Field activity subject:
Description of daily activities and events:
0815 ARRIVE @ SCHOOL STIE- CAUBRATE DID.
collected Screening Sample in PPSID and PPSI/PPSII area per vorkplan. General
observentions and screening results suggest that PPS10 may have more patentially
inpacted Soils.
11:55 LEFA school site to plu Chris (EHS) and Sear (Giffmon)
13:52 Arrive ansite at EHS and Coffman
1415 GUA (LYSD) arrived onsite - Opened Haber Alussing I , and School Complex.
Teacher Housing unit 2 ( booked) - He will open later today.
#SUPPOSACKS- GUA, Skitch that the superscens sucks and probably harland to the
airport and for shipped somewhere or hould to area (unknow) and spread.
band spread NOT onsite. 4
17:00 Completed Test pits and screening Suple areas- I vill select sample locations this
evening to collect analytical screens 9/17/15
18:15 just site to get the dinner @ the ctom
19:15 Dasite to collect GPS points of text pit; and perform Site not httmorph
18. V. strenged documented AST on-site
20:45 Arrived O Codging-
Penier field notes - Select analytical locations -
* 1930 - Dealth and Stety Note = withing around site to observe AST-
the particular particular and the particular and th
- and punctured my left foot - near pinky two-bled for about 30 secrets;  Stopped; downed wound; and pandaged wound deened wound of
logice and placed antisetic   bridge on for evening I have had
my tetrus shot il 7 yearst - observed neil atta stepping on 4-
it did not appear to be rusty.
If and not appear of the rossy.
Visitors on site: Chas Ottosen (EHS); Sean Lamb (Coffma); Elia (Lyso)
Changes from plans/specifications and other special orders and important decisions:
Glia stated that superspecks may have been transported offsite:
A MARINE MAN AND AND AND AND AND AND AND AND AND A
Weather conditions: Clear - Rain - Hail 500-604
Important telephone calls:
Personnel on site: Travon
Signature: Date: 9/16/15

	: 32-1-17747-001							Location: Aithers Point
ate: 9/16/								Site:
ampler: Tw						-		Sheet Number: 1 of 2
Sample		Sample	Sample	Sample	GPS »	PID		Shoot Italiabol. 4 64 es
Number	Location	Time	Depth (A)	Туре	GPS Reading*	Reading	Soil Classification	
PPS16-A	PPSIU = ESE LOCATION	16:50	0.5	±W.	- 18	1.6	Field screened on 9/11/15 - see field works	Analyses
PP910 - B	1 2 2	16.52	1.0	1		1.5	Theascreened on 9/14/15 - see had notes	
PPS10-C	/	16:54	1.5			2.3		
PP510 - D	<b>↓</b>	16:56	2.0	V		167		N Day on C
PS10-1-A	PPSID-1 = LOCATION (NOMIN)	08:59	0.5	FM	- 19	3.j &	dark brown, Pect w/sitty moits organic odor	* Dev, RRO, GED, BTEX
PS10-1-B	of PPSID	08:59	1.0	1	-	24 D	derk brown, Pect w silt; moist, organic odor	V1000 000 60- 0000
PPS16-1-6	/	09:03	1.5		gje-	10 @	dark bown, Pet ul sitt and Sand, moist	*DRO, RRO, GRO, BTEX
PPS10-1-D	<b>V</b>	09.05	2.0	4	-	12 0	don brown to gray; Silt of organics; moist	
P310-2-A	PPSIO-2 = LOCATION (FIRST)	09:10	0.5	Fm	- 20	2.4 P	dork brown : Pear I Silt, moist	
PS10-2-B	of opero	09:12	1.0		New	1.9	II BUT SIT MOIST	
P510-2-C		09/14	1.5		***	8.1	"same as above"	
P510-2-0	./	09-16	2.0	V		156 P	brown, Silt of organizes moist; hydrocorbon ador	Who are called
PS10-3-A		09:23	0.5	FM	- 21		brown to light brown; Sitt wil organies	oro, reo, Glas Blox
PS10-3-B	of PPSIO	09:24	1.0	1 .	***	5.0 P	"Same as above"	
9510-3-C		09:25	1.5		450		brown to light brown, Sitt workerwich indrocorbon,	
PS10-3-0	Y	09'-26	2.0	1	- alle	255 A	" same as dove" i hydrocarbon odar	*DRU, RRO, GRO, BTEX
0510-4-A	PASIO-4 = LOCATION (WEST)	09.35	05	FM	- 11	39 90	light provai, si Hr ul organics; moint	LOKALKKA LAKA COLOK
P510-4-B	DE 80510	09-36	1.0		- Marie -	5.3 (H)		* DRO, ERO, GRO, BTEX
P510-4-C		69-37	1.5		e 🦸 William	2.8	"some as above"	3K NE 1 1000, 1910, 1810,
PS10-4-D	<b>4</b>	09:38	2.0	4	- water	42 (4)	light brown, Silf, minist	
1851 - A	OPSI / PPSII = PSE LOCATION	10:19	0.5	FM	- 23	2.0		
PPs1 - B		10:10	1.0		-	2.1 D	derk brown; led of trace gilt; moist	* DRO, REO, ARO, BTEX
PS1-C		10:22	1.5		-	2.0 A	"Same as above"	TO DICO, ICED, MICO, BIGX
PPSI-P	Variety of marketing	10:24	2.0	7	-	16 9	brown, Sitt Worganics, moist	
PS1-1-A	PBI-1= Loration (North)		0.5	FM	- 24	1.6 A	" Same as above"	
P51-1-8	of ppsilppsii	10.32	1.8		-	12 0	" Sand as above"	
P51-1-6		10:34	1.5		-	13 A	" Same as about"	
PS1-1-D	V	10:36	2.0	¥		1.5 A	N same as above"	·
PS1-2-A	PPG1-2= LOCAtion (505)	10:48	0.5	Fin .	- 25	15 A		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
P51-2-B	of pertersin	to + 10:50	1.0	1 1	-		brown; Silt Worganics; moist	
P51-2-C		10.43	1.5		•	1.5 本	"save as above"	
P51-2-0	V	10:55	2.0	1	-	2.8 A	"Some as above"	
PS1-3-A	PPSI-3 Wocchion (West)	11:19	0.5	Fin	- 26	4 C A	" Some of chore"	V Den gange
P51-3-B	of pp1/411	11.23	10	4		27 (1)	u sque as objet	* DRO, RROGRO, BTE

Environmental sample


Field duplicate
Field Screening FD FM

ТВ

Trip blank
GPS readings only collected from analytical sample locations

+ Wormed in vehicle

Kield duplicate also collected



J 18694

Deter Alvil	32-1-17747-001							Location: Pitters Point
Date: 9 16 1 Sampler: Two								Site:
								Sheet Number: 2 of 2
Sample	#61 #	Sample	Sample	Sample	GPS	PID		
Number	Location	Time	Depth	Type	GPS Waypoint Reading*	Reading	Soil Classification	A T
PP51-3-C	PPSI-3 LOCATION (WEST)	11:24	1.5	FM	-		brown, Sitt of organics, moist	Analyses
PPS1-3-P	of posilopsii	11:30	2.0	T	100	2.5 4	"Some as above	
PPS12-A	PPS1212 Location	14.16	0.5	FM	- 27	1.8 4		
2PS12-B		14:22	1.0	1	- 17	1.8	de-Klorova, Peat; noist	
PSIZ-C		14-26	1.5		Nin.	1.9 1	"Some as above"	W Non CO. Co. Co.
P512- R	<b>→</b>	14:30	2.0	4	Va.	19 A	brown; Sitt Vorganics; Hu rounded gravels; moist	& DRO, REU, GEO, BTEX
PPS12-1-A	PPSIZ-1 (Location) (North)	14.35	0.5	FM	- 28	1.9 4	brown; silt of organics; 12-3/4" roveled grovel; moist	
19512-1-8	of pps/2	14:37	1.0	1	_ 28	2.6	"Sune as above"	
PPS12-1-6		14:40	1.5		Wo .	32 4	browni Peat ul sitt, maisi	
PPS12-1-D		14:43	2.0	1	900	2.6	" Same as above"	
PS12-2-A	PPS12-2 Location (EAST)	15:00	0.5	Fm	- 29	4.9 4	brown; Silt of organics hororded gravel, wo is	W D0- 222 222 2
PSN-2-B	of pest	15.02	1.0		- 29	3.4	" Save as above"	* DRO, RRO, GRO, BIEX
PS12-2-C		15:06	1.5		-	2.8	brown; Silt with sand; moist	
PS12-2-P		15:10	2.0.	V	war-	2.2	"Same as above"	
PS12-3-A	PPS12-3 LOCATION/COUTY)	15:20	0.5	FM	- 43	23 G	dock brown, Peat w/ silt; majet	
PS12-3-B	of Apsiz	15:23	1.0	No.	- 30	5,7 (	dock brown, lect ut silt ; some sand; moist; hydro	Action and a second
19512-3-4		15:25	1.5		Maga 1	271 4	I sure as about hydrocorbon ador	* Deo, Reo, GRO, BTGX
Ps12-3-D		15:28	2.0	4	Name . · · · ·	54 4	dock brown, leat moist; hydro cerbon odor	A 1/20, 120, 13/69
PPS12-4-A	PPS12-4 LOWTON (WEST)	K:34	0.5	PM	- 31	35 4	brown , Read with Silt, noist	Y 300 Allo Charles
P512-4-B	of 80512	15.36	1.0	1	-	1.3 F	Same as above"	The state of the s
P512-4-C		15:38	1.5		W04-	1.3 4	brown; Silt wl organics; worst	
P512-4-D	<b>4</b> 0 50 00	15.40	2.0	J	weeks-	24 4	1. sque as above"	
P513 - A	PP\$13 LOCATION	16:58	0.5	Fm	- 31	2.0	Ank Diown, Reat, Moist	
PS13-B		17: b1	1.0	1	With	1.C A		
19513 - C		12.63	1.5		fa.	2.7		* DRO, RRO, GRO, BJEX
P813-D	<b>*</b>	7:06	2.0 +	4	gilin.	1.5 (+)	" saw as about"	TORO, KEO, MEO, BIEX
P513-1-10	PDS13-1 LOCATION (NORTH)	17:12	0.5	FM	- 33	3.8	browni silt of gravel larguary; 3/4-1-7" gravely moist	Maria and a second
PS 13-1-B	of PPS13	17:16	1.0		_	2.0 (4	boor, Git, with organic) force 3/4-1", moist	T PRO, RED, CRO, ETC.
PS13-1-C	1	r7:20	1.5	1	-	24 4	" Same as chive"	
PS13-2-A	PP513-2 Location (Rast)	17:30	0.5	PM	- 34	42 @	" Same as above"	
19513-2-18	of 88513	17:35	1.0	4	2 6	81 (4)	brown, Sitt of organies (groves ) hydro carbon odor	N 500 00 000 0
19513 - 3 -A	PPS13-3 LOCETTON (SUITH)	17:37	05	PM		16 Q	"Sake as chose"	* DRO, RRO, GRO, BYEX
19513-3-B	of PP513	17:40	1.6	1	- 55	1.9 (4)		
00513-3-6	<b>V</b>	17 43	1.5	1		1.3 (4)		

\* 19913-1 THROUGH PPS13-3 VERY DIFFICULT DIGGING/ HARD ANDFROND - LARGER CHANGES-MEMSAR DIL

Environmental sample

Field duplicate

FM Field Screening


TB Trip blank

GPS readings only collected from analytical sample locations

permay 12-24; WES 84

# FIELD ACTIVITIES DAILY LOG

Date 9/17/15
Sheet / of /
Project No. <u>32-1-1794</u>
Project Name: Pithas Doint
Field activity subject:
Description of daily activities and events:
08:05 left ledge to heed to Pithas school.
12 20 collocted analytical samples for test pit areas; site wellethrough for
Ast and other debits
12:20 Left site to go to clinic - Addy gode of hoe about short in November 15 covered and noto-tote - don't need short
12:55 Back on site - collected analytical Tank form Songles. 13:05 - ish - offsite to take thris and Seem to alope it. Looked for
any et evidence of (100-13h) superscells. I dod not observe any
at the airport or rearby. Headed back to giver lodge to fill out
inivery form per Tim Lot request. I cannot modify the form or
print the form. It will have to wait until monday,
1925 off site - to losele to lobel Sample yard.
The state of the s
(
BETHERMONE OF SECTION OF THE PROPERTY OF THE P
'
Visitors on site: NA - NOVE
Changes from plans/specifications and other special orders and important decisions:
NONE.
the control of the second of t
Weather conditions: 500F; 37-48°F; Cheer to cloudy; rain (a and off) internity.
mportant telephone calls: 11:00 spoke of him about injury update (advised to
go to clinic)
ersonnel on site: There was y
ignature: Date: 9/17/18



Date: 9/12/19								Location: Pitkes Point
ampler: yw	6		**************************************					Site: —
Sample	Name	Comm1.					7	Sheet Number: /
Number	Location	Sample	Sample	Sample	GPS	PID		·
	Location	Time	Depth	Туре	Reading*	Reading	Soil Classification	A . 1
2242 - 760	South - ortside of bun	13:5	0.8	fin	1 MG	38 A	derk brown, Peat of Sill; worst	Analyses
2749 - 176	South east - outside of box	- 13:	0.9	pm	49	22 0	Same as above	
2242 -ASIZ	Beneath Fillvalye (Fichas)	15-25	0.7	Fm			2900	
7777 PPS17	Beneeth (3) piping	15130	0.6	fm	**************************************	114 0	bour to gray; silt of organics and gravel rous	*
1777- ASTY	News AST- By THI	15:39	1.0	Fm		12 0	"Some as abore", hydrocarbon ador	hydrorarbonodor * (X
1197-1519	Near AST - By tH2	15.42	0.7	Fm	gater space	95 0	botton till I am a som och odor	* Deo, RED, GRO, BTEX
111 1 - ASTS	Near AST - School complex	15:52	0.6	FW		4.4 8	brown, sith of organics; wet hydrocerbon odor brown; sitt of grovel, bet	of DRO, RED, GRO, BIES
7747 - 1010	News AST - old techer housing		n.7	Fm		623-1 D	Brown grape and a legal vet	
YHYT-ASTIL	Necr AST - gray - old TH	16:02	1.6	Fin				* DEO, EW, AW, BTEX
1+47- AST7	New AST- 84 TH	16:10	0.4	FM	Name of Street	17 P		
					1	H B	brown; organics of sitt and gravel; moist	
3.4			4.40%					
	Market St. Comments of the Comment o				Victory in the			
		Y to the William						
. 124			3			1 858 388		
			A					
					r ye Diff Hedeleys (1915).			
•		4.5						
Segre 1	- 1,500 Cm						에 가장 때 가장 보고 하는데 생각을 하는데 되었다. 사용 사용 사용 사용 사용 사용 기업	
		\$3500						
		10						
						19		
			ogy v e					
			ga yaya daga ku			Gartin et a		
				22.0				1100 8 20
				<ul> <li>Luggerine et ""</li> </ul>	रक्ष सम्बद्धाः स्टब्स्यानस्य	POT W		ASSET
		-		<u>-</u>				Townson.
			2.50		1.5		A Street	
			7.7					
					,949K			

Environmental sample

Field duplicate


GPS readings only collected from analytical sample locations


V see notes on doily field activities

X = deplicate sample

- = ARS point proviously recorded during AST

survey






#### **LEGEND**

Approximate location of Soil Sample location collected by PPS-1 Restoration Science & Engineering (RSE) in August 2000.



Approximate location of water supply line Approximate location of infiltration gallery





Soil samples with DRO concentrations exceeding the ADEC Method Two migration to groundwater cleanup level

Depth, feet (bgs)	DRO, mg/kg
1.5	57,400
0.66	18,100
1.0	3,250
1.0	1,990
1.0	9,750
	1.5 0.66 1.0 1.0

#### **BUILDING LEGEND**

TF Tank Farm

TH Teacher Housing


SSB Schools Shop Building

CBC Community Basketball Court

PPS Pitkas Point School

CW Community Washeteria

FH Fire House



Pitkas Point School Site Pitkas Point, Alaska

#### SITE PLAN

September 2015

32-1-17747-001



Fig. 2

ASTS	Lenstr	Dianeter	Grs Point	ua:	Staining   Stressed vegetation
**Commission	5.9	38	36	1	M. 9. 1. 2 ft s. 2 ft s. 2 ft s. 2 ft s. 3 ft
2	Section 2	3.8	37	Herryod	Yes, cover
3	6.6	3.2	38	Valer	No stoines
	6.1	3.7	39	And the second second	We hadren as soil strong
5	3.76.1	3.8	46	Making of	No! stime
6	6.0	3.8	4	2	NO Staining
7	6.0	3.8	42	Hola	
8	51)	3.1	43		
9	5.1	3,1	44		A series of the
	5.2		47	Hadra A	No striky
page Many	6.1	3.8	46	Hechry oil	ę.
12	6.2	3.8	45	1,	to gain in string

Piping.

# FIELD ACTIVITIES DAILY LOG

	Date 9/18/15
	Sheet of
	Project No. 32-1-17747
Project Name: Pitkas Point.	
Field activity subject:	
Description of daily activities and events:	
0.735 Arrive onsite sun almost over hon'	
Corpleted libris coupling and Screen	ing of contraineted debois.
lote shipped cargo @ LAVAN to Aveninge	
120 13:30 hiported sty manys to a charge	<u> </u>
የመጀመለያ ነገር የሚመረ ነገር መመመን ተመመመን ተመመመ ነገር መመመን የመመመ መመመመ መመመመ መመመመ መመመ ነገር መመመመ ነገር መመመመ ነገር መመመመ ነገር መመመመ ነገር መመመመ	graph with the country of the first that the first the first that the country of
A STATE OF THE STA	
	, .
isitors on site:	
intois on site.	4
hanges from plans/specifications and other special orders ar	nd important decisions:
nanges from plans, specimously and other special orders ar	ta important doolsions.
and the second of the second o	
/eather conditions:	
Court Contractions.	
nportant telephone calls:	
iportant telephone cans.	
ersonnel on site:	
gnature:	Date:
Budearó	PULU.

Project Number:	32-1-17747							
Date: 9/18/15								Location: Pithas Point
Sampler: TWC	-							Site: *****
Sample		C1						Sheet Number:
Number	Location	Sample	Sample	Sample	GPS Way Oblat Reading	PID		
1747- DE1	East of Down 1	Time	Depth	Туре	Reading*	Reading	Soil Classification	Analyses
12742- DOZ	WEST OF AST 10 - NE OF	07:49	0.4	PM	- 54	8.0	plank brown Peat I noist	7 maryses
NA O	ALUE COMPET	17:59	6.7		- 55	1.0	Peak dok bow Peak : march	
NA D	Above Geound pipingmen				50		East of yellow Bldg. & 9 metal courageted reld & 1 p. North of feel bldg. Old school 10 2 pieces - North of the 2 28-10 pieces	e corrupated
MA ®	in hi				5		North of Red bldg. Old school 10 2 pieces -	Cand
14747 PRI	New Berock Mex couple	8:15		-	- 51		Noth of the 28-10 Ricce	200
12242- PR2	East of old school	8:25	0.6	FM	- 56	8.0	North ast 10', Brown; organis Ill silt	
12742- 883	Tost of General Bloke	8:40	0.8		- 57	0.9	I' same as about"	
	7	71	018		- 53	1.2	North ast 10' Brown; organis Usilt I' same as about' Joint Section 10 Diping Rum gray, Sand, moist	* Dro, exo, any BIEX
	·							
								A
								· ·
			•					
					-			
		·						·
		N. W. C.	-					
<u> </u>								
						,		
<u> </u>							·	
								·
:								
34								
***	м	14						
<u> </u>	A HID							
				1				

· Above ground piping - water sever artic piping - pue il insulfoam

Sample Type

ES Environmental sample

FD Field duplicate
FM Field Screening

FM Field Screening

Trip blank

GPS readings only collected from analytical sample locations

NOTE: GB accuracy today 9/18/15 - 25:30' feet.

#### SUMMARY OF GPS COORDINATES

Sample Location	GPS Waypoint	Latitude (N)	Longitude (W)
PPS10	18	62.03164109	-163.286761
PPS10-1	19	62.0316623	-163.2867534
PPS10-2	20	62.03162667	-163.2867292
PPS10-3	21	62.03162374	-163.286825
PPS10-4	22	62.0316493	-163.2868374
PPS1/PPS11	23	62.03155794	-163.2865984
PPS1/PPS11-1	24	62.03158091	-163.286564
PPS1/PPS11-2	25	62.03155903	-163.2865715
PPS1/PPS11-3	26	62.03157018	-163.2866375
PPS12	27	62.03158594	-163.2864174
PPS12-1	28	62.03159432	-163.2863715
PPS12-2	29	62.03156624	-163.2863874
PPS12-3	30	62.03156783	-163.2864506
PPS12-4	31	62.0315991	-163.2864772
PPS13	32	62.03166104	-163.285664
PPS13-1	33	62.03166439	-163.2855741
PPS13-2	34	62.03163405	-163.2855521
PPS13-3	35	62.03162081	-163.2855964
AST1	36	62.03159533	-163.2871031
AST2	37	62.03164537	-163.2867626
AST3	38	62.0315846	-163.2866748
AST4	39	62.03172072	-163.2868568
AST5	40	62.03189992	-163.2870502
AST6	41	62.03188827	-163.2867698
AST7	42	62.03204627	-163.2861307
AST8	43	62.03210779	-163.2860697
AST9	44	62.03220687	-163.2861116
AST12	45	62.03237694	-163.285861
AST11	46	62.03243435	-163.2866893
AST10	47	62.0324331	-163.2866193
TF1	48	62.03234743	-163.285518
TF2	49	62.03233453	-163.2853836
Above Ground Piping	50	62.03200579	-163.2866396
Above Ground Piping	51	62.03225146	-163.2864045
Above Ground Piping	52	62.03254349	-163.2862649
Piping Run #3	53	62.03187218	-163.2863061
East of Drums	54	62.03248288	-163.2862574
West of AST 10	55	62.03244173	-163.2863402
Piping Run #1	56	62.03249236	-163.2861888
Piping Run #2	57	62.0319389	-163.2866177
Washeteria	CW	62.03156683	-163.2867416
Infiltration Gallery	IF	62.03165081	-163.285593
Teacher Housing #1	TH1	62.03217435	-163.2860882
Teacher Housing #2	TH2	62.03234383	-163.2862886
Water Line	WL1	62.03156699	-163.286674

Notes: GPS Coordinate system, WGS 84. Horizontal accuracy of GPS ranged from 12-30 feet during field activities.

# SHANNON & WILSON, INC.

# APPENDIX B SITE PHOTOGRAPHS



Photo 1: Looking south at the Pitkas Point Community and Yukon River. (September 18, 2015)



Photo 2: Looking east at the location of the PPS1/PPS11 sample area near the northwest corner of the Fire House. (September 16, 2015)

PHOTOS 1 AND 2

January 2016




Photo 3: Looking northwest at the location of the PPS10 sample area near the southeast corner of Pitkas Point School. (September 16, 2015)




Photo 4: Looking east at the location of the PPS12 sample area near the northeast of the Fire House. (September 16, 2015)

PHOTOS 3 AND 4

January 2016




Photo 5: Looking east at the location of the PPS13 sample area west of Infiltration Gallery. (September 16, 2015)




Photo 6: Looking northwest at the location of the PPS13 sample area east of Infiltration Gallery. (September 16, 2015)

**PHOTOS 5 AND 6** 

January 2016



Photo 7: Looking east at Tank Farm wood support of former School ASTs. (September 16, 2015)



Photo 8: Looking south at the southeast corner of the Tank Farm. A sheen was present on the surface water ponded within the lined Tank Farm. (September 16, 2015)

PHOTOS 7 AND 8

January 2016




Photo 9: Looking east at the southern boundary of the Tank Farm and associated piping. The piping appeared to be placed both above and below the ground surface in a southwesterly direction and continue to the Yukon River for filling the aboveground tanks. (September 17, 2015)



Photo 10: Looking east at AST4 positioned east of the School Complex building. (September 17, 2015)

PHOTOS 9 AND 10

January 2016



Photo 11: Looking south AST8 located on the north side of the Teacher Housing Building #1. (September 16, 2015)



Photo 12: Looking southwest at AST9 located on the north side of Teacher Housing Building #2. (September 16, 2015)

PHOTOS 11 AND 12

January 2016



Photo 13: Looking east at AST10 located on the west side of a Teacher Housing Building. (September 16, 2015)



Photo 14: Looking northeast at the location of Soil Sample PR3 east of the Generator Building. (September 18, 2015)

PHOTOS 13 AND 14

January 2016

#### **APPENDIX C**

# RESULTS OF ANALYTICAL TESTING BY SGS NORTH AMERICA INC. OF ANCHORAGE, ALASKA AND ADEC LABORATORY DATA REVIEW CHECKLISTS



#### **Laboratory Report of Analysis**

To: Shannon & Wilson, Inc.

5430 Fairbanks Street, Ste 3 Anchorage, AK 99518

Report Number: 1155496

Client Project: 32-1-17747 Pitkas Point

907-561-2120

Dear Tim Terry,

Enclosed are the results of the analytical services performed under the referenced project for the received samples and associated QC as applicable. The samples are certified to meet the requirements of the National Environmental Laboratory Accreditation Conference Standards. Copies of this report and supporting data will be retained in our files for a period of ten years in the event they are required for future reference. All results are intended to be used in their entirety and SGS is not responsible for use of less than the complete report. Any samples submitted to our laboratory will be retained for a maximum of fourteen (14) days from the date of this report unless other archiving requirements were included in the quote.

If there are any questions about the report or services performed during this project, please call Victoria at (907) 562-2343. We will be happy to answer any questions or concerns which you may have.

Thank you for using SGS North America Inc. for your analytical services. We look forward to working with you again on any additional analytical needs.

Sincerely,

SGS North America Inc.

Victoria Pennick

2015.10.08

11:58:33 -08'00'

Date

Victoria Pennick Project Manager

Victoria.Pennick@sgs.com

Print Date: 10/08/2015 11:54:01AM

SGS North America Inc. | 200 West Potter Drive, Anchorage, AK 99518 | t 907.562.2343 f 907.561.5301 www.us.sgs.com



#### **Case Narrative**

SGS Client: **Shannon & Wilson, Inc.**SGS Project: **1155496**Project Name/Site: **32-1-17747 Pitkas Point**Project Contact: **Tim Terry** 

Refer to sample receipt form for information on sample condition.

#### 17747-AST4 (1155496001) PS

AK 103 - Surrogate recovery for n-triacontane (273%) does not meet QC criteria due to sample matrix. Prep final volume is 5mL.

#### 17747-AST4X (1155496002) PS

AK 103 - Surrogate recovery for n-triacontane (268%) does not meet QC criteria due to sample matrix. Prep final volume is 5mL.

#### 17747-AST9 (1155496004) PS

AK101 - Surrogate recovery for 4-bromofluorobenzene (42.9%) does not meet QC criteria. Sample was analyzed twice { | k/2| } -4{ act} } È AK102 - Surrogate recovery for 5a-androstane (0%) does not meet QC criteria due to sample dilution (20X).

#### 17747-AST9X (1155496008) PS

Sample not analyzed per client request.

\*QC comments may be associated with the field samples found in this report. When applicable, comments will be applied to associated field samples.

Print Date: 10/08/2015 11:54:02AM



#### **Laboratory Qualifiers**

Enclosed are the analytical results associated with the above work order. All results are intended to be used in their entirety and SGS is not responsible for use of less than the complete report. This document is issued by the Company under its General Conditions of Service accessible at <a href="http://www.sgs.com/en/Terms-and-Conditions.aspx">http://www.sgs.com/en/Terms-and-Conditions.aspx</a>. Attention is drawn to the limitation of liability, indenmification and jurisdiction issues defined therein.

Any holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. Any unauthorized alteration, forgery or falsification of the context or appearance of this document is unlawful and offenders may be prosecuted to the fullest extent of the law.

SGS maintains a formal Quality Assurance/Quality Control (QA/QC) program. A copy of our Quality Assurance Plan (QAP), which outlines this program, is available at your request. The laboratory certification numbers are AK00971 (DW Chemistry & Microbiology) & UST-005 (CS) for ADEC and 2944.01 for DOD ELAP/ISO17025 (RCRA methods: 1020B, 1311, 3010A, 3050B, 3520C, 3550C, 5030B, 5035A, 6020A, 7470A, 7471B, 8021B, 8082A, 8260B, 8270D, 8270D-SIM, 9040C, 9045D, 9056A, 9060A, AK101 and AK102/103). Except as specifically noted, all statements and data in this report are in conformance to the provisions set forth by the SGS QAP and, when applicable, other regulatory authorities.

The following descriptors or qualifiers may be found in your report:

\* The analyte has exceeded allowable regulatory or control limits.

! Surrogate out of control limits.

B Indicates the analyte is found in a blank associated with the sample.

CCV/CVA/CVB Continuing Calibration Verification

CCCV/CVC/CVCA/CVCB Closing Continuing Calibration Verification

CL Control Limit

D The analyte concentration is the result of a dilution.

DF Dilution Factor

DL Detection Limit (i.e., maximum method detection limit)
E The analyte result is above the calibrated range.
F Indicates value that is greater than or equal to the DL

GT Greater Than
IB Instrument Blank

ICV Initial Calibration Verification

J The quantitation is an estimation.

JL The analyte was positively identified, but the quantitation is a low estimation.

LCS(D) Laboratory Control Spike (Duplicate)
LOD Limit of Detection (i.e., 1/2 of the LOQ)

LOQ Limit of Quantitation (i.e., reporting or practical quantitation limit)

LT Less Than

M A matrix effect was present.

MB Method Blank

MS(D) Matrix Spike (Duplicate)

ND Indicates the analyte is not detected.
Q QC parameter out of acceptance range.

R Rejected

RPD Relative Percent Difference

U Indicates the analyte was analyzed for but not detected.

Note: Sample summaries which include a result for "Total Solids" have already been adjusted for moisture content.

All DRO/RRO analyses are integrated per SOP.

Print Date: 10/08/2015 11:54:04AM

SGS North America Inc. 200 West Potter Drive, Anchorage, AK 99518



#### **Sample Summary**

Client Sample ID	Lab Sample ID	Collected	Received	<u>Matrix</u>
17747-AST4	1155496001	09/17/2015	09/22/2015	Soil/Solid (dry weight)
17747-AST4X	1155496002	09/17/2015	09/22/2015	Soil/Solid (dry weight)
17747-AST8	1155496003	09/17/2015	09/22/2015	Soil/Solid (dry weight)
17747-AST9	1155496004	09/17/2015	09/22/2015	Soil/Solid (dry weight)
17747-AST10	1155496005	09/17/2015	09/22/2015	Soil/Solid (dry weight)
17747-PR3	1155496006	09/18/2015	09/22/2015	Soil/Solid (dry weight)
17747-TB2	1155496007	09/18/2015	09/22/2015	Soil/Solid (dry weight)
17747-AST9X	1155496008	09/17/2015	09/22/2015	Soil/Solid (dry weight)

Method Method Description AK101 AK101/8021 Combo. (S) SW8021B AK101/8021 Combo. (S)

AK102 Diesel/Residual Range Organics AK103 Diesel/Residual Range Organics SM21 2540G

Percent Solids SM2540G



#### **Detectable Results Summary**

Client Sample ID: 17747-AST4			
Lab Sample ID: 1155496001	<u>Parameter</u>	Result	<u>Units</u>
Semivolatile Organic Fuels	Diesel Range Organics	6300	mg/Kg
	Residual Range Organics	3560	mg/Kg
Volatile Fuels	Ethylbenzene	49.2J	ug/Kg
	Gasoline Range Organics	30.6	mg/Kg
	o-Xylene	898	ug/Kg
	P & M -Xylene	314	ug/Kg
	Toluene	54.8J	ug/Kg
Client Sample ID: 17747-AST4X			
Lab Sample ID: 1155496002	Parameter	Result	Units
Semivolatile Organic Fuels	Diesel Range Organics	6740	mg/Kg
_	Residual Range Organics	3630	mg/Kg
Volatile Fuels	Gasoline Range Organics	20.8	mg/Kg
	o-Xylene	207	ug/Kg
	P & M -Xylene	171	ug/Kg
Client Sample ID: 17747-AST8			
Lab Sample ID: 1155496003	Parameter	Result	<u>Units</u>
Semivolatile Organic Fuels	Diesel Range Organics	126	mg/Kg
Comvolatile Organie i dele	Residual Range Organics	507	mg/Kg
Volatile Fuels	Gasoline Range Organics	2.57J	mg/Kg
Client Sample ID: 17747-AST9			
Lab Sample ID: 1155496004	Parameter	Result	Units
Semivolatile Organic Fuels	Diesel Range Organics	5330	mg/Kg
Jennivolatne Organic i dels	Residual Range Organics	248	mg/Kg
Volatile Fuels	Gasoline Range Organics	2.64J	mg/Kg
			99
Client Sample ID: 17747-AST10	_		
Lab Sample ID: 1155496005	<u>Parameter</u>	Result	<u>Units</u>
Samiyalatila Organia Eugle		288	mg/Kg
Semivolatile Organic Fuels	Diesel Range Organics	4400	
_	Residual Range Organics	1180	mg/Kg
Volatile Fuels		1180 2.65J	
Volatile Fuels Client Sample ID: 17747-PR3	Residual Range Organics		mg/Kg
Volatile Fuels	Residual Range Organics		mg/Kg

Print Date: 10/08/2015 11:54:06AM

SGS North America Inc. 200 West Potter Drive, Anchorage, AK 99518 t 907.562.2343 f 907.561.5301 www.us.sgs.com



#### Results of 17747-AST4

Client Sample ID: 17747-AST4

Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155496001 Lab Project ID: 1155496 Collection Date: 09/17/15 18:01 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):56.4 Location:

#### Results by Semivolatile Organic Fuels

Parameter Diesel Range Organics	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	Allowable	<u>Date Analyzed</u>
	6300	700	217	mg/Kg	4	Limits	10/05/15 10:37
Surrogates 5a Androstane (surr)	89.6	50-150		%	4		10/05/15 10:37

#### **Batch Information**

Analytical Batch: XFC12131 Analytical Method: AK102

Analyst: NLL

Analytical Date/Time: 10/05/15 10:37 Container ID: 1155496001-A

Prep Batch: XXX34222 Prep Method: SW3550C Prep Date/Time: 09/23/15 16:43 Prep Initial Wt./Vol.: 30.391 g Prep Extract Vol: 5 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	3560	175	54.3	mg/Kg	1		10/03/15 23:06
Surrogates							
n-Triacontane-d62 (surr)	273 *	50-150		%	1		10/03/15 23:06

#### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK103

Analyst: NLL

Analytical Date/Time: 10/03/15 23:06 Container ID: 1155496001-A Prep Batch: XXX34222 Prep Method: SW3550C Prep Date/Time: 09/23/15 16:43 Prep Initial Wt./Vol.: 30.391 g Prep Extract Vol: 5 mL

Print Date: 10/08/2015 11:54:07AM

J flagging is activated



#### Results of 17747-AST4

Client Sample ID: 17747-AST4

Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155496001 Lab Project ID: 1155496 Collection Date: 09/17/15 18:01 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):56.4 Location:

#### Results by Volatile Fuels

Parameter Gasoline Range Organics	Result Qual 30.6	<u>LOQ/CL</u> 8.06	<u>DL</u> 2.42	<u>Units</u> mg/Kg	<u>DF</u> 1	Allowable Limits	<u>Date Analyzed</u> 09/26/15 20:09
Surrogates							
4-Bromofluorobenzene (surr)	148	50-150		%	1		09/26/15 20:09

#### **Batch Information**

Analytical Batch: VFC12695 Analytical Method: AK101

Analyst: CRD

Analytical Date/Time: 09/26/15 20:09 Container ID: 1155496001-B Prep Batch: VXX27969 Prep Method: SW5035A Prep Date/Time: 09/17/15 18:01 Prep Initial Wt./Vol.: 52.838 g Prep Extract Vol: 48.0379 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	20.1 U	40.3	12.9	ug/Kg	1		09/26/15 20:09
Ethylbenzene	49.2 J	80.6	25.1	ug/Kg	1		09/26/15 20:09
o-Xylene	898	80.6	25.1	ug/Kg	1		09/26/15 20:09
P & M -Xylene	314	161	48.4	ug/Kg	1		09/26/15 20:09
Toluene	54.8 J	80.6	25.1	ug/Kg	1		09/26/15 20:09
Surrogates							
1,4-Difluorobenzene (surr)	89.1	72-119		%	1		09/26/15 20:09

#### **Batch Information**

Analytical Batch: VFC12695 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 09/26/15 20:09 Container ID: 1155496001-B Prep Batch: VXX27969
Prep Method: SW5035A
Prep Date/Time: 09/17/15 18:01
Prep Initial Wt./Vol.: 52.838 g

Prep Extract Vol: 48.0379 mL

Print Date: 10/08/2015 11:54:07AM

J flagging is activated



#### Results of 17747-AST4X

Client Sample ID: 17747-AST4X

Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155496002 Lab Project ID: 1155496 Collection Date: 09/17/15 18:04 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):58.3 Location:

#### Results by Semivolatile Organic Fuels

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Diesel Range Organics	6740	682	211	mg/Kg	4		10/05/15 10:46
Surrogates							
5a Androstane (surr)	97.2	50-150		%	4		10/05/15 10:46

#### **Batch Information**

Analytical Batch: XFC12131 Analytical Method: AK102

Analyst: NLL

Analytical Date/Time: 10/05/15 10:46 Container ID: 1155496002-A Prep Batch: XXX34222 Prep Method: SW3550C Prep Date/Time: 09/23/15 16:43 Prep Initial Wt./Vol.: 30.187 g Prep Extract Vol: 5 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	3630	171	52.9	mg/Kg	1		10/03/15 23:16
Surrogates							
n-Triacontane-d62 (surr)	268 *	50-150		%	1		10/03/15 23:16

#### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK103

Analyst: NLL

Analytical Date/Time: 10/03/15 23:16 Container ID: 1155496002-A

Prep Batch: XXX34222 Prep Method: SW3550C Prep Date/Time: 09/23/15 16:43 Prep Initial Wt./Vol.: 30.187 g Prep Extract Vol: 5 mL

Print Date: 10/08/2015 11:54:07AM

J flagging is activated



Client Sample ID: 17747-AST4X

Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155496002 Lab Project ID: 1155496 Collection Date: 09/17/15 18:04 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):58.3 Location:

# Results by Volatile Fuels

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Gasoline Range Organics	20.8	8.45	2.53	mg/Kg	1		10/01/15 02:01
Surrogates							
4-Bromofluorobenzene (surr)	107	50-150		%	1		10/01/15 02:01

### **Batch Information**

Analytical Batch: VFC12702 Analytical Method: AK101

Analyst: CRD

Analytical Date/Time: 10/01/15 02:01 Container ID: 1155496002-B

Prep Batch: VXX27990 Prep Method: SW5035A Prep Date/Time: 09/17/15 18:04 Prep Initial Wt./Vol.: 44.088 g Prep Extract Vol: 43.3985 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	21.1 U	42.2	13.5	ug/Kg	1		10/01/15 02:01
Ethylbenzene	42.3 U	84.5	26.4	ug/Kg	1		10/01/15 02:01
o-Xylene	207	84.5	26.4	ug/Kg	1		10/01/15 02:01
P & M -Xylene	171	169	50.7	ug/Kg	1		10/01/15 02:01
Toluene	42.3 U	84.5	26.4	ug/Kg	1		10/01/15 02:01
Surrogates							
1,4-Difluorobenzene (surr)	87.2	72-119		%	1		10/01/15 02:01

### **Batch Information**

Analytical Batch: VFC12702 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 10/01/15 02:01 Container ID: 1155496002-B

Prep Batch: VXX27990 Prep Method: SW5035A Prep Date/Time: 09/17/15 18:04

Prep Initial Wt./Vol.: 44.088 g Prep Extract Vol: 43.3985 mL

Print Date: 10/08/2015 11:54:07AM



Client Sample ID: 17747-AST8

Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155496003 Lab Project ID: 1155496 Collection Date: 09/17/15 17:13 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):59.8 Location:

# Results by Semivolatile Organic Fuels

Parameter Diesel Range Organics	Result Qual 126	<u>LOQ/CL</u> 74.1	<u>DL</u> 23.0	<u>Units</u> mg/Kg	<u>DF</u> 1	Allowable Limits	Date Analyzed 10/03/15 23:26
Surrogates							
5a Androstane (surr)	72.7	50-150		%	1		10/03/15 23:26

### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK102

Analyst: NLL

Analytical Date/Time: 10/03/15 23:26 Container ID: 1155496003-A Prep Batch: XXX34222 Prep Method: SW3550C Prep Date/Time: 09/23/15 16:43 Prep Initial Wt./Vol.: 13.538 g Prep Extract Vol: 1 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	507	74.1	23.0	mg/Kg	1		10/03/15 23:26
Surrogates							
n-Triacontane-d62 (surr)	84.3	50-150		%	1		10/03/15 23:26

#### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK103

Analyst: NLL

Analytical Date/Time: 10/03/15 23:26 Container ID: 1155496003-A Prep Batch: XXX34222 Prep Method: SW3550C Prep Date/Time: 09/23/15 16:43 Prep Initial Wt./Vol.: 13.538 g Prep Extract Vol: 1 mL

Print Date: 10/08/2015 11:54:07AM



Client Sample ID: 17747-AST8

Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155496003 Lab Project ID: 1155496 Collection Date: 09/17/15 17:13 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):59.8 Location:

# Results by Volatile Fuels

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Gasoline Range Organics	2.57 J	6.30	1.89	mg/Kg	1		09/26/15 20:47
Surrogates							
4-Bromofluorobenzene (surr)	71.3	50-150		%	1		09/26/15 20:47

### **Batch Information**

Analytical Batch: VFC12695 Analytical Method: AK101

Analyst: CRD

Analytical Date/Time: 09/26/15 20:47 Container ID: 1155496003-B

Prep Batch: VXX27969
Prep Method: SW5035A
Prep Date/Time: 09/17/15 17:13
Prep Initial Wt./Vol.: 71.114 g
Prep Extract Vol: 53.6005 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	15.8 U	31.5	10.1	ug/Kg	1		09/26/15 20:47
Ethylbenzene	31.5 ∪	63.0	19.7	ug/Kg	1		09/26/15 20:47
o-Xylene	31.5 ∪	63.0	19.7	ug/Kg	1		09/26/15 20:47
P & M -Xylene	63.0 U	126	37.8	ug/Kg	1		09/26/15 20:47
Toluene	31.5 ∪	63.0	19.7	ug/Kg	1		09/26/15 20:47
Surrogates							
1,4-Difluorobenzene (surr)	89.2	72-119		%	1		09/26/15 20:47

# **Batch Information**

Analytical Batch: VFC12695 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 09/26/15 20:47 Container ID: 1155496003-B Prep Batch: VXX27969
Prep Method: SW5035A
Prep Date/Time: 09/17/15 17:13
Prep Initial Wt./Vol.: 71.114 g

Prep Extract Vol: 53.6005 mL

Print Date: 10/08/2015 11:54:07AM J flagging is activated



Client Sample ID: 17747-AST9

Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155496004 Lab Project ID: 1155496 Collection Date: 09/17/15 17:40 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):66.1 Location:

# Results by Semivolatile Organic Fuels

Parameter Diesel Range Organics	Result Qual	<u>LOQ/CL</u>	<u>DL</u>	<u>Units</u>	<u>DF</u>	Allowable	Date Analyzed
	5330	602	187	mg/Kg	20	Limits	10/05/15 20:31
Surrogates 5a Androstane (surr)	0 *	50-150		%	20		10/05/15 20:31

### **Batch Information**

Analytical Batch: XFC12132 Analytical Method: AK102

Analyst: NLL

Analytical Date/Time: 10/05/15 20:31 Container ID: 1155496004-A

Prep Batch: XXX34222 Prep Method: SW3550C Prep Date/Time: 09/23/15 16:43 Prep Initial Wt./Vol.: 30.184 g Prep Extract Vol: 1 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	248	30.1	9.33	mg/Kg	1		10/03/15 23:36
Surrogates							
n-Triacontane-d62 (surr)	99.9	50-150		%	1		10/03/15 23:36

#### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK103

Analyst: NLL

Analytical Date/Time: 10/03/15 23:36 Container ID: 1155496004-A Prep Batch: XXX34222 Prep Method: SW3550C Prep Date/Time: 09/23/15 16:43 Prep Initial Wt./Vol.: 30.184 g Prep Extract Vol: 1 mL

Print Date: 10/08/2015 11:54:07AM



Client Sample ID: 17747-AST9

Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155496004 Lab Project ID: 1155496 Collection Date: 09/17/15 17:40 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):66.1 Location:

# Results by Volatile Fuels

Parameter Gasoline Range Organics	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Allowable</u>	<u>Date Analyzed</u>
	2.64 J	4.45	1.34	mg/Kg	1	<u>Limits</u>	10/01/15 02:58
Surrogates 4-Bromofluorobenzene (surr)	42.9 *	50-150		%	4		10/01/15 02:58

### **Batch Information**

Analytical Batch: VFC12702 Analytical Method: AK101

Analyst: CRD

Analytical Date/Time: 10/01/15 02:58 Container ID: 1155496004-B Prep Batch: VXX27990 Prep Method: SW5035A Prep Date/Time: 09/17/15 17:40 Prep Initial Wt./Vol.: 100.379 g Prep Extract Vol: 59.0631 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	11.2 U	22.3	7.13	ug/Kg	1		09/26/15 21:06
Ethylbenzene	22.3 ∪	44.5	13.9	ug/Kg	1		09/26/15 21:06
o-Xylene	22.3 ∪	44.5	13.9	ug/Kg	1		09/26/15 21:06
P & M -Xylene	44.5 U	89.1	26.7	ug/Kg	1		09/26/15 21:06
Toluene	22.3 ∪	44.5	13.9	ug/Kg	1		09/26/15 21:06
Surrogates							
1,4-Difluorobenzene (surr)	88.6	72-119		%	1		09/26/15 21:06

# **Batch Information**

Analytical Batch: VFC12695 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 09/26/15 21:06 Container ID: 1155496004-B Prep Batch: VXX27969
Prep Method: SW5035A
Prep Date/Time: 09/17/15 17:40
Prep Initial Wt./Vol.: 100.379 g
Prep Extract Vol: 59.0631 mL

Print Date: 10/08/2015 11:54:07AM



Client Sample ID: 17747-AST10

Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155496005 Lab Project ID: 1155496

Collection Date: 09/17/15 17:05 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):54.6 Location:

# Results by Semivolatile Organic Fuels

Parameter Diesel Range Organics	Result Qual	<u>LOQ/CL</u>	<u>DL</u>	<u>Units</u>	<u>DF</u>	Allowable	Date Analyzed
	288	36.1	11.2	mg/Kg	1	Limits	10/03/15 23:45
Surrogates 5a Androstane (surr)	77.3	50-150		%	1		10/03/15 23:45

### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK102

Analyst: NLL

Analytical Date/Time: 10/03/15 23:45 Container ID: 1155496005-A

Prep Batch: XXX34222 Prep Method: SW3550C Prep Date/Time: 09/23/15 16:43 Prep Initial Wt./Vol.: 30.38 g Prep Extract Vol: 1 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	1180	36.1	11.2	mg/Kg	1		10/03/15 23:45
Surrogates							
n-Triacontane-d62 (surr)	89.7	50-150		%	1		10/03/15 23:45

#### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK103

Analyst: NLL

Analytical Date/Time: 10/03/15 23:45 Container ID: 1155496005-A

Prep Batch: XXX34222 Prep Method: SW3550C Prep Date/Time: 09/23/15 16:43 Prep Initial Wt./Vol.: 30.38 g Prep Extract Vol: 1 mL

Print Date: 10/08/2015 11:54:07AM

t 907.562.2343 f 907.561.5301 www.us.sgs.com



Client Sample ID: 17747-AST10

Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155496005 Lab Project ID: 1155496 Collection Date: 09/17/15 17:05 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):54.6 Location:

# Results by Volatile Fuels

<u>Parameter</u> Gasoline Range Organics	Result Qual 2.65 J	<u>LOQ/CL</u> 6.98	<u>DL</u> 2.09	<u>Units</u> mg/Kg	<u>DF</u> 1	Allowable Limits	<u>Date Analyzed</u> 09/26/15 21:25
Surrogates							
4-Bromofluorobenzene (surr)	92.2	50-150		%	1		09/26/15 21:25

### **Batch Information**

Analytical Batch: VFC12695 Analytical Method: AK101

Analyst: CRD

Analytical Date/Time: 09/26/15 21:25 Container ID: 1155496005-B Prep Batch: VXX27969
Prep Method: SW5035A
Prep Date/Time: 09/17/15 17:05
Prep Initial Wt./Vol.: 80.794 g
Prep Extract Vol: 61.6423 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	17.4 ∪	34.9	11.2	ug/Kg	1		09/26/15 21:25
Ethylbenzene	34.9 ∪	69.8	21.8	ug/Kg	1		09/26/15 21:25
o-Xylene	34.9 ∪	69.8	21.8	ug/Kg	1		09/26/15 21:25
P & M -Xylene	70.0 ∪	140	41.9	ug/Kg	1		09/26/15 21:25
Toluene	34.9 ∪	69.8	21.8	ug/Kg	1		09/26/15 21:25
Surrogates							
1,4-Difluorobenzene (surr)	88.4	72-119		%	1		09/26/15 21:25

### **Batch Information**

Analytical Batch: VFC12695 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 09/26/15 21:25 Container ID: 1155496005-B Prep Batch: VXX27969 Prep Method: SW5035A Prep Date/Time: 09/17/15 17:05 Prep Initial Wt./Vol.: 80.794 g

Prep Extract Vol: 61.6423 mL

Print Date: 10/08/2015 11:54:07AM J flagging is activated



### Results of 17747-PR3

Client Sample ID: 17747-PR3

Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155496006 Lab Project ID: 1155496 Collection Date: 09/18/15 09:35 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):81.2 Location:

# Results by Semivolatile Organic Fuels

<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	Allowable Limits	Date Analyzed
Diesel Range Organics	12.2 U	24.3	7.53	mg/Kg	1		10/03/15 23:55
Surrogates							
5a Androstane (surr)	74	50-150		%	1		10/03/15 23:55

### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK102

Analyst: NLL

Analytical Date/Time: 10/03/15 23:55 Container ID: 1155496006-A Prep Batch: XXX34222
Prep Method: SW3550C
Prep Date/Time: 09/23/15 16:43
Prep Initial Wt./Vol.: 30.41 g
Prep Extract Vol: 1 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	57.2	24.3	7.53	mg/Kg	1		10/03/15 23:55
Surrogates							
n-Triacontane-d62 (surr)	83.3	50-150		%	1		10/03/15 23:55

#### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK103

Analyst: NLL

Analytical Date/Time: 10/03/15 23:55 Container ID: 1155496006-A Prep Batch: XXX34222 Prep Method: SW3550C Prep Date/Time: 09/23/15 16:43 Prep Initial Wt./Vol.: 30.41 g Prep Extract Vol: 1 mL

Print Date: 10/08/2015 11:54:07AM



### Results of 17747-PR3

Client Sample ID: 17747-PR3

Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155496006 Lab Project ID: 1155496 Collection Date: 09/18/15 09:35 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):81.2 Location:

# Results by Volatile Fuels

Parameter Gasoline Range Organics	Result Qual	<u>LOQ/CL</u> 3.17	<u>DL</u> 0.952	<u>Units</u> mg/Kg	<u>DF</u> 1	Allowable Limits	Date Analyzed 09/26/15 21:44
Surrogates	1.59 ()	3.17	0.932	mg/Kg	'		09/20/13 21.44
4-Bromofluorobenzene (surr)	99.2	50-150		%	1		09/26/15 21:44

### **Batch Information**

Analytical Batch: VFC12695 Analytical Method: AK101

Analyst: CRD

Analytical Date/Time: 09/26/15 21:44 Container ID: 1155496006-B Prep Batch: VXX27969
Prep Method: SW5035A
Prep Date/Time: 09/18/15 09:35
Prep Initial Wt./Vol.: 76.361 g
Prep Extract Vol: 39.3441 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	7.95 ∪	15.9	5.08	ug/Kg	1		09/26/15 21:44
Ethylbenzene	15.9 ∪	31.7	9.90	ug/Kg	1		09/26/15 21:44
o-Xylene	15.9 ∪	31.7	9.90	ug/Kg	1		09/26/15 21:44
P & M -Xylene	31.7 ∪	63.4	19.0	ug/Kg	1		09/26/15 21:44
Toluene	15.9 ∪	31.7	9.90	ug/Kg	1		09/26/15 21:44
Surrogates							
1,4-Difluorobenzene (surr)	89	72-119		%	1		09/26/15 21:44

### **Batch Information**

Analytical Batch: VFC12695 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 09/26/15 21:44 Container ID: 1155496006-B Prep Batch: VXX27969 Prep Method: SW5035A Prep Date/Time: 09/18/15 09:35 Prep Initial Wt./Vol.: 76.361 g

Prep Extract Vol: 39.3441 mL

Print Date: 10/08/2015 11:54:07AM



Client Sample ID: 17747-TB2

Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155496007 Lab Project ID: 1155496 Collection Date: 09/18/15 09:55 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%): Location:

# Results by Volatile Fuels

Parameter	Result Qual	LOQ/CL	<u>DL</u>	Units	<u>DF</u>	Allowable Limits	Date Analyzed
Gasoline Range Organics	1.25 U	2.51	0.752	mg/Kg	1	<u>Emmto</u>	09/26/15 16:02
Surrogates							
4-Bromofluorobenzene (surr)	82.8	50-150		%	1		09/26/15 16:02

### **Batch Information**

Analytical Batch: VFC12695 Analytical Method: AK101

Analyst: CRD

Analytical Date/Time: 09/26/15 16:02 Container ID: 1155496007-A Prep Batch: VXX27969
Prep Method: SW5035A
Prep Date/Time: 09/18/15 09:55
Prep Initial Wt./Vol.: 49.896 g
Prep Extract Vol: 25 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	6.25 ⋃	12.5	4.01	ug/Kg	1		09/26/15 16:02
Ethylbenzene	12.6 U	25.1	7.82	ug/Kg	1		09/26/15 16:02
o-Xylene	12.6 U	25.1	7.82	ug/Kg	1		09/26/15 16:02
P & M -Xylene	25.1 ∪	50.1	15.0	ug/Kg	1		09/26/15 16:02
Toluene	12.6 U	25.1	7.82	ug/Kg	1		09/26/15 16:02
Surrogates							
1,4-Difluorobenzene (surr)	87.4	72-119		%	1		09/26/15 16:02

# **Batch Information**

Analytical Batch: VFC12695 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 09/26/15 16:02 Container ID: 1155496007-A Prep Batch: VXX27969
Prep Method: SW5035A
Prep Date/Time: 09/18/15 09:55
Prep Initial Wt./Vol.: 49.896 g
Prep Extract Vol: 25 mL

Print Date: 10/08/2015 11:54:07AM



Blank ID: MB for HBN 1721128 [SPT/9747]

Blank Lab ID: 1292951

QC for Samples:

 $1155496001,\,1155496002,\,1155496003,\,1155496004,\,1155496005,\,1155496006,\,1155496008$ 

Results by SM21 2540G

 Parameter
 Results
 LOQ/CL
 DL
 Units

 Total Solids
 100
 %

Matrix: Soil/Solid (dry weight)

**Batch Information** 

Analytical Batch: SPT9747 Analytical Method: SM21 2540G

Instrument: Analyst: A.R

Analytical Date/Time: 9/23/2015 4:50:00PM

Print Date: 10/08/2015 11:54:10AM



# **Duplicate Sample Summary**

Original Sample ID: 1155534002 Analysis Date: 09/23/2015 16:50 Duplicate Sample ID: 1292952 Matrix: Soil/Solid (dry weight)

QC for Samples:

1155496001, 1155496002, 1155496003, 1155496004, 1155496005, 1155496006, 1155496008

# Results by SM21 2540G

NAME	<u>Original</u>	Duplicate	<u>Units</u>	RPD (%)	RPD CL
Total Solids	95.0	94.8	%	0.30	(< 15)

### **Batch Information**

Analytical Batch: SPT9747 Analytical Method: SM21 2540G

Instrument: Analyst: A.R

Print Date: 10/08/2015 11:54:11AM



Blank ID: MB for HBN 1721443 [VXX/27969]

Blank Lab ID: 1293514

QC for Samples:

1155496001, 1155496003, 1155496004, 1155496005, 1155496006, 1155496007

Results by AK101

ParameterResultsLOQ/CLDLUnitsGasoline Range Organics1.01J2.500.750mg/Kg

Matrix: Soil/Solid (dry weight)

**Surrogates** 

4-Bromofluorobenzene (surr) 73 50-150 %

**Batch Information** 

Analytical Batch: VFC12695 Prep Batch: VXX27969
Analytical Method: AK101 Prep Method: SW5035A

Instrument: Agilent 7890A PID/FID Prep Date/Time: 9/26/2015 8:00:00AM

Analyst: CRD Prep Initial Wt./Vol.: 50 g Analytical Date/Time: 9/26/2015 1:49:00PM Prep Extract Vol: 25 mL

Print Date: 10/08/2015 11:54:13AM



### **Blank Spike Summary**

Blank Spike ID: LCS for HBN 1155496 [VXX27969]

Blank Spike Lab ID: 1293517

Date Analyzed: 09/26/2015 14:46

Spike Duplicate ID: LCSD for HBN 1155496

[VXX27969]

Spike Duplicate Lab ID: 1293518

Matrix: Soil/Solid (dry weight)

QC for Samples: 1155496001, 1155496003, 1155496004, 1155496005, 1155496006, 1155496007

# Results by AK101

	В	lank Spike	(mg/Kg)	S	pike Duplic	ate (mg/Kg)			
<u>Parameter</u>	Spike	Result	Rec (%)	Spike	Result	Rec (%)	CL	RPD (%)	RPD CL
Gasoline Range Organics	10.0	11.6	116	10.0	11.3	113	(60-120)	2.60	(< 20 )
Surrogates									
4-Bromofluorobenzene (surr)	1.25	76.5	77	1.25	77.4	77	(50-150)	1.10	

### **Batch Information**

Analytical Batch: VFC12695
Analytical Method: AK101

Instrument: Agilent 7890A PID/FID

Analyst: CRD

Prep Batch: VXX27969
Prep Method: SW5035A

Prep Date/Time: 09/26/2015 08:00

Spike Init Wt./Vol.: 10.0 mg/Kg Extract Vol: 25 mL Dupe Init Wt./Vol.: 10.0 mg/Kg Extract Vol: 25 mL

Print Date: 10/08/2015 11:54:15AM



Blank ID: MB for HBN 1721443 [VXX/27969]

Blank Lab ID: 1293514

QC for Samples:

1155496001, 1155496003, 1155496004, 1155496005, 1155496006, 1155496007

# Results by SW8021B

<u>Parameter</u>	Results	LOQ/CL	<u>DL</u>	<u>Units</u>
Benzene	6.25U	12.5	4.00	ug/Kg
Ethylbenzene	12.5U	25.0	7.80	ug/Kg
o-Xylene	12.5U	25.0	7.80	ug/Kg
P & M -Xylene	15.5J	50.0	15.0	ug/Kg
Toluene	12.5J	25.0	7.80	ug/Kg
Surrogates				
1,4-Difluorobenzene (surr)	87.2	72-119		%

### **Batch Information**

Analytical Batch: VFC12695 Analytical Method: SW8021B

Instrument: Agilent 7890A PID/FID

Analyst: CRD

Analytical Date/Time: 9/26/2015 1:49:00PM

Prep Batch: VXX27969 Prep Method: SW5035A

Prep Date/Time: 9/26/2015 8:00:00AM

Matrix: Soil/Solid (dry weight)

Prep Initial Wt./Vol.: 50 g Prep Extract Vol: 25 mL

Print Date: 10/08/2015 11:54:17AM



### **Blank Spike Summary**

Blank Spike ID: LCS for HBN 1155496 [VXX27969]

Blank Spike Lab ID: 1293515 Date Analyzed: 09/26/2015 14:08 Spike Duplicate ID: LCSD for HBN 1155496

[VXX27969]

Spike Duplicate Lab ID: 1293516 Matrix: Soil/Solid (dry weight)

QC for Samples: 1155496001, 1155496003, 1155496004, 1155496005, 1155496006, 1155496007

# Results by SW8021B

	Е	Blank Spike	(ug/Kg)	S	pike Duplic	ate (ug/Kg)			
<u>Parameter</u>	<u>Spike</u>	Result	Rec (%)	<u>Spike</u>	Result	Rec (%)	CL	RPD (%)	RPD CL
Benzene	1250	1320	106	1250	1290	103	(75-125)	2.50	(< 20 )
Ethylbenzene	1250	1240	99	1250	1220	98	(75-125)	1.70	(< 20 )
o-Xylene	1250	1140	91	1250	1120	90	(75-125)	1.30	(< 20 )
P & M -Xylene	2500	2390	96	2500	2350	94	(80-125)	1.60	(< 20 )
Toluene	1250	1230	99	1250	1210	97	(70-125)	1.60	(< 20 )
Surrogates									
1,4-Difluorobenzene (surr)	1250	91	91	1250	90.6	91	(72-119)	0.48	

# **Batch Information**

Analytical Batch: VFC12695 Analytical Method: SW8021B Instrument: Agilent 7890A PID/FID

Analyst: CRD

Prep Batch: VXX27969
Prep Method: SW5035A

Prep Date/Time: 09/26/2015 08:00

Spike Init Wt./Vol.: 1250 ug/Kg Extract Vol: 25 mL Dupe Init Wt./Vol.: 1250 ug/Kg Extract Vol: 25 mL

Print Date: 10/08/2015 11:54:18AM



### **Matrix Spike Summary**

 Original Sample ID: 1155497013
 Analysis Date: 09/26/2015 16:21

 MS Sample ID: 1293519 MS
 Analysis Date: 09/26/2015 16:40

 MSD Sample ID: 1293520 MSD
 Analysis Date: 09/26/2015 16:59

 Matrix: Soil/Solid (dry weight)

QC for Samples: 1155496001, 1155496003, 1155496004, 1155496005, 1155496006, 1155496007

# Results by SW8021B

results by GWGGZTB		Mat	rix Spike (ι	ıg/Kg)	Spike	Duplicate	(ug/Kg)			
<u>Parameter</u>	<u>Sample</u>	Spike	Result	Rec (%)	Spike	Result	Rec (%)	CL	RPD (%)	RPD CL
Benzene	11.4U	1464	1517	103	1464	1491	102	75-125	1.60	(< 20)
Ethylbenzene	22.6U	1464	1438	98	1464	1412	96	75-125	1.60	(< 20)
o-Xylene	22.6U	1464	1332	91	1464	1305	89	75-125	1.90	(< 20)
P & M -Xylene	45.3U	2929	2770	94	2929	2704	92	80-125	2.10	(< 20)
Toluene	22.6U	1464	1398	95	1464	1385	94	70-125	1.10	(< 20 )
Surrogates										
1,4-Difluorobenzene (surr)		1464	1346	91	1464	1346	92	72-119	0.39	

### **Batch Information**

Analytical Batch: VFC12695 Analytical Method: SW8021B Instrument: Agilent 7890A PID/FID

Analyst: CRD

Analytical Date/Time: 9/26/2015 4:40:00PM

Prep Batch: VXX27969

Prep Method: AK101 Extraction (S)
Prep Date/Time: 9/26/2015 8:00:00AM

Prep Initial Wt./Vol.: 56.19g Prep Extract Vol: 25.00mL

Print Date: 10/08/2015 11:54:19AM



Blank ID: MB for HBN 1721692 [VXX/27990]

Blank Lab ID: 1294495

QC for Samples:

1155496002, 1155496004

Matrix: Soil/Solid (dry weight)

# Results by AK101

ParameterResultsLOQ/CLDLUnitsGasoline Range Organics1.17J2.500.750mg/Kg

**Surrogates** 

4-Bromofluorobenzene (surr) 68 50-150 %

# **Batch Information**

Analytical Batch: VFC12702 Prep E
Analytical Method: AK101 Prep N

Instrument: Agilent 7890A PID/FID

Analyst: CRD
Analytical Date/Time: 9/30/2015 11:49:00PM

Prep Batch: VXX27990 Prep Method: SW5035A

Prep Date/Time: 9/30/2015 8:00:00AM

Prep Initial Wt./Vol.: 50 g Prep Extract Vol: 25 mL

Print Date: 10/08/2015 11:54:21AM



### **Blank Spike Summary**

Blank Spike ID: LCS for HBN 1155496 [VXX27990]

Blank Spike Lab ID: 1294498 Date Analyzed: 10/01/2015 00:45

QC for Samples: 1155496002, 1155496004 Spike Duplicate ID: LCSD for HBN 1155496

[VXX27990]

Spike Duplicate Lab ID: 1294499 Matrix: Soil/Solid (dry weight)

# Results by AK101

	E	Blank Spike	(mg/Kg)	s	pike Duplic	ate (mg/Kg)			
<u>Parameter</u>	Spike	Result	Rec (%)	<u>Spike</u>	Result	Rec (%)	CL	RPD (%)	RPD CL
Gasoline Range Organics	10.0	10.5	105	10.0	10.7	107	(60-120)	1.70	(< 20 )
Surrogates									
4-Bromofluorobenzene (surr)	1.25	76.4	76	1.25	74.2	74	(50-150)	2.90	

### **Batch Information**

Analytical Batch: VFC12702 Analytical Method: AK101

Instrument: Agilent 7890A PID/FID

Analyst: CRD

Prep Batch: VXX27990 Prep Method: SW5035A

Prep Date/Time: 09/30/2015 08:00

Spike Init Wt./Vol.: 10.0 mg/Kg Extract Vol: 25 mL Dupe Init Wt./Vol.: 10.0 mg/Kg Extract Vol: 25 mL

Print Date: 10/08/2015 11:54:22AM



Blank ID: MB for HBN 1721692 [VXX/27990]

Blank Lab ID: 1294495

QC for Samples:

1155496002, 1155496004

Matrix: Soil/Solid (dry weight)

# Results by SW8021B

D	D!t-	1.00/01	DI	11-24-
<u>Parameter</u>	<u>Results</u>	LOQ/CL	<u>DL</u>	<u>Units</u>
Benzene	6.25U	12.5	4.00	ug/Kg
Ethylbenzene	12.5U	25.0	7.80	ug/Kg
o-Xylene	12.5U	25.0	7.80	ug/Kg
P & M -Xylene	19.5J	50.0	15.0	ug/Kg
Toluene	12.5U	25.0	7.80	ug/Kg
Surrogates				
1.4-Difluorobenzene (surr)	87	72-119		%

### **Batch Information**

Analytical Batch: VFC12702 Analytical Method: SW8021B

Instrument: Agilent 7890A PID/FID

Analyst: CRD

Analytical Date/Time: 9/30/2015 11:49:00PM

Prep Batch: VXX27990 Prep Method: SW5035A

Prep Date/Time: 9/30/2015 8:00:00AM

Prep Initial Wt./Vol.: 50 g Prep Extract Vol: 25 mL

Print Date: 10/08/2015 11:54:24AM



### **Blank Spike Summary**

Blank Spike ID: LCS for HBN 1155496 [VXX27990]

Blank Spike Lab ID: 1294496 Date Analyzed: 10/01/2015 00:07

QC for Samples: 1155496002, 1155496004

Spike Duplicate ID: LCSD for HBN 1155496

[VXX27990]

Spike Duplicate Lab ID: 1294497 Matrix: Soil/Solid (dry weight)

# Results by SW8021B

	E	Blank Spike	(ug/Kg)	S	pike Duplic	ate (ug/Kg)			
<u>Parameter</u>	<u>Spike</u>	Result	Rec (%)	<u>Spike</u>	Result	Rec (%)	CL	RPD (%)	RPD CL
Benzene	1250	1400	112	1250	1400	112	(75-125)	0.02	(< 20 )
Ethylbenzene	1250	1310	105	1250	1320	106	(75-125)	0.49	(< 20 )
o-Xylene	1250	1200	96	1250	1210	97	(75-125)	0.66	(< 20 )
P & M -Xylene	2500	2550	102	2500	2560	102	(80-125)	0.42	(< 20 )
Toluene	1250	1350	108	1250	1350	108	(70-125)	0.20	(< 20 )
Surrogates									
1,4-Difluorobenzene (surr)	1250	90.8	91	1250	90	90	(72-119)	0.88	

# **Batch Information**

Analytical Batch: VFC12702 Analytical Method: SW8021B Instrument: Agilent 7890A PID/FID

Analyst: CRD

Prep Batch: VXX27990
Prep Method: SW5035A

Prep Date/Time: 09/30/2015 08:00

Spike Init Wt./Vol.: 1250 ug/Kg Extract Vol: 25 mL Dupe Init Wt./Vol.: 1250 ug/Kg Extract Vol: 25 mL

Print Date: 10/08/2015 11:54:26AM



### **Matrix Spike Summary**

Original Sample ID: 1155496002 MS Sample ID: 1294500 MS MSD Sample ID: 1294501 MSD

QC for Samples: 1155496002, 1155496004

Analysis Date: 10/01/2015 2:01
Analysis Date: 10/01/2015 2:20
Analysis Date: 10/01/2015 2:39
Matrix: Soil/Solid (dry weight)

# Results by SW8021B

		Mat	rix Spike (ι	ug/Kg)	Spike	Duplicate	(ug/Kg)			
<u>Parameter</u>	<u>Sample</u>	Spike	Result	Rec (%)	<u>Spike</u>	Result	Rec (%)	CL	RPD (%)	RPD CL
Benzene	21.1U	2436	2744	113	2436	2727	112	75-125	1.10	(< 20)
Ethylbenzene	42.3U	2436	2487	103	2436	2487	102	75-125	0.39	(< 20)
o-Xylene	207	2436	2659	101	2436	2642	100	75-125	1.10	(< 20)
P & M -Xylene	171	4871	4906	98	4871	4871	97	80-125	0.93	(< 20)
Toluene	42.3U	2436	2470	102	2436	2453	101	70-125	0.69	(< 20 )
Surrogates										
1,4-Difluorobenzene (surr)		2436	2213	91	2436	2196	91	72-119	0.22	

### **Batch Information**

Analytical Batch: VFC12702 Analytical Method: SW8021B Instrument: Agilent 7890A PID/FID

Analyst: CRD

Analytical Date/Time: 10/1/2015 2:20:00AM

Prep Batch: VXX27990

Prep Method: AK101 Extraction (S)
Prep Date/Time: 9/30/2015 8:00:00AM

Prep Initial Wt./Vol.: 44.09g Prep Extract Vol: 25.00mL

Print Date: 10/08/2015 11:54:27AM



Blank ID: MB for HBN 1721067 [XXX/34222]

Blank Lab ID: 1292912

QC for Samples:

1155496001, 1155496002, 1155496003, 1155496004, 1155496005, 1155496006

Results by AK102

LOQ/CL Results <u>Units</u> <u>Parameter</u> DL Diesel Range Organics 10.0U 20.0 6.20 mg/Kg

Matrix: Soil/Solid (dry weight)

**Surrogates** 

5a Androstane (surr) 79.1 60-120 %

**Batch Information** 

Analytical Batch: XFC12126 Prep Batch: XXX34222 Analytical Method: AK102 Prep Method: SW3550C

Instrument: HP 6890 Series II FID SV D R Prep Date/Time: 9/23/2015 4:43:36PM

Analyst: NLL Prep Initial Wt./Vol.: 30 g Prep Extract Vol: 1 mL

Analytical Date/Time: 10/3/2015 8:08:00PM

Print Date: 10/08/2015 11:54:29AM



### **Blank Spike Summary**

Blank Spike ID: LCS for HBN 1155496 [XXX34222]

Blank Spike Lab ID: 1292913

Date Analyzed: 10/03/2015 20:17

Spike Duplicate ID: LCSD for HBN 1155496

[XXX34222]

Spike Duplicate Lab ID: 1292914

Matrix: Soil/Solid (dry weight)

QC for Samples: 1155496001, 1155496002, 1155496003, 1155496004, 1155496005, 1155496006

# Results by AK102

	ВІ	Blank Spike (mg/Kg)			oike Duplic	ate (mg/Kg)			
<u>Parameter</u>	<u>Spike</u>	Result	Rec (%)	<u>Spike</u>	Result	Rec (%)	<u>CL</u>	RPD (%)	RPD CL
Diesel Range Organics	167	139	84	167	142	85	(75-125)	2.30	(< 20 )
Surrogates									
5a Androstane (surr)	3.33	87.5	88	3.33	88	88	(60-120)	0.56	

### **Batch Information**

Analytical Batch: **XFC12126** Analytical Method: **AK102** 

Instrument: HP 6890 Series II FID SV D R

Analyst: NLL

Prep Batch: XXX34222
Prep Method: SW3550C

Prep Date/Time: 09/23/2015 16:43

Spike Init Wt./Vol.: 167 mg/Kg Extract Vol: 1 mL Dupe Init Wt./Vol.: 167 mg/Kg Extract Vol: 1 mL

Print Date: 10/08/2015 11:54:31AM



Blank ID: MB for HBN 1721067 [XXX/34222]

Blank Lab ID: 1292912

QC for Samples:

1155496001, 1155496002, 1155496003, 1155496004, 1155496005, 1155496006

Results by AK103

ParameterResultsLOQ/CLDLUnitsResidual Range Organics10.0U20.06.20mg/Kg

Matrix: Soil/Solid (dry weight)

**Surrogates** 

n-Triacontane-d62 (surr) 89.2 60-120 %

**Batch Information** 

Analytical Batch: XFC12126 Prep Batch: XXX34222
Analytical Method: AK103 Prep Method: SW3550C

Instrument: HP 6890 Series II FID SV D R Prep Date/Time: 9/23/2015 4:43:36PM

Analyst: NLL Prep Initial Wt./Vol.: 30 g Analytical Date/Time: 10/3/2015 8:08:00PM Prep Extract Vol: 1 mL

Print Date: 10/08/2015 11:54:33AM



### **Blank Spike Summary**

Blank Spike ID: LCS for HBN 1155496 [XXX34222]

Blank Spike Lab ID: 1292913

Date Analyzed: 10/03/2015 20:17

Spike Duplicate ID: LCSD for HBN 1155496

[XXX34222]

Spike Duplicate Lab ID: 1292914

Matrix: Soil/Solid (dry weight)

QC for Samples: 1155496001, 1155496002, 1155496003, 1155496004, 1155496005, 1155496006

# Results by AK103

	E	Blank Spike (mg/Kg)			pike Duplic	ate (mg/Kg)			
<u>Parameter</u>	<u>Spike</u>	Result	Rec (%)	<u>Spike</u>	Result	Rec (%)	CL	RPD (%)	RPD CL
Residual Range Organics	167	167	100	167	168	101	(60-120)	0.71	(< 20 )
Surrogates									
n-Triacontane-d62 (surr)	3.33	83.7	84	3.33	85	85	(60-120)	1.60	

### **Batch Information**

Analytical Batch: **XFC12126** Analytical Method: **AK103** 

Instrument: HP 6890 Series II FID SV D R

Analyst: NLL

Prep Batch: XXX34222
Prep Method: SW3550C

Prep Date/Time: 09/23/2015 16:43

Spike Init Wt./Vol.: 167 mg/Kg Extract Vol: 1 mL Dupe Init Wt./Vol.: 167 mg/Kg Extract Vol: 1 mL

Print Date: 10/08/2015 11:54:34AM



SHANNON & W. Geotechnical and Environ		Cŀ	IAIN-(	OF-	Cl	JST(	ODY	RE	CORD	)	Laborator	ry <u>SGS</u>	Page of
(206) 632-8020 (314) 69	uis, MO 63146-3564 699-9660	2705 Saint A Pasco, WA 99 (509) 946-630		Suite A				Analysi <sup>.</sup>	is Parameters	s/Sample Cor preservative i	ntainer Desc		
Fairbanks, AK 99709 Anchora (907) 479-0600 (907) 56	airbanks Street, Suite 3 rage, AK 99518 561-2120	>			ı	//	// «	<u>~/</u>	3	DIESCIVALUO.	n useu)	//	7
Lake Oswego, OR 97035 Denver, (503) 223-6147 (303) 82	Sanneck-Street, Suite 200 r, CO 80204 825-3800		Date	18	0./3		0 0			* *20° *80°	/,	10 65 65 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
Sample Identity	Lab No.	Time	Sampled	Silver		<u>/ 4</u>	/ 🗸	<u>/ &amp;</u>	× / 65			\$\$CY	Remarks/Matrix
17747- AST4	QA-B	18:01	9/17/15	1 1	X	X	X	×			2		L
- AST4X	2A-B	18:04		$\perp \perp$	1		<u> </u>	1				1	
- AST 8	3A-B	17:13		<del>                                     </del>	11		<u> </u>						
- AST 9 422	1504-P	17:40		1	4	$\perp \!\!\! \perp \!\!\! \perp$	<u> </u>		$\perp \perp \perp$				
-AST 9x Cm	ENT-D	1745	_	++	#	=		$\vdash \vdash$				++-	
- AST 10	(5) A-B	17:05	<u> </u>	1	1		<u> </u>		$\perp \perp \parallel$				
-XPR3	(G)A-B	0935	9 118/15		4	<b>4</b>	<u> </u>		++			_   ↓	
-TB2 (	(T)A-15	09:55	9/18/18	<u>.                                     </u>	-			1	1 4			TPIP B	BLANK
	9/24/15			++	$\perp$			<u> </u>		<b></b>			
	, ,						<u>                                     </u>						
Project Information	Samp	ole Receip	t 📲	Rel	ing	uished	Bÿ:	<b>i</b>  ×	Relinqu	ished By	: 2.	Reling	uished By: 3.
Project Number: 32-1-1924			<del>                                     </del>	Signature:	) ->	Ti	Time: <u>/ひ</u> こ	<u>&gt;/</u> Si	ignature:	Time:_	- 1	signature.	Time:
Project Name: Pitkas Point Contact: TMT, TWC			,	Printed Na		<u>5</u>	Date: 9h1	JE P	rinted Name:	Date:_		Printed Name:	Date:
Ongoing Project? Yes No	Received Good Delivery Metho			I Novo		cross	<u>52</u>	<u></u>	````				
Sampler: TWC	(attach shipping	bill, if any)		Sw.				٦	Company:			Company:	
in a line	structions		5.扩展 5	30 to 80 to 193	A Steel	ed By:			Receive	ed By:	2:	Receiv	red Bv: 3.
	STANDARD	Self-major de attack à part, que su	S	Signature:	The state of the s	50 C C C C C C C C C C C C C C C C C C C	rime:	DESCRIPTION STATE	ignaturo:	Time:		igrature:	Time: 1001
Special Instructions:  LEVEL 2			F	Printed Na	ame:		Date:	P	rinted Name:	Date: _		Printed Name:	Date: 9/22/5
				<u> </u>								Dana	Chia
Distribution: White - w/shipment - ret Yellow - w/shipment - fo Pink - Shannon & Wilson	for consignee files	Ison w/ laborato	ory report	Company:	:		$\leq$	Co	Company:			Company:	1.4°/D2



# 1155496



# SAMPLE RECEIPT FORM

Review Criteria:	Yes	N/A	No	Comments/Action Taken:
Were <b>custody seals</b> intact? Note # & location, if applicable. COC accompanied samples?	<b>\</b>	V		Exemption permitted if sampler hand carries/delivers.
<b>Temperature blank</b> compliant* (i.e., 0-6°C after CF)?	7			Exemption permitted if chilled & collected <8 hrs ago.
If >6°C, were samples collected <8 hours ago?	Ħ	7	Ħ	
If $< 0$ °C, were all sample containers ice free?		$\overline{\mathbf{V}}$		
Cooler ID: 1 @ 1.4 w/ Therm.ID: D2				
Cooler ID:				
Cooler ID: (a) w/ Therm.ID:				
Cooler ID: w/ Therm.ID:				
Cooler ID: (a) w/ Therm.ID:				
If samples are received without a temperature blank, the "cooler				
temperature" will be documented in lieu of the temperature blank &				
"COOLER TEMP" will be noted to the right. In cases where neither a				Note: Identify containers received at non-compliant temperature. Use form FS-0029 if more space is needed.
temp blank <u>nor</u> cooler temp can be obtained, note "ambient" or "chilled."				temperature. Ose form 1 5-0025 if more space is nectical.
Delivery method (specify all that apply): ☑Client (hand carried) ☐USPS ☐ Lynden ☐AK Air ☐ Alert Courier				
UPS FedEx RAVN C&D Delivery				
□Carlile □Pen Air □Warp Speed□Other:				
→ For WO# with airbills, was the WO# & airbill				
info recorded in the Front Counter eLog?	П	<b>V</b>	П	
. ,				
W	Yes	N/A	No	N. D.C. C. DODGE J.C. I. W. J. J.C.
Were samples received within hold time?		Н	$\square$	Note: Refer to form F-083 "Sample Guide" for hold times. Note: If times differ <1hr, record details and login per COC.
Do samples <b>match COC*</b> (i.e., sample IDs, dates/times collected)?	<u> </u>	H	$\vdash$	Trote. If times utifier Am, record details and togin per coc.
Were analyses requested unambiguous?		╫	₩	
Were samples in <b>good condition</b> (no leaks/cracks/breakage)?	$\checkmark$	Ш	Ш	
Packing material used (specify all that apply): Bubble Wrap				
Separate plastic bags Vermiculite Other:  Were <b>proper containers</b> (type/mass/volume/preservative*) used?		$\overline{}$		Exemption permitted for metals (e.g., 200.8/6020A).
Were <b>Trip Blanks</b> (i.e., VOAs, LL-Hg) in cooler with samples?	<del></del>	Н	H	Exemption permitted for metals (e.g., 200.0/0020A).
Were all VOA vials <b>free of headspace</b> (i.e., bubbles <6 mm)?		<b>V</b>	H	
Were all soil VOAs field extracted with MeOH+BFB?			H	
For preserved waters (other than VOA vials, LL-Mercury or	<u></u>			
microbiological analyses), was <b>pH verified and compliant</b> ?		7		
If pH was adjusted, were bottles flagged (i.e., stickers)?	ıĦ	7	Ħ	
For <b>special handling</b> (e.g., "MI" soils, foreign soils, lab filter for		<u> </u>		
dissolved, lab extract for volatiles, Ref Lab, limited volume),				
were bottles/paperwork flagged (e.g., sticker)?	П	$\checkmark$		
For RUSH/SHORT Hold Time, were COC/Bottles flagged	_			
accordingly? Was Rush/Short HT email sent, if applicable?	П	$\checkmark$		
For SITE-SPECIFIC QC, e.g. BMS/BMSD/BDUP, were				
containers / paperwork flagged accordingly?		$\checkmark$		
For any question answered "No," has the PM been notified and				SRF Completed by: D.C 09/22/2015
the problem resolved (or paperwork put in their bin)?		$\checkmark$		PM notified:
Was PEER REVIEW of sample numbering/labeling completed?	<b>/</b>			Peer Reviewed by: VDL
Additional notes (if applicable):				
On water Other and the few On and the sear OOO. Not the				
Sample 8 logged in for Generic per COC. Not to be ana	ilyzed	ı, per	clien	request.
D.C 09/22/2015				
Note to Client: Any "no" answer above indicates non-comp	liance	with s	tanda	rd procedures and may impact data quality.



# **Sample Containers and Preservatives**

Container Id	<u>Preservative</u>	Container Condition	Container Id	Preservative	Container Condition
1155496001-A	No Preservative Required	OK			
1155496001-B	Methanol field pres. 4 C	OK			
1155496002-A	No Preservative Required	OK			
1155496002-B	Methanol field pres. 4 C	OK			
1155496003-A	No Preservative Required	OK			
1155496003-B	Methanol field pres. 4 C	OK			
1155496004-A	No Preservative Required	OK			
1155496004-B	Methanol field pres. 4 C	OK			
1155496005-A	No Preservative Required	OK			
1155496005-B	Methanol field pres. 4 C	OK			
1155496006-A	No Preservative Required	OK			
1155496006-B	Methanol field pres. 4 C	OK			
1155496007-A	Methanol field pres. 4 C	OK			
1155496008-A	No Preservative Required	OK			
1155496008-B	Methanol field pres. 4 C	OK			

# Container Condition Glossary

Containers for bacteriological, low level mercury and VOA vials are not opened prior to analysis and will be assigned condition code OK unless evidence indicates than an inappropriate container was submitted.

- OK The container was received at an acceptable pH for the analysis requested.
- PA The container was received outside of the acceptable pH for the analysis requested. Preservative was added upon receipt and the container is now at the correct pH. See the Sample Receipt Form for details on the amount and lot # of the preservative added.
- PH The container was received outside of the acceptable pH for the analysis requested. Preservative was added upon receipt, but was insufficient to bring the container to the correct pH for the analysis requested. See the Sample Receipt Form for details on the amount and lot # of the preservative added.
- BU The container was received with headspace greater than 6mm.

9/22/2015 37 of 37

# LABORATORY DATA REVIEW CHECKLIST

Completed by: Trevor Crosby Title: Environmental Scientist

**Date:** October 30, 2015

CS Report Name: Site Assessment, Pitkas Point School Site, Pitkas Point, Alaska

**Laboratory Report Date:** October 8, 2015

Consultant Firm: Shannon & Wilson, Inc.

**Laboratory Name:** SGS North America Inc. **Laboratory Report Number:** 1155496

**ADEC File Number:** 2444.57.001 **ADEC Hazard ID Number:** 26405

(**NOTE**: *NA* = not applicable; Text in *italics* added by Shannon & Wilson, Inc.)

# 1. <u>Laboratory</u>

a. Did an ADEC CS approved laboratory receive and <u>perform</u> all of the submitted sample analyses? Yes/ No / NA

Comments: Yes, SGS North America, Inc. (SGS) received the samples and performed submitted sample analyses.

**b.** If the samples were transferred to another "network" laboratory or sub-contracted to an alternate laboratory, was the laboratory performing the analyses ADEC CS-approved? **Yes / No NA** 

Comments: The samples were not transferred to another "network" laboratory or subcontracted to an alternate laboratory.

# 2. Chain of Custody (COC)

**a.** COC information completed, signed, and dated (including released/received by)? **Yes/ No / NA** 

Comments:

**b.** Correct analyses requested? Yes / No / NA Comments:

# 3. Laboratory Sample Receipt Documentation

a. Sample/cooler temperature documented and within range at receipt  $(4^{\circ} \pm 2^{\circ} \text{ C})$ ? Yes (No) NA

Comments: The cooler temperature was 1.4° C upon receipt at SGS.

- **b.** Sample preservation acceptable acidified waters, Methanol-preserved VOC soil (GRO, BTEX, VOCs, etc.)? **Yes/ No / NA**
- c. Sample condition documented broken, leaking (soil MeOH), zero headspace (VOC vials)? Yes/No/NA
  Comments: SGS specifies that samples were received in good condition on the Sample Receipt Form (SRF).
- **d.** If there were any discrepancies, were they documented (e.g., incorrect sample containers/preservation, sample temperatures outside range, insufficient sample size, missing samples)? **Yes/No/NA**Comments: *The cooler temperature was outside the QC range at SGS*.
- **e.** Data quality or usability affected? Please explain. Comments: Although the cooler temperature was less than the QC range, the sample receipt form does not indicated that the samples were frozen. Therefore, data quality/usability is considered unaffected.

# 4. Case Narrative

- a. Present and understandable? Yes/ No / NA Comments:
- **b.** Discrepancies, errors or QC failures noted by the lab? Yes / No / NA Comments: *The following QC failures were noted by the lab:* 
  - RRO surrogate n-triacontane recovery for Project Samples AST4 and AST4X (Duplicate Sample of AST4) is biased high due to sample matrix;
  - GRO surrogate 4-bromofluorobenzene (BFB) recovery for Project Sample AST9 is outside QC criteria (biased low). Sample was analyzed twice for confirmation;
  - DRO surrogate 5a-androstane recovery for Project Sample AST9 is outside QC criteria (biased low) due to sample dilution.
- **c.** Were corrective actions documented? **Yes**/**No**/**NA**Comments: The case narrative notes that Sample AST9 was analyzed twice for GRO to confirm results.
- **d.** What is the effect on data quality/usability, according to the case narrative? Comments: *The case narrative does not comment on the data quality/usability*.

# 5. Sample Results

a. Correct analyses performed/reported as requested on COC? Yes / No / NA (please explain)
 Comments:

- **b.** All applicable holding times met? Yes / No / NA Comments:
- c. All soils reported on a dry-weight basis? **Yes** No / NA Comments:
- d. Are the reported LOQs less than the Cleanup Level or the minimum required detection level for the project? Yes / No / NA

  Comments: LOQs and reporting limits are less than cleanup levels where applicable (for non-detect results)
- e. Data quality or usability affected? NA Comments:

# 6. QC Samples

### a. Method Blank

- i. One method blank reported per matrix, analysis, and 20 samples?Yes/ No / NAComments:
- ii. All method blank results less than LOQ? Yes/No/NA
  Comments: However, GRO, P&M-xylene, and toluene were detected at estimated concentrations of 1.01 mg/kg, 0.0155 mg/kg, and 0.0125 mg/kg, respectively in the method blank for Project Samples AST4, AST8, AST9, AST10, PR3, and Trip Blank 2. GRO and P&M-xylene were detected at estimated concentrations of 1.17 mg/kg and 0.0195 mg/kg, respectively in a second method blank for Project Samples AST4X and AST9. Method blank detections of P&M xylene and GRO results for AST9 were 0.0155 mg/kg and 1.17 mg/kg, respectively.
- **iii.** If above LOQ, what samples are affected? Comments: *See above*.
- iv. Do the affected sample(s) have data flags? Yes No / NA

  Comments: The estimated GRO results in Project Samples AST8, AST9, and AST10

  are within 5 times the amounts found in the method blank and are considered non

  detect at the LOQ, flagged 'B' in Table 2 of the report. The estimated toluene result

  in Project Sample AST4 is within 5 times the amount found in the method blank and is

  considered non detect at the LOQ, flagged 'B' in Table 2 of the report. The P&M
  xylene result for AST4X is within 10 times the method blank and flagged 'B' in Table
  2 of the report.

If so, are the data flags clearly defined? **Yes**/**No**/**NA** Comments: *See above*.

v. Data quality or usability affected? Yes / No NA Comments: See above.

# b. Laboratory Control Sample/Duplicate (LCS/LCSD)

- i. Organics One LCS/LCSD reported per matrix, analysis, and 20 samples? (LCS/LCSD required per AK methods, LCS required per SW846) Yes No / NA Comments: One LCS/LCSD pair reported per analysis and 20 samples for GRO, DRO, RRO, and BTEX analyses.
- ii. Metals/Inorganics One LCS and one sample duplicate reported per matrix, analysis and 20 samples? Yes / No NA Comments: *Inorganic analyses not performed*.
- iii. Accuracy All percent recoveries (%R) reported *and within method or laboratory limits?* And project specified DQOs, if applicable. (AK petroleum methods: AK101 60%-120%, AK102 75%-125%, AK103 60%-120%; all other analyses see the laboratory QC pages) Yes No / NA Comments:
- iv. Precision All relative percent differences (RPDs) reported and less than method or laboratory limits? And project specified DQOs, if applicable. RPD reported from LCS/LCSD, MS/MSD, and or sample/sample duplicate. (AK Petroleum methods 20%; all other analyses see the laboratory QC pages) Yes/No/NA (please explain) Comments:
- v. If %R or RPD is outside of acceptable limits, what samples are affected? NA Comments: See above.
- vi. Do the affected samples(s) have data flags? Yes / No (NA) Comments: See above.

If so, are the data flags clearly defined? **Yes / No NA** Comments: *See above.* 

vii. Data quality or usability affected? Explain. NA Comments: See above.

# c. Surrogates - Organics Only

i. Are surrogate recoveries reported for organic analyses, field, QC, and laboratory samples? Yes/ No / NA
Comments:

- ii. Accuracy All percent recoveries (%R) reported and within method or laboratory limits? And project specified DQOs if applicable. (AK Petroleum methods 50-150 %R; all other analyses see the laboratory report pages) Yes No NA Comments: Recovery of RRO surrogate n-triacontane in Project Samples AST4 and AST4X is above QC criteria due to sample matrix. Recovery of GRO surrogate 4-bromofluorobenzene (BFB) recovery for Project Sample AST9 is outside QC criteria biased low. Recovery of DRO surrogate 5a-androstane recovery for Project Sample AST9 is outside QC criteria biased low due to sample dilution.
- iii. Do the sample results with failed surrogate recoveries have data flags? Yes No / NA Comments: RRO results for Samples AST4 and AST4X are flagged "J+". GRO results for Sample AST9 are 'B' flagged due to the method blank detection. DRO results for Sample AST9 are considered unaffected because the surrogate percent recovery failure was due to sample dilution.

If so, are the data flags clearly defined? **Yes**/**No**/**NA** Comments: *See above*.

- iv. Data quality or usability affected? Explain. Yes/No/NA
  Comments: The associated RRO results are considered a biased high estimate and flagged "J+" in Table 2 of the Report. Because the reported result is less than the ADEC cleanup level, potentially high bias should not affect the data usability for this project.
- **d. Trip Blank** Volatile analyses only (GRO, BTEX, VOCs, etc.) <u>Water</u>
  - i. One trip blank reported per matrix, analysis and cooler? Yes/ No / NA Comments:
  - ii. Is the cooler used to transport the trip blank and volatile samples clearly indicated on the COC? Yes / No NA Comments: Only one cooler was submitted to the laboratory.
  - iii. All results less than LOQ? Yes / No / NA Comments:
  - iv. If above LOQ, what samples are affected? NA Comments:
  - v. Data quality or usability affected? Explain. NA Comments: *See above*.

# e. Field Duplicate

i. One field duplicate submitted per matrix, analysis and 10 project samples?

Yes/ No / NA

Comments: A field duplicate was submitted per 10 project samples for CPA

Comments: A field duplicate was submitted per 10 project samples for GRO, DRO, RRO, and BTEX analysis.

- ii. Were the field duplicates submitted blind to the lab? Yes/No/NA Comments: Sample AST4X is a field duplicate of AST4.
- iii. Precision All relative percent differences (RPDs) less than specified DQOs? (Recommended: 30% for water, 50% for soil) Yes/No/NA Comments: RPD for total xylenes is greater than 50% (105%). RPDs for GRO, DRO, and RRO were less than the DQOs. Benzene, toluene, and ethylbenzene analytes could not be calculated due to non-detect results for the primary and/or duplicate samples.
- iv. Data quality or usability affected? Explain. (NA)

  Comments: The RPD failure is likely due to non-homogeneous distribution of contaminants in the soil. For total xylenes, both primary and duplicate concentrations are less than the most stringent ADEC Method Two cleanup level. Therefore, the results are considered usable for the purpose of this project.
- **f. Decontamination or Equipment Blank** (if not applicable, a comment stating why must be entered below)

**Yes** / **No** (NA) Collecting and submitting a decontamination or equipment blank was not included in the ADEC-approved project scope.

- i. All results less than LOQ? Yes / No NA Comments: See above.
- ii. If results are above LOQ, what samples are affected? NA Comments: See above.
- **iii.** Data quality or usability affected? Explain. **NA** Comments: *See above*.

# 7. Other Data Flags/Qualifiers (ACOE, AFCEE, Lab-specific, etc.)

a. Are they defined and appropriate? Yes / No / NA Comments: Laboratory-applied data flags are defined on page 3 of the SGS report.



### **Laboratory Report of Analysis**

To: Shannon & Wilson, Inc.

5430 Fairbanks Street, Ste 3 Anchorage, AK 99518

907-561-2120

Report Number: 1155497

Client Project: 32-1-17747 Pitkas Point

Dear Tim Terry,

Enclosed are the results of the analytical services performed under the referenced project for the received samples and associated QC as applicable. The samples are certified to meet the requirements of the National Environmental Laboratory Accreditation Conference Standards. Copies of this report and supporting data will be retained in our files for a period of ten years in the event they are required for future reference. All results are intended to be used in their entirety and SGS is not responsible for use of less than the complete report. Any samples submitted to our laboratory will be retained for a maximum of fourteen (14) days from the date of this report unless other archiving requirements were included in the quote.

If there are any questions about the report or services performed during this project, please call Victoria at (907) 562-2343. We will be happy to answer any questions or concerns which you may have.

Thank you for using SGS North America Inc. for your analytical services. We look forward to working with you again on any additional analytical needs.

Sincerely,

SGS North America Inc.

Victoria Pennick

2015.10.27

15:31:59 -08'00'

Victoria Pennick

Date

Project Manager

Victoria.Pennick@sgs.com

Print Date: 10/27/2015 1:51:41PM



#### **Case Narrative**

SGS Client: **Shannon & Wilson, Inc.**SGS Project: **1155497**Project Name/Site: **32-1-17747 Pitkas Point**Project Contact: **Tim Terry** 

Refer to sample receipt form for information on sample condition.

### 17747-PPS10-D (1155497003) PS

AK101 - Surrogate recovery for 4-bromofluorobenzene (328%) does not meet QC criteria due to matrix interference.

#### 17747-PPS10-1-B (1155497004) PS

AK102/103 - Surrogate recoveries for 5a androstane (0%) and n-triacontane (0%) do not meet QC criteria due to sample dilution (20X).

10/16/15: amended collection time per client request.

### 17747-PPS10-3-D (1155497006) PS

AK101 - Surrogate recovery for 4-bromofluorobenzene (340%) does not meet QC criteria due to matrix interference.

#### 17747-PPS10-3-DX (1155497007) PS

AK101 - Surrogate recovery for 4-bromofluorobenzene (237%) does not meet QC criteria due to matrix interference.

### 17747-PPS13-C (1155497011) PS

10/16/15: Amended to correct sample ID and date/time of collection.

### 17747-PPS12-3-C (1155497013) PS

10/16/15: Amended to correct sample ID and date/time of collection, and add DRO/RRO + DRO/RRO SiGel.. AK102/103 - Sample was analyzed past the 14 day hold time.

\*QC comments may be associated with the field samples found in this report. When applicable, comments will be applied to associated field samples.

Print Date: 10/27/2015 1:51:43PM



### **Laboratory Qualifiers**

Enclosed are the analytical results associated with the above work order. All results are intended to be used in their entirety and SGS is not responsible for use of less than the complete report. This document is issued by the Company under its General Conditions of Service accessible at <a href="http://www.sgs.com/en/Terms-and-Conditions.aspx">http://www.sgs.com/en/Terms-and-Conditions.aspx</a>. Attention is drawn to the limitation of liability, indenmification and jurisdiction issues defined therein.

Any holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. Any unauthorized alteration, forgery or falsification of the context or appearance of this document is unlawful and offenders may be prosecuted to the fullest extent of the law.

SGS maintains a formal Quality Assurance/Quality Control (QA/QC) program. A copy of our Quality Assurance Plan (QAP), which outlines this program, is available at your request. The laboratory certification numbers are AK00971 (DW Chemistry & Microbiology) & UST-005 (CS) for ADEC and 2944.01 for DOD ELAP/ISO17025 (RCRA methods: 1020B, 1311, 3010A, 3050B, 3520C, 3550C, 5030B, 5035A, 6020A, 7470A, 7471B, 8021B, 8082A, 8260B, 8270D, 8270D-SIM, 9040C, 9045D, 9056A, 9060A, AK101 and AK102/103). Except as specifically noted, all statements and data in this report are in conformance to the provisions set forth by the SGS QAP and, when applicable, other regulatory authorities.

The following descriptors or qualifiers may be found in your report:

\* The analyte has exceeded allowable regulatory or control limits.

! Surrogate out of control limits.

B Indicates the analyte is found in a blank associated with the sample.

CCV/CVA/CVB Continuing Calibration Verification

CCCV/CVC/CVCA/CVCB Closing Continuing Calibration Verification

CL Control Limit

D The analyte concentration is the result of a dilution.

DF Dilution Factor

DL Detection Limit (i.e., maximum method detection limit)
E The analyte result is above the calibrated range.
F Indicates value that is greater than or equal to the DL

GT Greater Than
IB Instrument Blank

ICV Initial Calibration Verification

J The quantitation is an estimation.

JL The analyte was positively identified, but the quantitation is a low estimation.

LCS(D) Laboratory Control Spike (Duplicate)
LOD Limit of Detection (i.e., 1/2 of the LOQ)

LOQ Limit of Quantitation (i.e., reporting or practical quantitation limit)

LT Less Than

M A matrix effect was present.

MB Method Blank

MS(D) Matrix Spike (Duplicate)

ND Indicates the analyte is not detected.
Q QC parameter out of acceptance range.

R Rejected

RPD Relative Percent Difference

U Indicates the analyte was analyzed for but not detected.

Note: Sample summaries which include a result for "Total Solids" have already been adjusted for moisture content.

All DRO/RRO analyses are integrated per SOP.

Print Date: 10/27/2015 1:51:44PM

SGS North America Inc. 200 West Potter Drive, Anchorage, AK 99518



### Sample Summary

Client Sample ID	Lab Sample ID	Collected	Received	<u>Matrix</u>
17747-PPS1/PPS11-B	1155497001	09/17/2015	09/22/2015	Soil/Solid (dry weight)
17747-PPS1/PPS11-3-A	1155497002	09/17/2015	09/22/2015	Soil/Solid (dry weight)
17747-PPS10-D	1155497003	09/17/2015	09/22/2015	Soil/Solid (dry weight)
17747-PPS10-1-B	1155497004	09/17/2015	09/22/2015	Soil/Solid (dry weight)
17747-PPS10-2-D	1155497005	09/17/2015	09/22/2015	Soil/Solid (dry weight)
17747-PPS10-3-D	1155497006	09/17/2015	09/22/2015	Soil/Solid (dry weight)
17747-PPS10-3-DX	1155497007	09/17/2015	09/22/2015	Soil/Solid (dry weight)
17747-PPS10-4-B	1155497008	09/17/2015	09/22/2015	Soil/Solid (dry weight)
17747-PPS12-C	1155497009	09/17/2015	09/22/2015	Soil/Solid (dry weight)
17747-PPS12-2-A	1155497010	09/17/2015	09/22/2015	Soil/Solid (dry weight)
17747-PPS13-C	1155497011	09/17/2015	09/22/2015	Soil/Solid (dry weight)
17747-PPS12-3-CX	1155497012	09/17/2015	09/22/2015	Soil/Solid (dry weight)
17747-PPS12-3-C	1155497013	09/17/2015	09/22/2015	Soil/Solid (dry weight)
17747-PPS13-1-A	1155497014	09/17/2015	09/22/2015	Soil/Solid (dry weight)
17747-PPS13-2-B	1155497015	09/17/2015	09/22/2015	Soil/Solid (dry weight)
17747-TF1	1155497016	09/17/2015	09/22/2015	Soil/Solid (dry weight)
17747-TF2	1155497017	09/17/2015	09/22/2015	Soil/Solid (dry weight)
17747-TB1	1155497018	09/17/2015	09/22/2015	Soil/Solid (dry weight)

 Method
 Method Description

 AK101
 AK101/8021 Combo. (S)

 SW8021B
 AK101/8021 Combo. (S)

 AK102
 Diesel/Residual Range Or

AK102 Diesel/Residual Range Organics
AK103 Diesel/Residual Range Organics

AK102 Diesel/Residual Range Organics w/ Silica
AK103 Diesel/Residual Range Organics w/ Silica

SM21 2540G Percent Solids SM2540G



# **Detectable Results Summary**

Client Sample ID: 17747-PPS1/PPS11-E	3		
Lab Sample ID: 1155497001	<u>Parameter</u>	Result	<u>Units</u>
Semivolatile Organic Fuels	Diesel Range Organics	50.6	mg/Kg
	Residual Range Organics	316	mg/Kg
Volatile Fuels	Ethylbenzene	23.7J	ug/Kg
	Gasoline Range Organics	4.41J	mg/Kg
	P & M -Xylene	32.6J	ug/Kg
Client Sample ID: 17747-PPS1/PPS11-3	s- <b>A</b>		
Lab Sample ID: 1155497002	<u>Parameter</u>	Result	<u>Units</u>
Semivolatile Organic Fuels	Diesel Range Organics	11.4J	mg/Kg
	Residual Range Organics	123	mg/Kg
Volatile Fuels	Gasoline Range Organics	1.66J	mg/Kg
	P & M -Xylene	25.8J	ug/Kg
	Toluene	20.0J	ug/Kg
Client Sample ID: 17747-PPS10-D			
Lab Sample ID: 1155497003	<u>Parameter</u>	Result	<u>Units</u>
Semivolatile Organic Fuels	Diesel Range Organics	9430	mg/Kg
•	Residual Range Organics	61.1	mg/Kg
Volatile Fuels	Ethylbenzene	117	ug/Kg
	Gasoline Range Organics	64.3	mg/Kg
	o-Xylene	4100	ug/Kg
	P & M -Xylene	1450	ug/Kg
	Toluene	255	ug/Kg
Client Sample ID: 17747-PPS10-1-B			
Lab Sample ID: 1155497004	<u>Parameter</u>	Result	<u>Units</u>
Semivolatile Organic Fuels	Diesel Range Organics	1800	mg/Kg
-	Residual Range Organics	1560	mg/Kg
Volatile Fuels	Gasoline Range Organics	5.36J	mg/Kg
	o-Xylene	62.3	ug/Kg
	P & M -Xylene	59.9J	ug/Kg
Client Sample ID: 17747-PPS10-2-D			
Lab Sample ID: 1155497005	<u>Parameter</u>	Result	<u>Units</u>
Semivolatile Organic Fuels	Diesel Range Organics	2500	mg/Kg
J	Residual Range Organics	110	mg/Kg
Volatile Fuels	Gasoline Range Organics	4.53	mg/Kg
	o-Xylene	62.4	ug/Kg
	P & M -Xylene	27.6J	ug/Kg

Print Date: 10/27/2015 1:51:46PM

SGS North America Inc.



# **Detectable Results Summary**

Client Sample ID: 17747-PPS10-3-D			
Lab Sample ID: 1155497006	<u>Parameter</u>	Result	<u>Units</u>
Semivolatile Organic Fuels	Diesel Range Organics	888	mg/Kg
_	Residual Range Organics	63.7	mg/Kg
Semivolatile Organic Fuels Departme	nt, SilicaDRO Silica Gel	795	mg/Kg
-	RRO Silica Gel	30.3J	mg/Kg
Volatile Fuels	Ethylbenzene	53.6	ug/Kg
	Gasoline Range Organics	20.5	mg/Kg
	o-Xylene	517	ug/Kg
	P & M -Xylene	126	ug/Kg
Client Sample ID: 17747-PPS10-3-DX			
Lab Sample ID: 1155497007	<u>Parameter</u>	Result	<u>Units</u>
Semivolatile Organic Fuels	Diesel Range Organics	1180	mg/Kg
-	Residual Range Organics	35.9J	mg/Kg
Semivolatile Organic Fuels Departme	nt, SilicaDRO Silica Gel	1110	mg/Kg
	RRO Silica Gel	35.4J	mg/Kg
Volatile Fuels	Ethylbenzene	27.7	ug/Kg
	Gasoline Range Organics	10.2	mg/Kg
	o-Xylene	242	ug/Kg
	P & M -Xylene	72.3	ug/Kg
Client Sample ID: 17747-PPS10-4-B			
Lab Sample ID: 1155497008	<u>Parameter</u>	<u>Result</u>	<u>Units</u>
Semivolatile Organic Fuels	Residual Range Organics	64.5	mg/Kg
Volatile Fuels	Gasoline Range Organics	1.88J	mg/Kg
Client Sample ID: 17747-PPS12-C			
Lab Sample ID: 1155497009	Parameter	Result	<u>Units</u>
Semivolatile Organic Fuels	Diesel Range Organics	27.1	mg/Kg
•	Residual Range Organics	230	mg/Kg
Volatile Fuels	Gasoline Range Organics	2.78J	mg/Kg
Client Sample ID: 17747-PPS12-2-A			
Lab Sample ID: 1155497010	Parameter	Result	Units
Semivolatile Organic Fuels	Diesel Range Organics	19.0J	mg/Kg
•	Residual Range Organics	155	mg/Kg
Volatile Fuels	Gasoline Range Organics	1.78J	mg/Kg
Client Sample ID: 17747-PPS13-C			
Lab Sample ID: 1155497011	<u>Parameter</u>	Result	<u>Units</u>
Semivolatile Organic Fuels	Diesel Range Organics	27.3J	mg/Kg
-	Residual Range Organics	232	mg/Kg
Semivolatile Organic Fuels Departme	nt, SilicaDRO Silica Gel	18.7J	mg/Kg
·	RRO Silica Gel	81.7	mg/Kg

Print Date: 10/27/2015 1:51:46PM

200 West Potter Drive, Anchorage, AK 99518 t 907.562.2343 f 907.561.5301 www.us.sgs.com



# **Detectable Results Summary**

Client Sample ID: 17747-PPS12-3-CX			
Lab Sample ID: 1155497012	<u>Parameter</u>	Result	<u>Units</u>
Semivolatile Organic Fuels	Diesel Range Organics	510	mg/Kg
	Residual Range Organics	631	mg/Kg
Semivolatile Organic Fuels Department, Si	<b>lica</b> DRO Silica Gel	301	mg/Kg
	RRO Silica Gel	167	mg/Kg
Volatile Fuels	Gasoline Range Organics	2.91J	mg/Kg
Client Sample ID: 17747-PPS12-3-C			
Lab Sample ID: 1155497013	<u>Parameter</u>	<u>Result</u>	<u>Units</u>
Semivolatile Organic Fuels	Diesel Range Organics	317	mg/Kg
	Residual Range Organics	488	mg/Kg
Semivolatile Organic Fuels Department, Si	<b>lica</b> DRO Silica Gel	155	mg/Kg
	RRO Silica Gel	86.5	mg/Kg
Client Sample ID: 17747-PPS13-1-A			
Lab Sample ID: 1155497014	<u>Parameter</u>	<u>Result</u>	<u>Units</u>
Semivolatile Organic Fuels	Diesel Range Organics	18.7J	mg/Kg
	Residual Range Organics	189	mg/Kg
Volatile Fuels	Gasoline Range Organics	3.30J	mg/Kg
Client Sample ID: 17747-PPS13-2-B			
Lab Sample ID: 1155497015	Parameter	Result	Units
Semivolatile Organic Fuels	Residual Range Organics	67.8	mg/Kg
Volatile Fuels	Gasoline Range Organics	1.88J	mg/Kg
Client Sample ID: 17747-TF1			
Lab Sample ID: 1155497016	Parameter	Result	<u>Units</u>
Semivolatile Organic Fuels	Diesel Range Organics	19.5J	mg/Kg
•	Residual Range Organics	141	mg/Kg
Volatile Fuels	Gasoline Range Organics	3.62J	mg/Kg
Client Sample ID: 17747-TF2			
Lab Sample ID: 1155497017	<u>Parameter</u>	Result	Units
Semivolatile Organic Fuels	Diesel Range Organics	849	mg/Kg
<b>3</b>	Residual Range Organics	164	mg/Kg
Volatile Fuels	Gasoline Range Organics	2.68J	mg/Kg
Client Sample ID: 17747-TB1			
Lab Sample ID: 1155497018	Parameter	Result	Units
Volatile Fuels	P & M -Xylene	17.1J	ug/Kg
	Toluene	15.6J	ug/Kg
	<del>-</del>		33

Print Date: 10/27/2015 1:51:46PM



# Results of 17747-PPS1/PPS11-B

Client Sample ID: 17747-PPS1/PPS11-B
Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497001 Lab Project ID: 1155497 Collection Date: 09/17/15 08:32 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):72.2 Location:

# Results by Semivolatile Organic Fuels

Parameter Diesel Range Organics	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	Allowable	Date Analyzed
	50.6	27.5	8.51	mg/Kg	1	Limits	10/04/15 02:44
Surrogates 5a Androstane (surr)	76.3	50-150		%	1		10/04/15 02:44

### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK102

Analyst: NLL

Analytical Date/Time: 10/04/15 02:44 Container ID: 1155497001-A Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.271 g Prep Extract Vol: 1 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	316	27.5	8.51	mg/Kg	1		10/04/15 02:44
Surrogates							
n-Triacontane-d62 (surr)	95.3	50-150		%	1		10/04/15 02:44

#### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK103

Analyst: NLL

Analytical Date/Time: 10/04/15 02:44 Container ID: 1155497001-A Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.271 g Prep Extract Vol: 1 mL



# Results of 17747-PPS1/PPS11-B

Client Sample ID: 17747-PPS1/PPS11-B Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497001 Lab Project ID: 1155497

Collection Date: 09/17/15 08:32 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):72.2 Location:

# Results by Volatile Fuels

<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	Allowable Limits	Date Analyzed
Gasoline Range Organics	4.41 J	4.94	1.48	mg/Kg	1		09/24/15 20:06
Surrogates 4-Bromofluorobenzene (surr)	85.3	50-150		%	1		09/24/15 20:06

### **Batch Information**

Analytical Batch: VFC12692 Analytical Method: AK101 Analyst: CRD

Analytical Date/Time: 09/24/15 20:06

Container ID: 1155497001-B

Prep Batch: VXX27961 Prep Method: SW5035A Prep Date/Time: 09/17/15 08:32 Prep Initial Wt./Vol.: 57.417 g Prep Extract Vol: 40.9621 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	12.4 U	24.7	7.90	ug/Kg	1		09/24/15 20:06
Ethylbenzene	23.7 J	49.4	15.4	ug/Kg	1		09/24/15 20:06
o-Xylene	24.7 ∪	49.4	15.4	ug/Kg	1		09/24/15 20:06
P & M -Xylene	32.6 J	98.8	29.6	ug/Kg	1		09/24/15 20:06
Toluene	24.7 U	49.4	15.4	ug/Kg	1		09/24/15 20:06
Surrogates							
1,4-Difluorobenzene (surr)	85.9	72-119		%	1		09/24/15 20:06

# **Batch Information**

Analytical Batch: VFC12692 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 09/24/15 20:06 Container ID: 1155497001-B

Prep Batch: VXX27961 Prep Method: SW5035A Prep Date/Time: 09/17/15 08:32 Prep Initial Wt./Vol.: 57.417 g Prep Extract Vol: 40.9621 mL

Print Date: 10/27/2015 1:51:47PM

J flagging is activated



# Results of 17747-PPS1/PPS11-3-A

Client Sample ID: 17747-PPS1/PPS11-3-A Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497002 Lab Project ID: 1155497 Collection Date: 09/17/15 08:42 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):74.8 Location:

# Results by Semivolatile Organic Fuels

Parameter Diesel Range Organics	Result Qual	<u>LOQ/CL</u>	<u>DL</u>	<u>Units</u>	<u>DF</u>	Allowable	Date Analyzed
	11.4 J	26.5	8.21	mg/Kg	1	<u>Limits</u>	10/04/15 02:53
Surrogates 5a Androstane (surr)	69.1	50-150		%	1		10/04/15 02:53

### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK102

Analyst: NLL

Analytical Date/Time: 10/04/15 02:53 Container ID: 1155497002-A Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.286 g Prep Extract Vol: 1 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	123	26.5	8.21	mg/Kg	1		10/04/15 02:53
Surrogates							
n-Triacontane-d62 (surr)	79.8	50-150		%	1		10/04/15 02:53

#### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK103

Analyst: NLL

Analytical Date/Time: 10/04/15 02:53 Container ID: 1155497002-A Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.286 g Prep Extract Vol: 1 mL



# Results of 17747-PPS1/PPS11-3-A

Client Sample ID: 17747-PPS1/PPS11-3-A Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497002 Lab Project ID: 1155497

Collection Date: 09/17/15 08:42 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):74.8 Location:

# Results by Volatile Fuels

Parameter Gasoline Range Organics	Result Qual 1.66 J	<u>LOQ/CL</u> 3.85	<u>DL</u> 1.16	<u>Units</u> mg/Kg	<u>DF</u> 1	Allowable Limits	<u>Date Analyzed</u> 09/24/15 21:41
Surrogates							
4-Bromofluorobenzene (surr)	84.2	50-150		%	1		09/24/15 21:41

### **Batch Information**

Analytical Batch: VFC12692 Analytical Method: AK101

Analyst: CRD

Analytical Date/Time: 09/24/15 21:41 Container ID: 1155497002-B

Prep Batch: VXX27961 Prep Method: SW5035A Prep Date/Time: 09/17/15 08:42 Prep Initial Wt./Vol.: 76.966 g Prep Extract Vol: 44.388 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	9.65 ∪	19.3	6.17	ug/Kg	1		09/24/15 21:41
Ethylbenzene	19.3 ∪	38.5	12.0	ug/Kg	1		09/24/15 21:41
o-Xylene	19.3 ∪	38.5	12.0	ug/Kg	1		09/24/15 21:41
P & M -Xylene	25.8 J	77.1	23.1	ug/Kg	1		09/24/15 21:41
Toluene	20.0 J	38.5	12.0	ug/Kg	1		09/24/15 21:41
Surrogates							
1,4-Difluorobenzene (surr)	85.8	72-119		%	1		09/24/15 21:41

#### **Batch Information**

Analytical Batch: VFC12692 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 09/24/15 21:41 Container ID: 1155497002-B

Prep Batch: VXX27961 Prep Method: SW5035A Prep Date/Time: 09/17/15 08:42 Prep Initial Wt./Vol.: 76.966 g

Prep Extract Vol: 44.388 mL



### Results of 17747-PPS10-D

Client Sample ID: 17747-PPS10-D Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497003 Lab Project ID: 1155497

Collection Date: 09/17/15 08:52 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):82.3 Location:

# Results by Semivolatile Organic Fuels

Parameter Diesel Range Organics	Result Qual	<u>LOQ/CL</u>	<u>DL</u>	<u>Units</u>	<u>DF</u>	Allowable	<u>Date Analyzed</u>
	9430	964	299	mg/Kg	40	<u>Limits</u>	10/05/15 19:52
Surrogates 5a Androstane (surr)	84.9	50-150		%	1		10/04/15 03:03

### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK102

Analyst: NLL

Analytical Date/Time: 10/04/15 03:03 Container ID: 1155497003-A

Analytical Batch: XFC12132 Analytical Method: AK102

Analyst: NLL Analytical Date/Time: 10/05/15 19:52

Container ID: 1155497003-A

Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.255 g Prep Extract Vol: 1 mL

Prep Batch: XXX34262

Prep Extract Vol: 1 mL

Prep Method: SW3550C

Prep Date/Time: 09/28/15 17:31

Prep Initial Wt./Vol.: 30.255 g

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	61.1	24.1	7.47	mg/Kg	1		10/04/15 03:03
Surrogates							
n-Triacontane-d62 (surr)	106	50-150		%	1		10/04/15 03:03

### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK103 Analyst: NLL

Analytical Date/Time: 10/04/15 03:03 Container ID: 1155497003-A

Prep Batch: XXX34262 Prep Method: SW3550C

Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.255 g Prep Extract Vol: 1 mL

Print Date: 10/27/2015 1:51:47PM

J flagging is activated



# Results of 17747-PPS10-D

Client Sample ID: 17747-PPS10-D Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497003 Lab Project ID: 1155497 Collection Date: 09/17/15 08:52 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):82.3 Location:

# Results by Volatile Fuels

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Gasoline Range Organics	64.3	3.20	0.960	mg/Kg	1		09/29/15 22:56
Surrogates							
4-Bromofluorobenzene (surr)	328 *	50-150		%	1		09/29/15 22:56

### **Batch Information**

Analytical Batch: VFC12701 Analytical Method: AK101

Analyst: KAS

Analytical Date/Time: 09/29/15 22:56 Container ID: 1155497003-B Prep Batch: VXX27983 Prep Method: SW5035A Prep Date/Time: 09/17/15 08:52 Prep Initial Wt./Vol.: 71.548 g Prep Extract Vol: 37.6705 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	8.00 ∪	16.0	5.12	ug/Kg	1		09/29/15 22:56
Ethylbenzene	117	32.0	9.98	ug/Kg	1		09/29/15 22:56
o-Xylene	4100	32.0	9.98	ug/Kg	1		09/29/15 22:56
P & M -Xylene	1450	64.0	19.2	ug/Kg	1		09/29/15 22:56
Toluene	255	32.0	9.98	ug/Kg	1		09/29/15 22:56
Surrogates							
1,4-Difluorobenzene (surr)	92	72-119		%	1		09/29/15 22:56

# **Batch Information**

Analytical Batch: VFC12701 Analytical Method: SW8021B

Analyst: KAS

Analytical Date/Time: 09/29/15 22:56 Container ID: 1155497003-B Prep Batch: VXX27983 Prep Method: SW5035A Prep Date/Time: 09/17/15 08:52 Prep Initial Wt./Vol.: 71.548 g

Prep Extract Vol: 37.6705 mL



# Results of 17747-PPS10-1-B

Client Sample ID: 17747-PPS10-1-B
Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497004 Lab Project ID: 1155497 Collection Date: 09/17/15 09:10 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):63.4 Location:

# Results by Semivolatile Organic Fuels

Parameter Diesel Range Organics	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	Allowable	Date Analyzed
	1800	628	195	mg/Kg	20	Limits	10/05/15 11:26
Surrogates 5a Androstane (surr)	0 *	50-150		%	20		10/05/15 11:26

### **Batch Information**

Analytical Batch: XFC12131 Analytical Method: AK102

Analyst: NLL

Analytical Date/Time: 10/05/15 11:26 Container ID: 1155497004-A Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.157 g Prep Extract Vol: 1 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	1560	628	195	mg/Kg	20		10/05/15 11:26
Surrogates							
n-Triacontane-d62 (surr)	0 *	50-150		%	20		10/05/15 11:26

#### **Batch Information**

Analytical Batch: XFC12131 Analytical Method: AK103

Analyst: NLL

Analytical Date/Time: 10/05/15 11:26 Container ID: 1155497004-A Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.157 g Prep Extract Vol: 1 mL



# Results of 17747-PPS10-1-B

Client Sample ID: 17747-PPS10-1-B Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497004 Lab Project ID: 1155497

Collection Date: 09/17/15 09:10 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):63.4 Location:

# Results by Volatile Fuels

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Gasoline Range Organics	5.36 J	5.93	1.78	mg/Kg	1		09/24/15 22:19
Surrogates							
4-Bromofluorobenzene (surr)	67.3	50-150		%	1		09/24/15 22:19

### **Batch Information**

Analytical Batch: VFC12692 Analytical Method: AK101

Analyst: CRD

Analytical Date/Time: 09/24/15 22:19 Container ID: 1155497004-B

Prep Batch: VXX27961 Prep Method: SW5035A Prep Date/Time: 09/17/15 09:40 Prep Initial Wt./Vol.: 64.89 g Prep Extract Vol: 48.778 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	14.9 ∪	29.7	9.49	ug/Kg	1		09/24/15 22:19
Ethylbenzene	29.6 ∪	59.3	18.5	ug/Kg	1		09/24/15 22:19
o-Xylene	62.3	59.3	18.5	ug/Kg	1		09/24/15 22:19
P & M -Xylene	59.9 J	119	35.6	ug/Kg	1		09/24/15 22:19
Toluene	29.6 U	59.3	18.5	ug/Kg	1		09/24/15 22:19
Surrogates							
1,4-Difluorobenzene (surr)	87	72-119		%	1		09/24/15 22:19

# **Batch Information**

Analytical Batch: VFC12692 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 09/24/15 22:19 Container ID: 1155497004-B

Prep Batch: VXX27961 Prep Method: SW5035A Prep Date/Time: 09/17/15 09:40 Prep Initial Wt./Vol.: 64.89 g

Prep Extract Vol: 48.778 mL



# Results of 17747-PPS10-2-D

Client Sample ID: 17747-PPS10-2-D
Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497005 Lab Project ID: 1155497 Collection Date: 09/17/15 09:00 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):81.9 Location:

# Results by Semivolatile Organic Fuels

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	Limits	Date Analyzed
Diesel Range Organics	2500	97.5	30.2	mg/Kg	4		10/05/15 11:06
Surrogates							
5a Androstane (surr)	76.2	50-150		%	4		10/05/15 11:06

### **Batch Information**

Analytical Batch: XFC12131 Analytical Method: AK102

Analyst: NLL

Analytical Date/Time: 10/05/15 11:06

Container ID:

Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.066 g Prep Extract Vol: 1 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	110	24.4	7.56	mg/Kg	1		10/04/15 03:23
Surrogates							
n-Triacontane-d62 (surr)	67.1	50-150		%	1		10/04/15 03:23

#### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK103

Analyst: NLL

Analytical Date/Time: 10/04/15 03:23 Container ID: 1155497005-A Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.066 g Prep Extract Vol: 1 mL



# Results of 17747-PPS10-2-D

Client Sample ID: 17747-PPS10-2-D Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497005 Lab Project ID: 1155497

Collection Date: 09/17/15 09:00 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):81.9 Location:

# Results by Volatile Fuels

Parameter Gasoline Range Organics	Result Qual 4.53	<u>LOQ/CL</u> 3.41	<u>DL</u> 1.02	<u>Units</u> mg/Kg	<u>DF</u> 1	Allowable Limits	<u>Date Analyzed</u> 09/24/15 22:38
Surrogates							
4-Bromofluorobenzene (surr)	94.5	50-150		%	1		09/24/15 22:38

### **Batch Information**

Analytical Batch: VFC12692 Analytical Method: AK101 Analyst: CRD

Analytical Date/Time: 09/24/15 22:38

Container ID: 1155497005-B

Prep Batch: VXX27961 Prep Method: SW5035A Prep Date/Time: 09/17/15 09:00 Prep Initial Wt./Vol.: 66.331 g Prep Extract Vol: 37.0251 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	8.50 ∪	17.0	5.45	ug/Kg	1		09/24/15 22:38
Ethylbenzene	17.1 U	34.1	10.6	ug/Kg	1		09/24/15 22:38
o-Xylene	62.4	34.1	10.6	ug/Kg	1		09/24/15 22:38
P & M -Xylene	27.6 J	68.2	20.5	ug/Kg	1		09/24/15 22:38
Toluene	17.1 U	34.1	10.6	ug/Kg	1		09/24/15 22:38
Surrogates							
1,4-Difluorobenzene (surr)	86.4	72-119		%	1		09/24/15 22:38

# **Batch Information**

Analytical Batch: VFC12692 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 09/24/15 22:38 Container ID: 1155497005-B

Prep Batch: VXX27961 Prep Method: SW5035A Prep Date/Time: 09/17/15 09:00 Prep Initial Wt./Vol.: 66.331 g

Prep Extract Vol: 37.0251 mL



# Results of 17747-PPS10-3-D

Client Sample ID: 17747-PPS10-3-D
Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497006 Lab Project ID: 1155497 Collection Date: 09/17/15 09:35 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):82.9 Location:

# Results by Semivolatile Organic Fuels

Parameter Diesel Range Organics	Result Qual	<u>LOQ/CL</u>	<u>DL</u>	<u>Units</u>	<u>DF</u>	Allowable	Date Analyzed
	888	48.1	14.9	mg/Kg	1	Limits	10/04/15 18:27
Surrogates 5a Androstane (surr)	88.1	50-150		%	1		10/04/15 18:27

### **Batch Information**

Analytical Batch: XFC12133 Analytical Method: AK102

Analyst: KJO

Analytical Date/Time: 10/04/15 18:27 Container ID: 1155497006-A Prep Batch: XXX34275
Prep Method: SW3550C
Prep Date/Time: 09/30/15 08:29
Prep Initial Wt./Vol.: 30.098 g
Prep Extract Vol: 2 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	63.7	48.1	14.9	mg/Kg	1		10/04/15 18:27
Surrogates							
n-Triacontane-d62 (surr)	84.3	50-150		%	1		10/04/15 18:27

#### **Batch Information**

Analytical Batch: XFC12133 Analytical Method: AK103

Analyst: KJO

Analytical Date/Time: 10/04/15 18:27 Container ID: 1155497006-A Prep Batch: XXX34275
Prep Method: SW3550C
Prep Date/Time: 09/30/15 08:29
Prep Initial Wt./Vol.: 30.098 g
Prep Extract Vol: 2 mL



# Results of 17747-PPS10-3-D

Client Sample ID: 17747-PPS10-3-D
Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497006 Lab Project ID: 1155497 Collection Date: 09/17/15 09:35 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):82.9 Location:

# Results by Semivolatile Organic Fuels Department, Silica G

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
DRO Silica Gel	795	48.1	14.9	mg/Kg	1		10/05/15 00:17
Surrogates							
5a Androstane (surr)	82.7	50-150		%	1		10/05/15 00:17

### **Batch Information**

Analytical Batch: XFC12133 Analytical Method: AK102

Analyst: KJO

Analytical Date/Time: 10/04/15 18:27 Container ID: 1155497006-A Prep Batch: XXX34275
Prep Method: SW3550C
Prep Date/Time: 09/30/15 08:29
Prep Initial Wt./Vol.: 30.098 g
Prep Extract Vol: 2 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
RRO Silica Gel	30.3 J	48.1	14.9	mg/Kg	1		10/05/15 00:17
Surrogates							
n-Triacontane-d62 (surr)	78.9	50-150		%	1		10/05/15 00:17

#### **Batch Information**

Analytical Batch: XFC12133 Analytical Method: AK103

Analyst: KJO

Analytical Date/Time: 10/04/15 18:27 Container ID: 1155497006-A Prep Batch: XXX34275
Prep Method: SW3550C
Prep Date/Time: 09/30/15 08:29
Prep Initial Wt./Vol.: 30.098 g
Prep Extract Vol: 2 mL



# Results of 17747-PPS10-3-D

Client Sample ID: 17747-PPS10-3-D
Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497006 Lab Project ID: 1155497 Collection Date: 09/17/15 09:35 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):82.9 Location:

# Results by Volatile Fuels

<u>Parameter</u> Gasoline Range Organics	Result Qual 20.5	LOQ/CL 2.65	<u>DL</u> 0.796	<u>Units</u> mg/Kg	<u>DF</u> 1	Allowable Limits	<u>Date Analyzed</u> 09/24/15 22:57
Surrogates							
4-Bromofluorobenzene (surr)	340 *	50-150		%	1		09/24/15 22:57

### **Batch Information**

Analytical Batch: VFC12692 Analytical Method: AK101

Analyst: CRD

Analytical Date/Time: 09/24/15 22:57 Container ID: 1155497006-B Prep Batch: VXX27961 Prep Method: SW5035A Prep Date/Time: 09/17/15 09:35 Prep Initial Wt./Vol.: 92.977 g Prep Extract Vol: 40.9 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	6.65 ∪	13.3	4.25	ug/Kg	1		09/24/15 22:57
Ethylbenzene	53.6	26.5	8.28	ug/Kg	1		09/24/15 22:57
o-Xylene	517	26.5	8.28	ug/Kg	1		09/24/15 22:57
P & M -Xylene	126	53.1	15.9	ug/Kg	1		09/24/15 22:57
Toluene	13.3 ∪	26.5	8.28	ug/Kg	1		09/24/15 22:57
Surrogates							
1,4-Difluorobenzene (surr)	90.6	72-119		%	1		09/24/15 22:57

#### **Batch Information**

Analytical Batch: VFC12692 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 09/24/15 22:57 Container ID: 1155497006-B Prep Batch: VXX27961 Prep Method: SW5035A Prep Date/Time: 09/17/15 09:35 Prep Initial Wt./Vol.: 92.977 g Prep Extract Vol: 40.9 mL



# Results of 17747-PPS10-3-DX

Client Sample ID: 17747-PPS10-3-DX
Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497007 Lab Project ID: 1155497 Collection Date: 09/17/15 09:37 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):83.2 Location:

# Results by Semivolatile Organic Fuels

Parameter Diesel Range Organics	Result Qual	<u>LOQ/CL</u>	<u>DL</u>	<u>Units</u>	<u>DF</u>	Allowable	<u>Date Analyzed</u>
	1180	47.6	14.8	mg/Kg	1	Limits	10/04/15 18:48
Surrogates 5a Androstane (surr)	91.7	50-150		%	1		10/04/15 18:48

### **Batch Information**

Analytical Batch: XFC12133 Analytical Method: AK102

Analyst: KJO

Analytical Date/Time: 10/04/15 18:48 Container ID: 1155497007-A Prep Batch: XXX34275
Prep Method: SW3550C
Prep Date/Time: 09/30/15 08:29
Prep Initial Wt./Vol.: 30.266 g
Prep Extract Vol: 2 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	35.9 J	47.6	14.8	mg/Kg	1		10/04/15 18:48
Surrogates							
n-Triacontane-d62 (surr)	86.9	50-150		%	1		10/04/15 18:48

#### **Batch Information**

Analytical Batch: XFC12133 Analytical Method: AK103

Analyst: KJO

Analytical Date/Time: 10/04/15 18:48 Container ID: 1155497007-A Prep Batch: XXX34275
Prep Method: SW3550C
Prep Date/Time: 09/30/15 08:29
Prep Initial Wt./Vol.: 30.266 g
Prep Extract Vol: 2 mL



# Results of 17747-PPS10-3-DX

Client Sample ID: 17747-PPS10-3-DX
Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497007 Lab Project ID: 1155497 Collection Date: 09/17/15 09:37 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):83.2 Location:

# Results by Semivolatile Organic Fuels Department, Silica G

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
DRO Silica Gel	1110	47.6	14.8	mg/Kg	1		10/05/15 00:37
Surrogates							
5a Androstane (surr)	89.7	50-150		%	1		10/05/15 00:37

### **Batch Information**

Analytical Batch: XFC12133 Analytical Method: AK102

Analyst: KJO

Analytical Date/Time: 10/04/15 18:48 Container ID: 1155497007-A Prep Batch: XXX34275
Prep Method: SW3550C
Prep Date/Time: 09/30/15 08:29
Prep Initial Wt./Vol.: 30.266 g
Prep Extract Vol: 2 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
RRO Silica Gel	35.4 J	47.6	14.8	mg/Kg	1		10/05/15 00:37
Surrogates							
n-Triacontane-d62 (surr)	85.5	50-150		%	1		10/05/15 00:37

#### **Batch Information**

Analytical Batch: XFC12133 Analytical Method: AK103

Analyst: KJO

Analytical Date/Time: 10/04/15 18:48 Container ID: 1155497007-A Prep Batch: XXX34275
Prep Method: SW3550C
Prep Date/Time: 09/30/15 08:29
Prep Initial Wt./Vol.: 30.266 g
Prep Extract Vol: 2 mL



# Results of 17747-PPS10-3-DX

Client Sample ID: 17747-PPS10-3-DX Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497007 Lab Project ID: 1155497

Collection Date: 09/17/15 09:37 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):83.2 Location:

# Results by Volatile Fuels

Parameter Gasoline Range Organics	Result Qual 10.2	<u>LOQ/CL</u> 2.35	<u>DL</u> 0.704	<u>Units</u> mg/Kg	<u>DF</u> 1	Allowable Limits	<u>Date Analyzed</u> 09/24/15 23:16
Surrogates							
4-Bromofluorobenzene (surr)	237 *	50-150		%	1		09/24/15 23:16

### **Batch Information**

Analytical Batch: VFC12692 Analytical Method: AK101

Analyst: CRD

Analytical Date/Time: 09/24/15 23:16 Container ID: 1155497007-B

Prep Batch: VXX27961 Prep Method: SW5035A Prep Date/Time: 09/17/15 09:37 Prep Initial Wt./Vol.: 112.13 g Prep Extract Vol: 43.8067 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	5.85 ∪	11.7	3.76	ug/Kg	1		09/24/15 23:16
Ethylbenzene	27.7	23.5	7.32	ug/Kg	1		09/24/15 23:16
o-Xylene	242	23.5	7.32	ug/Kg	1		09/24/15 23:16
P & M -Xylene	72.3	46.9	14.1	ug/Kg	1		09/24/15 23:16
Toluene	11.8 ∪	23.5	7.32	ug/Kg	1		09/24/15 23:16
Surrogates							
1,4-Difluorobenzene (surr)	90.1	72-119		%	1		09/24/15 23:16

#### **Batch Information**

Analytical Batch: VFC12692 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 09/24/15 23:16 Container ID: 1155497007-B

Prep Batch: VXX27961 Prep Method: SW5035A Prep Date/Time: 09/17/15 09:37 Prep Initial Wt./Vol.: 112.13 g Prep Extract Vol: 43.8067 mL



# Results of 17747-PPS10-4-B

Client Sample ID: 17747-PPS10-4-B
Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497008 Lab Project ID: 1155497 Collection Date: 09/17/15 09:18 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):82.3 Location:

# Results by Semivolatile Organic Fuels

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Diesel Range Organics	11.9 U	23.9	7.42	mg/Kg	1		10/04/15 03:33
Surrogates							
5a Androstane (surr)	75.9	50-150		%	1		10/04/15 03:33

### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK102

Analyst: NLL

Analytical Date/Time: 10/04/15 03:33 Container ID: 1155497008-A Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.465 g Prep Extract Vol: 1 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	64.5	23.9	7.42	mg/Kg	1		10/04/15 03:33
Surrogates							
n-Triacontane-d62 (surr)	83.7	50-150		%	1		10/04/15 03:33

#### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK103

Analyst: NLL

Analytical Date/Time: 10/04/15 03:33 Container ID: 1155497008-A Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.465 g Prep Extract Vol: 1 mL



# Results of 17747-PPS10-4-B

Client Sample ID: 17747-PPS10-4-B Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497008 Lab Project ID: 1155497

Collection Date: 09/17/15 09:18 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):82.3 Location:

# Results by Volatile Fuels

Parameter Gasoline Range Organics	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	Allowable	<u>Date Analyzed</u>
	1.88 J	3.38	1.01	mg/Kg	1	Limits	09/24/15 23:35
Surrogates 4-Bromofluorobenzene (surr)	107	50-150		%	1		09/24/15 23:35

### **Batch Information**

Analytical Batch: VFC12692 Analytical Method: AK101 Analyst: CRD

Analytical Date/Time: 09/24/15 23:35 Container ID: 1155497008-B

Prep Batch: VXX27961 Prep Method: SW5035A Prep Date/Time: 09/17/15 09:18 Prep Initial Wt./Vol.: 65.838 g Prep Extract Vol: 36.6336 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	8.45 ∪	16.9	5.41	ug/Kg	1		09/24/15 23:35
Ethylbenzene	16.9 ∪	33.8	10.5	ug/Kg	1		09/24/15 23:35
o-Xylene	16.9 ∪	33.8	10.5	ug/Kg	1		09/24/15 23:35
P & M -Xylene	33.8 ∪	67.6	20.3	ug/Kg	1		09/24/15 23:35
Toluene	16.9 ∪	33.8	10.5	ug/Kg	1		09/24/15 23:35
Surrogates							
1,4-Difluorobenzene (surr)	87.4	72-119		%	1		09/24/15 23:35

#### **Batch Information**

Analytical Batch: VFC12692 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 09/24/15 23:35 Container ID: 1155497008-B

Prep Batch: VXX27961 Prep Method: SW5035A Prep Date/Time: 09/17/15 09:18 Prep Initial Wt./Vol.: 65.838 g

Prep Extract Vol: 36.6336 mL



# Results of 17747-PPS12-C

Client Sample ID: 17747-PPS12-C Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497009 Lab Project ID: 1155497 Collection Date: 09/17/15 10:01 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):74.8 Location:

# Results by Semivolatile Organic Fuels

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Diesel Range Organics	27.1	26.4	8.18	mg/Kg	1		10/04/15 03:43
Surrogates							
5a Androstane (surr)	74.1	50-150		%	1		10/04/15 03:43

### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK102

Analyst: NLL

Analytical Date/Time: 10/04/15 03:43 Container ID: 1155497009-A Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.391 g Prep Extract Vol: 1 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	230	26.4	8.18	mg/Kg	1		10/04/15 03:43
Surrogates							
n-Triacontane-d62 (surr)	95.3	50-150		%	1		10/04/15 03:43

#### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK103

Analyst: NLL

Analytical Date/Time: 10/04/15 03:43 Container ID: 1155497009-A Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.391 g Prep Extract Vol: 1 mL



# Results of 17747-PPS12-C

Client Sample ID: 17747-PPS12-C

Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497009 Lab Project ID: 1155497 Collection Date: 09/17/15 10:01 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):74.8 Location:

# Results by Volatile Fuels

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Gasoline Range Organics	2.78 J	4.46	1.34	mg/Kg	1		09/24/15 23:54
Surrogates							
4-Bromofluorobenzene (surr)	75.5	50-150		%	1		09/24/15 23:54

### **Batch Information**

Analytical Batch: VFC12692 Analytical Method: AK101

Analyst: CRD

Analytical Date/Time: 09/24/15 23:54 Container ID: 1155497009-B Prep Batch: VXX27961 Prep Method: SW5035A Prep Date/Time: 09/17/15 10:01 Prep Initial Wt./Vol.: 60.111 g Prep Extract Vol: 40.1234 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	11.2 U	22.3	7.14	ug/Kg	1		09/24/15 23:54
Ethylbenzene	22.3 ∪	44.6	13.9	ug/Kg	1		09/24/15 23:54
o-Xylene	22.3 U	44.6	13.9	ug/Kg	1		09/24/15 23:54
P & M -Xylene	44.6 U	89.2	26.8	ug/Kg	1		09/24/15 23:54
Toluene	22.3 U	44.6	13.9	ug/Kg	1		09/24/15 23:54
Surrogates							
1,4-Difluorobenzene (surr)	86.9	72-119		%	1		09/24/15 23:54

#### **Batch Information**

Analytical Batch: VFC12692 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 09/24/15 23:54 Container ID: 1155497009-B Prep Batch: VXX27961
Prep Method: SW5035A
Prep Date/Time: 09/17/15 10:01
Prep Initial Wt./Vol.: 60.111 g
Prep Extract Vol: 40.1234 mL



# Results of 17747-PPS12-2-A

Client Sample ID: 17747-PPS12-2-A
Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497010 Lab Project ID: 1155497 Collection Date: 09/17/15 10:09 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):78.2 Location:

# Results by Semivolatile Organic Fuels

Parameter Diesel Range Organics	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	Allowable	<u>Date Analyzed</u>
	19.0 J	25.3	7.84	mg/Kg	1	Limits	10/04/15 03:53
Surrogates 5a Androstane (surr)	74.7	50-150		%	1		10/04/15 03:53

### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK102

Analyst: NLL

Analytical Date/Time: 10/04/15 03:53 Container ID: 1155497010-A Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.342 g Prep Extract Vol: 1 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	155	25.3	7.84	mg/Kg	1		10/04/15 03:53
Surrogates							
n-Triacontane-d62 (surr)	82.3	50-150		%	1		10/04/15 03:53

#### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK103

Analyst: NLL

Analytical Date/Time: 10/04/15 03:53 Container ID: 1155497010-A Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.342 g Prep Extract Vol: 1 mL



# Results of 17747-PPS12-2-A

Client Sample ID: 17747-PPS12-2-A Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497010 Lab Project ID: 1155497

Collection Date: 09/17/15 10:09 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):78.2 Location:

# Results by Volatile Fuels

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Gasoline Range Organics	1.78 J	3.79	1.14	mg/Kg	1		09/25/15 00:13
Surrogates							
4-Bromofluorobenzene (surr)	91.2	50-150		%	1		09/25/15 00:13

### **Batch Information**

Analytical Batch: VFC12692 Analytical Method: AK101 Analyst: CRD

Analytical Date/Time: 09/25/15 00:13 Container ID: 1155497010-B

Prep Batch: VXX27961 Prep Method: SW5035A Prep Date/Time: 09/17/15 10:09 Prep Initial Wt./Vol.: 66.557 g Prep Extract Vol: 39.5008 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	9.50 ∪	19.0	6.07	ug/Kg	1		09/25/15 00:13
Ethylbenzene	18.9 U	37.9	11.8	ug/Kg	1		09/25/15 00:13
o-Xylene	18.9 U	37.9	11.8	ug/Kg	1		09/25/15 00:13
P & M -Xylene	38.0 ∪	75.9	22.8	ug/Kg	1		09/25/15 00:13
Toluene	18.9 U	37.9	11.8	ug/Kg	1		09/25/15 00:13
Surrogates							
1,4-Difluorobenzene (surr)	87.1	72-119		%	1		09/25/15 00:13

# **Batch Information**

Analytical Batch: VFC12692 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 09/25/15 00:13 Container ID: 1155497010-B

Prep Batch: VXX27961 Prep Method: SW5035A Prep Date/Time: 09/17/15 10:09 Prep Initial Wt./Vol.: 66.557 g Prep Extract Vol: 39.5008 mL



# Results of 17747-PPS13-C

Client Sample ID: 17747-PPS13-C Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497011 Lab Project ID: 1155497 Collection Date: 09/17/15 10:40 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):73.0 Location:

# Results by Semivolatile Organic Fuels

Parameter Diesel Range Organics	Result Qual	<u>LOQ/CL</u>	<u>DL</u>	<u>Units</u>	<u>DF</u>	Allowable	Date Analyzed
	27.3 J	54.7	17.0	mg/Kg	1	Limits	10/04/15 19:08
Surrogates 5a Androstane (surr)	98.1	50-150		%	1		10/04/15 19:08

### **Batch Information**

Analytical Batch: XFC12133 Analytical Method: AK102

Analyst: KJO

Analytical Date/Time: 10/04/15 19:08 Container ID: 1155497011-A Prep Batch: XXX34275
Prep Method: SW3550C
Prep Date/Time: 09/30/15 08:29
Prep Initial Wt./Vol.: 30.037 g
Prep Extract Vol: 2 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	232	54.7	17.0	mg/Kg	1		10/04/15 19:08
Surrogates							
n-Triacontane-d62 (surr)	93.4	50-150		%	1		10/04/15 19:08

#### **Batch Information**

Analytical Batch: XFC12133 Analytical Method: AK103

Analyst: KJO

Analytical Date/Time: 10/04/15 19:08 Container ID: 1155497011-A Prep Batch: XXX34275
Prep Method: SW3550C
Prep Date/Time: 09/30/15 08:29
Prep Initial Wt./Vol.: 30.037 g
Prep Extract Vol: 2 mL



# Results of 17747-PPS13-C

Client Sample ID: 17747-PPS13-C

Client Project ID: **32-1-17747 Pitkas Point** Lab Sample ID: 1155497011

Lab Project ID: 1155497

Collection Date: 09/17/15 10:40 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):73.0 Location:

# Results by Semivolatile Organic Fuels Department, Silica G

<u>Parameter</u>	Result Qual	<u>LOQ/CL</u>	<u>DL</u>	<u>Units</u>	<u>DF</u>	Allowable	<u>Date Analyzed</u>
DRO Silica Gel	18.7 J	54.7	17.0	mg/Kg	1	Limits	10/05/15 00:58
Surrogates 5a Androstane (surr)	85.6	50-150		%	1		10/05/15 00:58

### **Batch Information**

Analytical Batch: XFC12133 Analytical Method: AK102

Analyst: KJO

Analytical Date/Time: 10/04/15 19:08 Container ID: 1155497011-A Prep Batch: XXX34275
Prep Method: SW3550C
Prep Date/Time: 09/30/15 08:29
Prep Initial Wt./Vol.: 30.037 g
Prep Extract Vol: 2 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
RRO Silica Gel	81.7	54.7	17.0	mg/Kg	1		10/05/15 00:58
Surrogates							
n-Triacontane-d62 (surr)	87	50-150		%	1		10/05/15 00:58

#### **Batch Information**

Analytical Batch: XFC12133 Analytical Method: AK103

Analyst: KJO

Analytical Date/Time: 10/04/15 19:08 Container ID: 1155497011-A Prep Batch: XXX34275
Prep Method: SW3550C
Prep Date/Time: 09/30/15 08:29
Prep Initial Wt./Vol.: 30.037 g
Prep Extract Vol: 2 mL



# Results of 17747-PPS13-C

Client Sample ID: 17747-PPS13-C Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497011 Lab Project ID: 1155497 Collection Date: 09/17/15 10:40 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):73.0 Location:

# Results by Volatile Fuels

<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	Allowable Limits	Date Analyzed
Gasoline Range Organics	2.36 U	4.71	1.41	mg/Kg	1	<del></del>	09/25/15 00:32
Surrogates							
4-Bromofluorobenzene (surr)	72	50-150		%	1		09/25/15 00:32

### **Batch Information**

Analytical Batch: VFC12692 Analytical Method: AK101

Analyst: CRD

Analytical Date/Time: 09/25/15 00:32 Container ID: 1155497011-B Prep Batch: VXX27961
Prep Method: SW5035A
Prep Date/Time: 09/17/15 10:40
Prep Initial Wt./Vol.: 59.967 g
Prep Extract Vol: 41.1998 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	11.8 ∪	23.5	7.53	ug/Kg	1		09/25/15 00:32
Ethylbenzene	23.6 ∪	47.1	14.7	ug/Kg	1		09/25/15 00:32
o-Xylene	23.6 ∪	47.1	14.7	ug/Kg	1		09/25/15 00:32
P & M -Xylene	47.0 ∪	94.1	28.2	ug/Kg	1		09/25/15 00:32
Toluene	23.6 U	47.1	14.7	ug/Kg	1		09/25/15 00:32
Surrogates							
1,4-Difluorobenzene (surr)	87.1	72-119		%	1		09/25/15 00:32

#### **Batch Information**

Analytical Batch: VFC12692 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 09/25/15 00:32 Container ID: 1155497011-B Prep Batch: VXX27961 Prep Method: SW5035A Prep Date/Time: 09/17/15 10:40 Prep Initial Wt./Vol.: 59.967 g

Prep Extract Vol: 41.1998 mL



# Results of 17747-PPS12-3-CX

Client Sample ID: 17747-PPS12-3-CX
Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497012 Lab Project ID: 1155497 Collection Date: 09/17/15 10:22 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):75.8 Location:

# Results by Semivolatile Organic Fuels

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	DF	<u>Limits</u>	Date Analyzed
Diesel Range Organics	510	52.0	16.1	mg/Kg	1		10/04/15 19:29
Surrogates							
5a Androstane (surr)	101	50-150		%	1		10/04/15 19:29

### **Batch Information**

Analytical Batch: XFC12133 Analytical Method: AK102

Analyst: KJO

Analytical Date/Time: 10/04/15 19:29 Container ID: 1155497012-A Prep Batch: XXX34275
Prep Method: SW3550C
Prep Date/Time: 09/30/15 08:29
Prep Initial Wt./Vol.: 30.46 g
Prep Extract Vol: 2 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	631	52.0	16.1	mg/Kg	1		10/04/15 19:29
Surrogates							
n-Triacontane-d62 (surr)	96.2	50-150		%	1		10/04/15 19:29

#### **Batch Information**

Analytical Batch: XFC12133 Analytical Method: AK103

Analyst: KJO

Analytical Date/Time: 10/04/15 19:29 Container ID: 1155497012-A Prep Batch: XXX34275
Prep Method: SW3550C
Prep Date/Time: 09/30/15 08:29
Prep Initial Wt./Vol.: 30.46 g
Prep Extract Vol: 2 mL



# Results of 17747-PPS12-3-CX

Client Sample ID: 17747-PPS12-3-CX Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497012 Lab Project ID: 1155497

Collection Date: 09/17/15 10:22 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):75.8 Location:

# Results by Semivolatile Organic Fuels Department, Silica G

<u>Parameter</u>	Result Qual	<u>LOQ/CL</u>	<u>DL</u>	<u>Units</u>	<u>DF</u>	Allowable	Date Analyzed
DRO Silica Gel	301	52.0	16.1	mg/Kg	1	Limits	10/05/15 01:19
Surrogates 5a Androstane (surr)	90.2	50-150		%	1		10/05/15 01:19

### **Batch Information**

Analytical Batch: XFC12133 Analytical Method: AK102

Analyst: KJO

Analytical Date/Time: 10/04/15 19:29 Container ID: 1155497012-A

Prep Batch: XXX34275 Prep Method: SW3550C Prep Date/Time: 09/30/15 08:29 Prep Initial Wt./Vol.: 30.46 g Prep Extract Vol: 2 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
RRO Silica Gel	167	52.0	16.1	mg/Kg	1		10/05/15 01:19
Surrogates							
n-Triacontane-d62 (surr)	94.2	50-150		%	1		10/05/15 01:19

#### **Batch Information**

Analytical Batch: XFC12133 Analytical Method: AK103

Analyst: KJO

Analytical Date/Time: 10/04/15 19:29 Container ID: 1155497012-A

Prep Batch: XXX34275 Prep Method: SW3550C Prep Date/Time: 09/30/15 08:29 Prep Initial Wt./Vol.: 30.46 g Prep Extract Vol: 2 mL



# Results of 17747-PPS12-3-CX

Client Sample ID: 17747-PPS12-3-CX Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497012 Lab Project ID: 1155497

Collection Date: 09/17/15 10:22 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):75.8 Location:

# Results by Volatile Fuels

<u>Parameter</u> Gasoline Range Organics	Result Qual 2.91 J	<u>LOQ/CL</u> 4.20	<u>DL</u> 1.26	<u>Units</u> mg/Kg	<u>DF</u> 1	Allowable Limits	<u>Date Analyzed</u> 09/25/15 00:51
Surrogates							
4-Bromofluorobenzene (surr)	82.6	50-150		%	1		09/25/15 00:51

### **Batch Information**

Analytical Batch: VFC12692 Analytical Method: AK101 Analyst: CRD

Analytical Date/Time: 09/25/15 00:51 Container ID: 1155497012-B

Prep Batch: VXX27961 Prep Method: SW5035A Prep Date/Time: 09/17/15 10:22 Prep Initial Wt./Vol.: 63.313 g Prep Extract Vol: 40.304 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	10.5 ∪	21.0	6.72	ug/Kg	1		09/25/15 00:51
Ethylbenzene	21.0 ∪	42.0	13.1	ug/Kg	1		09/25/15 00:51
o-Xylene	21.0 ∪	42.0	13.1	ug/Kg	1		09/25/15 00:51
P & M -Xylene	42.0 U	84.0	25.2	ug/Kg	1		09/25/15 00:51
Toluene	21.0 U	42.0	13.1	ug/Kg	1		09/25/15 00:51
Surrogates							
1,4-Difluorobenzene (surr)	86.3	72-119		%	1		09/25/15 00:51

#### **Batch Information**

Analytical Batch: VFC12692 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 09/25/15 00:51 Container ID: 1155497012-B

Prep Batch: VXX27961 Prep Method: SW5035A Prep Date/Time: 09/17/15 10:22 Prep Initial Wt./Vol.: 63.313 g Prep Extract Vol: 40.304 mL



# Results of 17747-PPS12-3-C

Client Sample ID: 17747-PPS12-3-C Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497013 Lab Project ID: 1155497 Collection Date: 09/17/15 10:20 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):75.8 Location:

# Results by Semivolatile Organic Fuels

<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	Allowable Limits	Date Analyzed
Diesel Range Organics	317	52.5	16.3	mg/Kg	1		10/21/15 05:03
Surrogates							
5a Androstane (surr)	96.3	50-150		%	1		10/21/15 05:03

### **Batch Information**

Analytical Batch: XFC12174 Analytical Method: AK102

Analyst: KJO

Analytical Date/Time: 10/21/15 05:03 Container ID: 1155497013-A Prep Batch: XXX34453 Prep Method: SW3550C Prep Date/Time: 10/19/15 12:44 Prep Initial Wt./Vol.: 30.163 g Prep Extract Vol: 2 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	488	52.5	16.3	mg/Kg	1		10/21/15 05:03
Surrogates							
n-Triacontane-d62 (surr)	104	50-150		%	1		10/21/15 05:03

#### **Batch Information**

Analytical Batch: XFC12174 Analytical Method: AK103

Analyst: KJO

Analytical Date/Time: 10/21/15 05:03 Container ID: 1155497013-A Prep Batch: XXX34453 Prep Method: SW3550C Prep Date/Time: 10/19/15 12:44 Prep Initial Wt./Vol.: 30.163 g Prep Extract Vol: 2 mL



# Results of 17747-PPS12-3-C

Client Sample ID: 17747-PPS12-3-C Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497013 Lab Project ID: 1155497 Collection Date: 09/17/15 10:20 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):75.8 Location:

# Results by Semivolatile Organic Fuels Department, Silica G

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
DRO Silica Gel	155	52.5	16.3	mg/Kg	1		10/20/15 20:11
Surrogates							
5a Androstane (surr)	86.4	50-150		%	1		10/20/15 20:11

### **Batch Information**

Analytical Batch: XFC12174 Analytical Method: AK102

Analyst: KJO

Analytical Date/Time: 10/21/15 05:03 Container ID: 1155497013-A Prep Batch: XXX34453 Prep Method: SW3550C Prep Date/Time: 10/19/15 12:44 Prep Initial Wt./Vol.: 30.163 g Prep Extract Vol: 2 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
RRO Silica Gel	86.5	52.5	16.3	mg/Kg	1		10/20/15 20:11
Surrogates							
n-Triacontane-d62 (surr)	85.7	50-150		%	1		10/20/15 20:11

#### **Batch Information**

Analytical Batch: XFC12174 Analytical Method: AK103

Analyst: KJO

Analytical Date/Time: 10/21/15 05:03 Container ID: 1155497013-A Prep Batch: XXX34453 Prep Method: SW3550C Prep Date/Time: 10/19/15 12:44 Prep Initial Wt./Vol.: 30.163 g Prep Extract Vol: 2 mL



## Results of 17747-PPS12-3-C

Client Sample ID: 17747-PPS12-3-C Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497013 Lab Project ID: 1155497 Collection Date: 09/17/15 10:20 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):75.8 Location:

## Results by Volatile Fuels

Parameter Gasoline Range Organics	Result Qual	<u>LOQ/CL</u>	<u>DL</u>	<u>Units</u>	<u>DF</u>	Allowable	<u>Date Analyzed</u>
	2.27 U	4.53	1.36	mg/Kg	1	Limits	09/26/15 16:21
Surrogates 4-Bromofluorobenzene (surr)	80.8	50-150		%	1		09/26/15 16:21

### **Batch Information**

Analytical Batch: VFC12695 Analytical Method: AK101

Analyst: CRD

Analytical Date/Time: 09/26/15 16:21 Container ID: 1155497013-B

Prep Batch: VXX27969
Prep Method: SW5035A
Prep Date/Time: 09/17/15 10:20
Prep Initial Wt./Vol.: 56.194 g
Prep Extract Vol: 38.5988 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	11.4 U	22.7	7.25	ug/Kg	1		09/26/15 16:21
Ethylbenzene	22.6 ∪	45.3	14.1	ug/Kg	1		09/26/15 16:21
o-Xylene	22.6 ∪	45.3	14.1	ug/Kg	1		09/26/15 16:21
P & M -Xylene	45.3 ∪	90.6	27.2	ug/Kg	1		09/26/15 16:21
Toluene	22.6 U	45.3	14.1	ug/Kg	1		09/26/15 16:21
Surrogates							
1,4-Difluorobenzene (surr)	86.7	72-119		%	1		09/26/15 16:21

#### **Batch Information**

Analytical Batch: VFC12695 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 09/26/15 16:21 Container ID: 1155497013-B Prep Batch: VXX27969
Prep Method: SW5035A
Prep Date/Time: 09/17/15 10:20
Prep Initial Wt./Vol.: 56.194 g

Prep Extract Vol: 38.5988 mL



## Results of 17747-PPS13-1-A

Client Sample ID: 17747-PPS13-1-A
Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497014 Lab Project ID: 1155497 Collection Date: 09/17/15 10:50 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):67.8 Location:

# Results by Semivolatile Organic Fuels

Parameter Diesel Range Organics	Result Qual	<u>LOQ/CL</u> 29.3	<u>DL</u> 9.07	<u>Units</u> mg/Kg	<u>DF</u> 1	Allowable Limits	<u>Date Analyzed</u> 10/04/15 04:32
Surrogates 5a Androstane (surr)	73.5	50-150		%	1		10/04/15 04:32

### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK102

Analyst: NLL

Analytical Date/Time: 10/04/15 04:32 Container ID: 1155497014-A

Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.234 g Prep Extract Vol: 1 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	189	29.3	9.07	mg/Kg	1		10/04/15 04:32
Surrogates							
n-Triacontane-d62 (surr)	94.9	50-150		%	1		10/04/15 04:32

#### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK103

Analyst: NLL

Analytical Date/Time: 10/04/15 04:32 Container ID: 1155497014-A

Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.234 g Prep Extract Vol: 1 mL



## Results of 17747-PPS13-1-A

Client Sample ID: 17747-PPS13-1-A
Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497014 Lab Project ID: 1155497 Collection Date: 09/17/15 10:50 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):67.8 Location:

## Results by Volatile Fuels

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Gasoline Range Organics	3.30 J	6.15	1.85	mg/Kg	1		09/26/15 17:18
Surrogates							
4-Bromofluorobenzene (surr)	74.4	50-150		%	1		09/26/15 17:18

### **Batch Information**

Analytical Batch: VFC12695 Analytical Method: AK101

Analyst: CRD

Analytical Date/Time: 09/26/15 17:18 Container ID: 1155497014-B Prep Batch: VXX27969 Prep Method: SW5035A Prep Date/Time: 09/17/15 10:50 Prep Initial Wt./Vol.: 48.805 g Prep Extract Vol: 40.7087 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	15.4 ∪	30.8	9.84	ug/Kg	1		09/26/15 17:18
Ethylbenzene	30.8 ∪	61.5	19.2	ug/Kg	1		09/26/15 17:18
o-Xylene	30.8 ∪	61.5	19.2	ug/Kg	1		09/26/15 17:18
P & M -Xylene	61.5 ∪	123	36.9	ug/Kg	1		09/26/15 17:18
Toluene	30.8 U	61.5	19.2	ug/Kg	1		09/26/15 17:18
Surrogates							
1,4-Difluorobenzene (surr)	87.5	72-119		%	1		09/26/15 17:18

# **Batch Information**

Analytical Batch: VFC12695 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 09/26/15 17:18 Container ID: 1155497014-B Prep Batch: VXX27969 Prep Method: SW5035A Prep Date/Time: 09/17/15 10:50 Prep Initial Wt./Vol.: 48.805 g

Prep Extract Vol: 40.7087 mL



## Results of 17747-PPS13-2-B

Client Sample ID: 17747-PPS13-2-B
Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497015 Lab Project ID: 1155497 Collection Date: 09/17/15 10:59 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):78.3 Location:

# Results by Semivolatile Organic Fuels

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	DF	<u>Limits</u>	Date Analyzed
Diesel Range Organics	12.8 U	25.5	7.91	mg/Kg	1		10/04/15 04:42
Surrogates							
5a Androstane (surr)	75.5	50-150		%	1		10/04/15 04:42

### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK102

Analyst: NLL

Analytical Date/Time: 10/04/15 04:42 Container ID: 1155497015-A Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.044 g Prep Extract Vol: 1 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	67.8	25.5	7.91	mg/Kg	1		10/04/15 04:42
Surrogates							
n-Triacontane-d62 (surr)	82.6	50-150		%	1		10/04/15 04:42

#### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK103

Analyst: NLL

Analytical Date/Time: 10/04/15 04:42 Container ID: 1155497015-A

Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.044 g Prep Extract Vol: 1 mL



## Results of 17747-PPS13-2-B

Client Sample ID: 17747-PPS13-2-B Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497015 Lab Project ID: 1155497

Collection Date: 09/17/15 10:59 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):78.3 Location:

## Results by Volatile Fuels

<u>Parameter</u> Gasoline Range Organics	Result Qual 1.88 J	LOQ/CL 3.12	<u>DL</u> 0.935	<u>Units</u> mg/Kg	<u>DF</u> 1	Allowable Limits	<u>Date Analyzed</u> 09/26/15 17:37
Surrogates							
4-Bromofluorobenzene (surr)	86.3	50-150		%	1		09/26/15 17:37

### **Batch Information**

Analytical Batch: VFC12695 Analytical Method: AK101

Analyst: CRD

Analytical Date/Time: 09/26/15 17:37 Container ID: 1155497015-B

Prep Batch: VXX27969 Prep Method: SW5035A Prep Date/Time: 09/17/15 10:59 Prep Initial Wt./Vol.: 92.235 g Prep Extract Vol: 45.0145 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	7.80 U	15.6	4.99	ug/Kg	1		09/26/15 17:37
Ethylbenzene	15.6 U	31.2	9.72	ug/Kg	1		09/26/15 17:37
o-Xylene	15.6 U	31.2	9.72	ug/Kg	1		09/26/15 17:37
P & M -Xylene	31.1 U	62.3	18.7	ug/Kg	1		09/26/15 17:37
Toluene	15.6 ∪	31.2	9.72	ug/Kg	1		09/26/15 17:37
Surrogates							
1,4-Difluorobenzene (surr)	87.4	72-119		%	1		09/26/15 17:37

#### **Batch Information**

Analytical Batch: VFC12695 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 09/26/15 17:37 Container ID: 1155497015-B

Prep Batch: VXX27969 Prep Method: SW5035A Prep Date/Time: 09/17/15 10:59 Prep Initial Wt./Vol.: 92.235 g

Prep Extract Vol: 45.0145 mL



Client Sample ID: 17747-TF1

Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497016 Lab Project ID: 1155497 Collection Date: 09/17/15 13:14 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):63.2 Location:

# Results by Semivolatile Organic Fuels

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Diesel Range Organics	19.5 J	31.5	9.78	mg/Kg	1		10/04/15 04:52
Surrogates							
5a Androstane (surr)	67.4	50-150		%	1		10/04/15 04:52

### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK102

Analyst: NLL

Analytical Date/Time: 10/04/15 04:52 Container ID: 1155497016-A Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.102 g Prep Extract Vol: 1 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	141	31.5	9.78	mg/Kg	1		10/04/15 04:52
Surrogates							
n-Triacontane-d62 (surr)	82.5	50-150		%	1		10/04/15 04:52

#### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK103

Analyst: NLL

Analytical Date/Time: 10/04/15 04:52 Container ID: 1155497016-A

Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.102 g Prep Extract Vol: 1 mL



Client Sample ID: 17747-TF1

Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497016 Lab Project ID: 1155497 Collection Date: 09/17/15 13:14 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):63.2 Location:

## Results by Volatile Fuels

Parameter Gasoline Range Organics	Result Qual 3.62 .I	<u>LOQ/CL</u> 6.51	<u>DL</u> 1.95	<u>Units</u> mg/Kg	<u>DF</u>	Allowable Limits	<u>Date Analyzed</u> 09/26/15 17:56
Surrogates	3.02 J	0.51	1.95	mg/Kg	'		09/20/13 17:30
4-Bromofluorobenzene (surr)	69	50-150		%	1		09/26/15 17:56

### **Batch Information**

Analytical Batch: VFC12695 Analytical Method: AK101

Analyst: CRD

Analytical Date/Time: 09/26/15 17:56 Container ID: 1155497016-B Prep Batch: VXX27969
Prep Method: SW5035A
Prep Date/Time: 09/17/15 13:14
Prep Initial Wt./Vol.: 55.069 g
Prep Extract Vol: 45.2757 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	16.3 U	32.5	10.4	ug/Kg	1		09/26/15 17:56
Ethylbenzene	32.5 ∪	65.1	20.3	ug/Kg	1		09/26/15 17:56
o-Xylene	32.5 ∪	65.1	20.3	ug/Kg	1		09/26/15 17:56
P & M -Xylene	65.0 U	130	39.0	ug/Kg	1		09/26/15 17:56
Toluene	32.5 U	65.1	20.3	ug/Kg	1		09/26/15 17:56
Surrogates							
1,4-Difluorobenzene (surr)	89.1	72-119		%	1		09/26/15 17:56

#### **Batch Information**

Analytical Batch: VFC12695 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 09/26/15 17:56 Container ID: 1155497016-B Prep Batch: VXX27969 Prep Method: SW5035A Prep Date/Time: 09/17/15 13:14 Prep Initial Wt./Vol.: 55.069 g Prep Extract Vol: 45.2757 mL



Client Sample ID: 17747-TF2

Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497017 Lab Project ID: 1155497 Collection Date: 09/17/15 13:21 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):70.3 Location:

# Results by Semivolatile Organic Fuels

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Diesel Range Organics	849	28.0	8.69	mg/Kg	1		10/04/15 05:02
Surrogates							
5a Androstane (surr)	70.9	50-150		%	1		10/04/15 05:02

### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK102

Analyst: NLL

Analytical Date/Time: 10/04/15 05:02 Container ID: 1155497017-A

Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.421 g Prep Extract Vol: 1 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Residual Range Organics	164	28.0	8.69	mg/Kg	1		10/04/15 05:02
Surrogates							
n-Triacontane-d62 (surr)	86.7	50-150		%	1		10/04/15 05:02

#### **Batch Information**

Analytical Batch: XFC12126 Analytical Method: AK103

Analyst: NLL

Analytical Date/Time: 10/04/15 05:02 Container ID: 1155497017-A

Prep Batch: XXX34262 Prep Method: SW3550C Prep Date/Time: 09/28/15 17:31 Prep Initial Wt./Vol.: 30.421 g Prep Extract Vol: 1 mL



Client Sample ID: 17747-TF2

Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497017 Lab Project ID: 1155497 Collection Date: 09/17/15 13:21 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%):70.3 Location:

## Results by Volatile Fuels

<u>Parameter</u> Gasoline Range Organics	Result Qual 2.68 J	<u>LOQ/CL</u> 4.57	<u>DL</u> 1.37	<u>Units</u> mg/Kg	<u>DF</u> 1	Allowable <u>Limits</u>	<u>Date Analyzed</u> 09/26/15 18:15
Surrogates							
4-Bromofluorobenzene (surr)	108	50-150		%	1		09/26/15 18:15

### **Batch Information**

Analytical Batch: VFC12695 Analytical Method: AK101

Analyst: CRD

Analytical Date/Time: 09/26/15 18:15 Container ID: 1155497017-B Prep Batch: VXX27969
Prep Method: SW5035A
Prep Date/Time: 09/17/15 13:21
Prep Initial Wt./Vol.: 72.143 g
Prep Extract Vol: 46.4109 mL

						Allowable	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	11.4 U	22.9	7.32	ug/Kg	1		09/26/15 18:15
Ethylbenzene	22.9 ∪	45.7	14.3	ug/Kg	1		09/26/15 18:15
o-Xylene	22.9 ∪	45.7	14.3	ug/Kg	1		09/26/15 18:15
P & M -Xylene	45.8 U	91.5	27.4	ug/Kg	1		09/26/15 18:15
Toluene	22.9 U	45.7	14.3	ug/Kg	1		09/26/15 18:15
Surrogates							
1,4-Difluorobenzene (surr)	88.5	72-119		%	1		09/26/15 18:15

#### **Batch Information**

Analytical Batch: VFC12695 Analytical Method: SW8021B

Analyst: CRD

Analytical Date/Time: 09/26/15 18:15 Container ID: 1155497017-B Prep Batch: VXX27969
Prep Method: SW5035A
Prep Date/Time: 09/17/15 13:21
Prep Initial Wt./Vol.: 72.143 g
Prep Extract Vol: 46.4109 mL

Print Date: 10/27/2015 1:51:47PM

J flagging is activated



Client Sample ID: 17747-TB1

Client Project ID: 32-1-17747 Pitkas Point

Lab Sample ID: 1155497018 Lab Project ID: 1155497 Collection Date: 09/17/15 13:30 Received Date: 09/22/15 10:01 Matrix: Soil/Solid (dry weight)

Solids (%): Location:

# Results by Volatile Fuels

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Gasoline Range Organics	1.25 U	2.51	0.754	mg/Kg	1		09/23/15 16:47
Surrogates							
4-Bromofluorobenzene (surr)	82.1	50-150		%	1		09/23/15 16:47

### **Batch Information**

Analytical Batch: VFC12688 Analytical Method: AK101

Analyst: KAS

Analytical Date/Time: 09/23/15 16:47 Container ID: 1155497018-A Prep Batch: VXX27953 Prep Method: SW5035A Prep Date/Time: 09/17/15 13:30 Prep Initial Wt./Vol.: 49.71 g Prep Extract Vol: 25 mL

						<u>Allowable</u>	
<u>Parameter</u>	Result Qual	LOQ/CL	<u>DL</u>	<u>Units</u>	<u>DF</u>	<u>Limits</u>	Date Analyzed
Benzene	6.30 U	12.6	4.02	ug/Kg	1		09/23/15 16:47
Ethylbenzene	12.6 U	25.1	7.85	ug/Kg	1		09/23/15 16:47
o-Xylene	12.6 U	25.1	7.85	ug/Kg	1		09/23/15 16:47
P & M -Xylene	17.1 J	50.3	15.1	ug/Kg	1		09/23/15 16:47
Toluene	15.6 J	25.1	7.85	ug/Kg	1		09/23/15 16:47
Surrogates							
1,4-Difluorobenzene (surr)	86.7	72-119		%	1		09/23/15 16:47

# **Batch Information**

Analytical Batch: VFC12688 Analytical Method: SW8021B

Analyst: KAS

Analytical Date/Time: 09/23/15 16:47 Container ID: 1155497018-A Prep Batch: VXX27953 Prep Method: SW5035A Prep Date/Time: 09/17/15 13:30 Prep Initial Wt./Vol.: 49.71 g Prep Extract Vol: 25 mL

Print Date: 10/27/2015 1:51:47PM

J flagging is activated



Blank ID: MB for HBN 1721517 [SPT/9752]

Blank Lab ID: 1293873

QC for Samples:

1155497001, 1155497002, 1155497003, 1155497004, 1155497005, 1155497006, 1155497007, 1155497008, 1155497009,

Matrix: Soil/Solid (dry weight)

1155497010, 1155497011, 1155497012, 1155497013, 1155497014, 1155497015, 1155497016, 1155497017

Results by SM21 2540G

 Parameter
 Results
 LOQ/CL
 DL
 Units

 Total Solids
 100
 %

**Batch Information** 

Analytical Batch: SPT9752 Analytical Method: SM21 2540G

Instrument: Analyst: A.R

Analytical Date/Time: 9/28/2015 6:25:00PM

Print Date: 10/27/2015 1:51:52PM



# **Duplicate Sample Summary**

Original Sample ID: 1155490031 Duplicate Sample ID: 1293874

QC for Samples: 1155497001

Analysis Date: 09/28/2015 18:25 Matrix: Soil/Solid (dry weight)

# Results by SM21 2540G

<u>NAME</u>	<u>Original</u>	<u>Duplicate</u>	<u>Units</u>	RPD (%)	RPD CL
Total Solids	83.0	82.3	%	0.86	(< 15 )

## **Batch Information**

Analytical Batch: SPT9752 Analytical Method: SM21 2540G

Instrument: Analyst: A.R

Print Date: 10/27/2015 1:51:53PM



### **Duplicate Sample Summary**

Original Sample ID: 1155497001 Analysis Date: 09/28/2015 18:25
Duplicate Sample ID: 1293875 Matrix: Soil/Solid (dry weight)

QC for Samples:

 $1155497001, 1155497002, 1155497003, 1155497004, 1155497005, 1155497006, 1155497007, 1155497008, \\1155497009, 1155497010, 1155497011, 1155497012, 1155497013, 1155497014, 1155497015, 1155497016, \\1155497016, 1155497017, 11$ 

## Results by SM21 2540G

NAME	<u>Original</u>	<u>Duplicate</u>	<u>Units</u>	RPD (%)	RPD CL
Total Solids	72.2	71.2	%	1.50	(< 15 )

### **Batch Information**

Analytical Batch: SPT9752 Analytical Method: SM21 2540G

Instrument: Analyst: A.R

Print Date: 10/27/2015 1:51:53PM



### **Duplicate Sample Summary**

Original Sample ID: 1158652011 Analysis Date: 09/28/2015 18:25
Duplicate Sample ID: 1293876 Matrix: Soil/Solid (dry weight)

QC for Samples:

 $1155497002, 1155497003, 1155497004, 1155497005, 1155497006, 1155497007, 1155497008, 1155497009, \\1155497010, 1155497011, 1155497012, 1155497013, 1155497014, 1155497015, 1155497016, 1155497017$ 

## Results by SM21 2540G

NAME	<u>Original</u>	<u>Duplicate</u>	<u>Units</u>	RPD (%)	RPD CL
Total Solids	89.7	87.3	%	2.70	(< 15)

### **Batch Information**

Analytical Batch: SPT9752 Analytical Method: SM21 2540G

Instrument: Analyst: A.R

Print Date: 10/27/2015 1:51:53PM



Blank ID: MB for HBN 1721147 [VXX/27953]

Blank Lab ID: 1293001

QC for Samples: 1155497018

Matrix: Soil/Solid (dry weight)

## Results by AK101

ParameterResultsLOQ/CLDLUnitsGasoline Range Organics1.50J2.500.750mg/Kg

**Surrogates** 

4-Bromofluorobenzene (surr) 79.1 50-150 %

## **Batch Information**

Analytical Batch: VFC12688 Analytical Method: AK101

Instrument: Agilent 7890A PID/FID

Analyst: KAS

Analytical Date/Time: 9/23/2015 10:28:00AM

Prep Batch: VXX27953 Prep Method: SW5035A

Prep Date/Time: 9/23/2015 8:00:00AM

Prep Initial Wt./Vol.: 50 g Prep Extract Vol: 25 mL

Print Date: 10/27/2015 1:51:55PM



Blank Spike ID: LCS for HBN 1155497 [VXX27953]

Blank Spike Lab ID: 1293004 Date Analyzed: 09/23/2015 11:25

QC for Samples: 1155497018

Spike Duplicate ID: LCSD for HBN 1155497

[VXX27953]

Spike Duplicate Lab ID: 1293005 Matrix: Soil/Solid (dry weight)

## Results by AK101

			_							
	Е	Blank Spike (mg/Kg)		Spike Duplicate (mg/Kg)						
<u>Parameter</u>	Spike	Result	Rec (%)	Spike	Result	Rec (%)	CL	RPD (%)	RPD CL	
Gasoline Range Organics	10.0	10.9	109	10.0	10.3	103	(60-120)	5.10	(< 20 )	
Surrogates										
4-Bromofluorobenzene (surr)	1.25	77.5	78	1.25	78.7	79	(50-150)	1.60		

### **Batch Information**

Analytical Batch: VFC12688
Analytical Method: AK101

Instrument: Agilent 7890A PID/FID

Analyst: KAS

Prep Batch: VXX27953
Prep Method: SW5035A

Prep Date/Time: 09/23/2015 08:00

Spike Init Wt./Vol.: 10.0 mg/Kg Extract Vol: 25 mL Dupe Init Wt./Vol.: 10.0 mg/Kg Extract Vol: 25 mL

Print Date: 10/27/2015 1:51:57PM



Blank ID: MB for HBN 1721147 [VXX/27953]

Blank Lab ID: 1293001

QC for Samples: 1155497018

Matrix: Soil/Solid (dry weight)

## Results by SW8021B

<u>Parameter</u>	Results	LOQ/CL	<u>DL</u>	<u>Units</u>
Benzene	6.25U	12.5	4.00	ug/Kg
Ethylbenzene	12.5U	25.0	7.80	ug/Kg
o-Xylene	12.5U	25.0	7.80	ug/Kg
P & M -Xylene	16.8J	50.0	15.0	ug/Kg
Toluene	13.8J	25.0	7.80	ug/Kg
Surrogates				
1,4-Difluorobenzene (surr)	87.6	72-119		%

### **Batch Information**

Analytical Batch: VFC12688 Analytical Method: SW8021B

Instrument: Agilent 7890A PID/FID

Analyst: KAS

Analytical Date/Time: 9/23/2015 10:28:00AM

Prep Batch: VXX27953 Prep Method: SW5035A

Prep Date/Time: 9/23/2015 8:00:00AM

Prep Initial Wt./Vol.: 50 g Prep Extract Vol: 25 mL

Print Date: 10/27/2015 1:51:59PM



Blank Spike ID: LCS for HBN 1155497 [VXX27953]

Blank Spike Lab ID: 1293002 Date Analyzed: 09/23/2015 10:47

QC for Samples: 1155497018

Spike Duplicate ID: LCSD for HBN 1155497

[VXX27953]

Spike Duplicate Lab ID: 1293003 Matrix: Soil/Solid (dry weight)

## Results by SW8021B

	Е	Blank Spike	(ug/Kg)	S	pike Duplic	ate (ug/Kg)			
<u>Parameter</u>	<u>Spike</u>	Result	Rec (%)	Spike	Result	Rec (%)	CL	RPD (%)	RPD CL
Benzene	1250	1330	107	1250	1370	110	(75-125)	2.80	(< 20 )
Ethylbenzene	1250	1270	102	1250	1300	104	(75-125)	2.10	(< 20 )
o-Xylene	1250	1170	94	1250	1200	96	(75-125)	2.40	(< 20 )
P & M -Xylene	2500	2460	98	2500	2530	101	(80-125)	2.70	(< 20 )
Toluene	1250	1300	104	1250	1330	106	(70-125)	2.30	(< 20 )
Surrogates									
1,4-Difluorobenzene (surr)	1250	91	91	1250	91.3	91	(72-119)	0.33	

## **Batch Information**

Analytical Batch: VFC12688 Analytical Method: SW8021B Instrument: Agilent 7890A PID/FID

Analyst: KAS

Prep Batch: VXX27953
Prep Method: SW5035A

Prep Date/Time: 09/23/2015 08:00

Spike Init Wt./Vol.: 1250 ug/Kg Extract Vol: 25 mL Dupe Init Wt./Vol.: 1250 ug/Kg Extract Vol: 25 mL

Print Date: 10/27/2015 1:52:00PM



Blank ID: MB for HBN 1721201 [VXX/27961]

Blank Lab ID: 1293232

QC for Samples:

1155497001, 1155497002, 1155497004, 1155497005, 1155497006, 1155497007, 1155497008, 1155497009, 1155497010,

Matrix: Soil/Solid (dry weight)

1155497011, 1155497012

Results by AK101

ParameterResultsLOQ/CLDLUnitsGasoline Range Organics1.47J2.500.750mg/Kg

**Surrogates** 

4-Bromofluorobenzene (surr) 72.4 50-150 %

**Batch Information** 

Analytical Batch: VFC12692 Prep Batch: VXX27961 Analytical Method: AK101 Prep Method: SW5035A

Instrument: Agilent 7890A PID/FID Prep Date/Time: 9/24/2015 8:00:00AM

Analyst: CRD Prep Initial Wt./Vol.: 50 g Analytical Date/Time: 9/24/2015 2:24:00PM Prep Extract Vol: 25 mL

Print Date: 10/27/2015 1:52:01PM



Blank Spike ID: LCS for HBN 1155497 [VXX27961]

Blank Spike Lab ID: 1293235

Date Analyzed: 09/24/2015 15:21

Spike Duplicate ID: LCSD for HBN 1155497

[VXX27961]

Spike Duplicate Lab ID: 1293236

Matrix: Soil/Solid (dry weight)

QC for Samples: 1155497001, 1155497002, 1155497004, 1155497005, 1155497006, 1155497007, 1155497008,

1155497009, 1155497010, 1155497011, 1155497012

## Results by AK101

	E	Blank Spike	(mg/Kg)	S	pike Duplic	ate (mg/Kg)			
<u>Parameter</u>	<u>Spike</u>	Result	Rec (%)	<u>Spike</u>	Result	Rec (%)	CL	RPD (%)	RPD CL
Gasoline Range Organics	10.0	10.0	100	10.0	10.3	103	(60-120)	3.00	(< 20 )
Surrogates									
4-Bromofluorobenzene (surr)	1.25	80.8	81	1.25	79.4	79	(50-150)	1.70	

### **Batch Information**

Analytical Batch: VFC12692
Analytical Method: AK101

Instrument: Agilent 7890A PID/FID

Analyst: CRD

Prep Batch: VXX27961
Prep Method: SW5035A

Prep Date/Time: 09/24/2015 08:00

Spike Init Wt./Vol.: 10.0 mg/Kg Extract Vol: 25 mL Dupe Init Wt./Vol.: 10.0 mg/Kg Extract Vol: 25 mL

Print Date: 10/27/2015 1:52:04PM



Blank ID: MB for HBN 1721201 [VXX/27961]

Blank Lab ID: 1293232

QC for Samples:

1155497001, 1155497002, 1155497004, 1155497005, 1155497006, 1155497007, 1155497008, 1155497009, 1155497010,

1155497011, 1155497012

## Results by SW8021B

	Б 1	1.00/01	DI	
<u>Parameter</u>	Results Programme Results	LOQ/CL	<u>DL</u>	<u>Units</u>
Benzene	6.25U	12.5	4.00	ug/Kg
Ethylbenzene	12.5U	25.0	7.80	ug/Kg
o-Xylene	12.5U	25.0	7.80	ug/Kg
P & M -Xylene	25.0U	50.0	15.0	ug/Kg
Toluene	11.3J	25.0	7.80	ug/Kg
Surrogates				
1,4-Difluorobenzene (surr)	86.6	72-119		%

### **Batch Information**

Analytical Batch: VFC12692 Analytical Method: SW8021B

Instrument: Agilent 7890A PID/FID

Analyst: CRD

Analytical Date/Time: 9/24/2015 2:24:00PM

Prep Batch: VXX27961 Prep Method: SW5035A

Prep Date/Time: 9/24/2015 8:00:00AM

Matrix: Soil/Solid (dry weight)

Prep Initial Wt./Vol.: 50 g Prep Extract Vol: 25 mL

Print Date: 10/27/2015 1:52:08PM



Blank Spike ID: LCS for HBN 1155497 [VXX27961]

Blank Spike Lab ID: 1293233 Date Analyzed: 09/24/2015 14:43 Spike Duplicate ID: LCSD for HBN 1155497

[VXX27961]

Spike Duplicate Lab ID: 1293234 Matrix: Soil/Solid (dry weight)

QC for Samples: 1155497001, 1155497002, 1155497004, 1155497005, 1155497006, 1155497007, 1155497008,

1155497009, 1155497010, 1155497011, 1155497012

## Results by SW8021B

	E	Blank Spike	(ug/Kg)	S	pike Duplic	ate (ug/Kg)			
<u>Parameter</u>	<u>Spike</u>	Result	Rec (%)	Spike	Result	Rec (%)	CL	RPD (%)	RPD CL
Benzene	1250	1330	106	1250	1320	106	(75-125)	0.64	(< 20 )
Ethylbenzene	1250	1270	101	1250	1270	102	(75-125)	0.16	(< 20 )
o-Xylene	1250	1160	93	1250	1180	94	(75-125)	1.40	(< 20 )
P & M -Xylene	2500	2440	98	2500	2450	98	(80-125)	0.58	(< 20 )
Toluene	1250	1260	101	1250	1250	100	(70-125)	0.32	(< 20 )
Surrogates									
1,4-Difluorobenzene (surr)	1250	89.4	89	1250	89.8	90	(72-119)	0.40	

### **Batch Information**

Analytical Batch: VFC12692 Analytical Method: SW8021B Instrument: Agilent 7890A PID/FID

Analyst: CRD

Prep Batch: VXX27961
Prep Method: SW5035A

Prep Date/Time: 09/24/2015 08:00

Spike Init Wt./Vol.: 1250 ug/Kg Extract Vol: 25 mL Dupe Init Wt./Vol.: 1250 ug/Kg Extract Vol: 25 mL

Print Date: 10/27/2015 1:52:10PM



### **Matrix Spike Summary**

 Original Sample ID: 1155497001
 Analysis Date: 09/24/2015 20:06

 MS Sample ID: 1293952 MS
 Analysis Date: 09/24/2015 20:25

 MSD Sample ID: 1293953 MSD
 Analysis Date: 09/24/2015 20:44

 Matrix: Soil/Solid (dry weight)

QC for Samples: 1155497001, 1155497002, 1155497004, 1155497005, 1155497006, 1155497007, 1155497008,

1155497009, 1155497010, 1155497011, 1155497012

## Results by SW8021B

results by GWGGZTB		Mat	rix Spike (ι	ug/Kg)	Spike	Duplicate	(ug/Kg)			
<u>Parameter</u>	<u>Sample</u>	Spike	Result	Rec (%)	Spike	Result	Rec (%)	CL	RPD (%)	RPD CL
Benzene	12.4U	1510	1607	107	1510	1634	108	75-125	1.10	(< 20)
Ethylbenzene	23.7J	1510	1551	102	1510	1565	102	75-125	0.43	(< 20)
o-Xylene	24.7U	1510	1454	96	1510	1454	96	75-125	0.02	(< 20)
P & M -Xylene	32.6J	3019	3006	99	3019	3019	99	80-125	0.29	(< 20)
Toluene	24.7U	1510	1510	100	1510	1524	101	70-125	0.77	(< 20 )
Surrogates										
1,4-Difluorobenzene (surr)		1510	1357	90	1510	1356	90	72-119	0.11	

#### **Batch Information**

Analytical Batch: VFC12692 Analytical Method: SW8021B

Instrument: Agilent 7890A PID/FID

Analyst: CRD

Analytical Date/Time: 9/24/2015 8:25:00PM

Prep Batch: VXX27961

Prep Method: AK101 Extraction (S)
Prep Date/Time: 9/24/2015 8:00:00AM

Prep Initial Wt./Vol.: 57.42g Prep Extract Vol: 25.00mL

Print Date: 10/27/2015 1:52:11PM



Blank ID: MB for HBN 1721443 [VXX/27969]

Blank Lab ID: 1293514

QC for Samples:

1155497013, 1155497014, 1155497015, 1155497016, 1155497017

Matrix: Soil/Solid (dry weight)

## Results by AK101

ParameterResultsLOQ/CLDLUnitsGasoline Range Organics1.01J2.500.750mg/Kg

**Surrogates** 

4-Bromofluorobenzene (surr) 73 50-150 %

## **Batch Information**

Analytical Batch: VFC12695 Prep Batch: VXX27969
Analytical Method: AK101 Prep Method: SW5035A

Instrument: Agilent 7890A PID/FID Prep Date/Time: 9/26/2015 8:00:00AM

Analyst: CRD Prep Initial Wt./Vol.: 50 g
Analytical Date/Time: 9/26/2015 1:49:00PM Prep Extract Vol: 25 mL

Print Date: 10/27/2015 1:52:12PM



Blank Spike ID: LCS for HBN 1155497 [VXX27969]

Blank Spike Lab ID: 1293517

Date Analyzed: 09/26/2015 14:46

Spike Duplicate ID: LCSD for HBN 1155497

[VXX27969]

Spike Duplicate Lab ID: 1293518

Matrix: Soil/Solid (dry weight)

QC for Samples: 1155497013, 1155497014, 1155497015, 1155497016, 1155497017

## Results by AK101

			_						
	В	lank Spike	(mg/Kg)	S	pike Duplic	ate (mg/Kg)			
<u>Parameter</u>	<u>Spike</u>	Result	Rec (%)	Spike	Result	Rec (%)	CL	RPD (%)	RPD CL
Gasoline Range Organics	10.0	11.6	116	10.0	11.3	113	(60-120)	2.60	(< 20 )
Surrogates									
4-Bromofluorobenzene (surr)	1.25	76.5	77	1.25	77.4	77	(50-150)	1.10	

### **Batch Information**

Analytical Batch: VFC12695
Analytical Method: AK101

Instrument: Agilent 7890A PID/FID

Analyst: CRD

Prep Batch: VXX27969
Prep Method: SW5035A

Prep Date/Time: 09/26/2015 08:00

Spike Init Wt./Vol.: 10.0 mg/Kg Extract Vol: 25 mL Dupe Init Wt./Vol.: 10.0 mg/Kg Extract Vol: 25 mL

Print Date: 10/27/2015 1:52:15PM



Blank ID: MB for HBN 1721443 [VXX/27969]

Blank Lab ID: 1293514

QC for Samples:

1155497013, 1155497014, 1155497015, 1155497016, 1155497017

Matrix: Soil/Solid (dry weight)

## Results by SW8021B

<u>Parameter</u>	Results	LOQ/CL	<u>DL</u>	<u>Units</u>
Benzene	6.25U	12.5	4.00	ug/Kg
Ethylbenzene	12.5U	25.0	7.80	ug/Kg
o-Xylene	12.5U	25.0	7.80	ug/Kg
P & M -Xylene	15.5J	50.0	15.0	ug/Kg
Toluene	12.5J	25.0	7.80	ug/Kg
Surrogates				
1,4-Difluorobenzene (surr)	87.2	72-119		%

### **Batch Information**

Analytical Batch: VFC12695 Analytical Method: SW8021B

Instrument: Agilent 7890A PID/FID

Analyst: CRD

Analytical Date/Time: 9/26/2015 1:49:00PM

Prep Batch: VXX27969 Prep Method: SW5035A

Prep Date/Time: 9/26/2015 8:00:00AM

Prep Initial Wt./Vol.: 50 g Prep Extract Vol: 25 mL

Print Date: 10/27/2015 1:52:16PM



Blank Spike ID: LCS for HBN 1155497 [VXX27969]

Blank Spike Lab ID: 1293515 Date Analyzed: 09/26/2015 14:08 Spike Duplicate ID: LCSD for HBN 1155497

[VXX27969]

Spike Duplicate Lab ID: 1293516 Matrix: Soil/Solid (dry weight)

QC for Samples: 1155497013, 1155497014, 1155497015, 1155497016, 1155497017

## Results by SW8021B

	E	Blank Spike	(ug/Kg)	S	pike Duplic	ate (ug/Kg)			
<u>Parameter</u>	<u>Spike</u>	Result	Rec (%)	<u>Spike</u>	Result	Rec (%)	CL	RPD (%)	RPD CL
Benzene	1250	1320	106	1250	1290	103	(75-125)	2.50	(< 20 )
Ethylbenzene	1250	1240	99	1250	1220	98	(75-125)	1.70	(< 20)
o-Xylene	1250	1140	91	1250	1120	90	(75-125)	1.30	(< 20)
P & M -Xylene	2500	2390	96	2500	2350	94	(80-125)	1.60	(< 20 )
Toluene	1250	1230	99	1250	1210	97	(70-125)	1.60	(< 20 )
Surrogates									
1,4-Difluorobenzene (surr)	1250	91	91	1250	90.6	91	(72-119)	0.48	

# **Batch Information**

Analytical Batch: VFC12695 Analytical Method: SW8021B Instrument: Agilent 7890A PID/FID

Analyst: CRD

Prep Batch: VXX27969
Prep Method: SW5035A

Prep Date/Time: 09/26/2015 08:00

Spike Init Wt./Vol.: 1250 ug/Kg Extract Vol: 25 mL Dupe Init Wt./Vol.: 1250 ug/Kg Extract Vol: 25 mL

Print Date: 10/27/2015 1:52:18PM



### **Matrix Spike Summary**

 Original Sample ID: 1155497013
 Analysis Date: 09/26/2015 16:21

 MS Sample ID: 1293519 MS
 Analysis Date: 09/26/2015 16:40

 MSD Sample ID: 1293520 MSD
 Analysis Date: 09/26/2015 16:59

 Matrix: Soil/Solid (dry weight)

QC for Samples: 1155497013, 1155497014, 1155497015, 1155497016, 1155497017

## Results by SW8021B

		Mat	rix Spike (ι	ug/Kg)	Spike	Duplicate	(ug/Kg)			
<u>Parameter</u>	<u>Sample</u>	Spike	Result	Rec (%)	Spike	Result	Rec (%)	CL	RPD (%)	RPD CL
Benzene	11.4U	1464	1517	103	1464	1491	102	75-125	1.60	(< 20 )
Ethylbenzene	22.6U	1464	1438	98	1464	1412	96	75-125	1.60	(< 20)
o-Xylene	22.6U	1464	1332	91	1464	1305	89	75-125	1.90	(< 20)
P & M -Xylene	45.3U	2929	2770	94	2929	2704	92	80-125	2.10	(< 20)
Toluene	22.6U	1464	1398	95	1464	1385	94	70-125	1.10	(< 20 )
Surrogates										
1,4-Difluorobenzene (surr)		1464	1346	91	1464	1346	92	72-119	0.39	

### **Batch Information**

Analytical Batch: VFC12695 Analytical Method: SW8021B Instrument: Agilent 7890A PID/FID

Analyst: CRD

Analytical Date/Time: 9/26/2015 4:40:00PM

Prep Batch: VXX27969

Prep Method: AK101 Extraction (S)
Prep Date/Time: 9/26/2015 8:00:00AM

Prep Initial Wt./Vol.: 56.19g Prep Extract Vol: 25.00mL

Print Date: 10/27/2015 1:52:19PM



Blank ID: MB for HBN 1721607 [VXX/27983]

Blank Lab ID: 1294286

QC for Samples: 1155497003

Matrix: Soil/Solid (dry weight)

## Results by AK101

ParameterResultsLOQ/CLDLUnitsGasoline Range Organics1.45J2.500.750mg/Kg

**Surrogates** 

4-Bromofluorobenzene (surr) 77.6 50-150 %

## **Batch Information**

Analytical Batch: VFC12701 Analytical Method: AK101

Instrument: Agilent 7890A PID/FID

Analyst: KAS

Analytical Date/Time: 9/29/2015 6:30:00PM

Prep Batch: VXX27983 Prep Method: SW5035A

Prep Date/Time: 9/29/2015 8:00:00AM

Prep Initial Wt./Vol.: 50 g Prep Extract Vol: 25 mL

Print Date: 10/27/2015 1:52:20PM



Blank Spike ID: LCS for HBN 1155497 [VXX27983]

Blank Spike Lab ID: 1294514 Date Analyzed: 09/29/2015 19:27

QC for Samples: 1155497003

Spike Duplicate ID: LCSD for HBN 1155497

[VXX27983]

Spike Duplicate Lab ID: 1294515 Matrix: Soil/Solid (dry weight)

## Results by AK101

	E	Blank Spike	(mg/Kg)	s	pike Duplic	ate (mg/Kg)			
<u>Parameter</u>	Spike	Result	Rec (%)	<u>Spike</u>	Result	Rec (%)	CL	RPD (%)	RPD CL
Gasoline Range Organics	10.0	11.9	119	10.0	11.9	119	(60-120)	0.17	(< 20 )
Surrogates									
4-Bromofluorobenzene (surr)	1.25	79.2	79	1.25	78.8	79	(50-150)	0.58	

### **Batch Information**

Analytical Batch: VFC12701
Analytical Method: AK101

Instrument: Agilent 7890A PID/FID

Analyst: KAS

Prep Batch: VXX27983
Prep Method: SW5035A

Prep Date/Time: 09/29/2015 08:00

Spike Init Wt./Vol.: 10.0 mg/Kg Extract Vol: 25 mL Dupe Init Wt./Vol.: 10.0 mg/Kg Extract Vol: 25 mL

Print Date: 10/27/2015 1:52:23PM



Blank ID: MB for HBN 1721607 [VXX/27983]

Blank Lab ID: 1294286

QC for Samples: 1155497003

Matrix: Soil/Solid (dry weight)

## Results by SW8021B

<u>Parameter</u>	Results	LOQ/CL	<u>DL</u>	<u>Units</u>
Benzene	6.25U	12.5	4.00	ug/Kg
Ethylbenzene	12.5U	25.0	7.80	ug/Kg
o-Xylene	12.5U	25.0	7.80	ug/Kg
P & M -Xylene	25.0U	50.0	15.0	ug/Kg
Toluene	12.5U	25.0	7.80	ug/Kg
Surrogates				
1,4-Difluorobenzene (surr)	88.5	72-119		%

### **Batch Information**

Analytical Batch: VFC12701 Analytical Method: SW8021B

Instrument: Agilent 7890A PID/FID

Analyst: KAS

Analytical Date/Time: 9/29/2015 6:30:00PM

Prep Batch: VXX27983 Prep Method: SW5035A

Prep Date/Time: 9/29/2015 8:00:00AM

Prep Initial Wt./Vol.: 50 g Prep Extract Vol: 25 mL

Print Date: 10/27/2015 1:52:26PM



Blank Spike ID: LCS for HBN 1155497 [VXX27983]

Blank Spike Lab ID: 1294287 Date Analyzed: 09/29/2015 18:49

QC for Samples: 1155497003

Spike Duplicate ID: LCSD for HBN 1155497

[VXX27983]

Spike Duplicate Lab ID: 1294288 Matrix: Soil/Solid (dry weight)

## Results by SW8021B

	E	Blank Spike (ug/Kg)		Spike Duplicate (ug/Kg)					
<u>Parameter</u>	<u>Spike</u>	Result	Rec (%)	Spike	Result	Rec (%)	CL	RPD (%)	RPD CL
Benzene	1250	1360	109	1250	1340	107	(75-125)	1.90	(< 20 )
Ethylbenzene	1250	1290	103	1250	1270	102	(75-125)	1.80	(< 20 )
o-Xylene	1250	1190	95	1250	1170	94	(75-125)	1.10	(< 20 )
P & M -Xylene	2500	2490	99	2500	2450	98	(80-125)	1.50	(< 20 )
Toluene	1250	1260	101	1250	1240	99	(70-125)	2.10	(< 20 )
Surrogates									
1,4-Difluorobenzene (surr)	1250	91.3	91	1250	91	91	(72-119)	0.37	

## **Batch Information**

Analytical Batch: VFC12701 Analytical Method: SW8021B Instrument: Agilent 7890A PID/FID

Analyst: KAS

Prep Batch: VXX27983
Prep Method: SW5035A

Prep Date/Time: 09/29/2015 08:00

Spike Init Wt./Vol.: 1250 ug/Kg Extract Vol: 25 mL Dupe Init Wt./Vol.: 1250 ug/Kg Extract Vol: 25 mL

Print Date: 10/27/2015 1:52:27PM



### **Matrix Spike Summary**

Original Sample ID: 1158662003 MS Sample ID: 1294662 MS MSD Sample ID: 1294663 MSD

QC for Samples: 1155497003

Analysis Date: 09/29/2015 21:40 Analysis Date: 09/29/2015 21:59 Analysis Date: 09/29/2015 22:18 Matrix: Soil/Solid (dry weight)

## Results by SW8021B

		Matrix Spike (ug/Kg)		Spike Duplicate (ug/Kg)						
<u>Parameter</u>	<u>Sample</u>	Spike	Result	Rec (%)	Spike	Result	Rec (%)	CL	RPD (%)	RPD CL
Benzene	17.0U	2751	2977	108	2751	3028	110	75-125	1.80	(< 20)
Ethylbenzene	34.0U	2751	2839	103	2751	2877	104	75-125	1.50	(< 20)
o-Xylene	34.0U	2751	2601	95	2751	2638	96	75-125	1.10	(< 20)
P & M -Xylene	68.0U	5515	5465	99	5515	5553	101	80-125	1.60	(< 20)
Toluene	34.0U	2751	2877	104	2751	2915	106	70-125	1.50	(< 20 )
Surrogates										
1,4-Difluorobenzene (surr)		2751	2500	91	2751	2500	91	72-119	0.20	

### **Batch Information**

Analytical Batch: VFC12701 Analytical Method: SW8021B Instrument: Agilent 7890A PID/FID

Analyst: KAS

Analytical Date/Time: 9/29/2015 9:59:00PM

Prep Batch: VXX27983

Prep Method: AK101 Extraction (S)
Prep Date/Time: 9/29/2015 8:00:00AM

Prep Initial Wt./Vol.: 28.48g Prep Extract Vol: 25.00mL

Print Date: 10/27/2015 1:52:29PM



Blank ID: MB for HBN 1721488 [XXX/34262]

Blank Lab ID: 1293748

QC for Samples:

1155497001, 1155497002, 1155497003, 1155497004, 1155497005, 1155497008, 1155497009, 1155497010, 1155497014,

Matrix: Soil/Solid (dry weight)

1155497015, 1155497016, 1155497017

Results by AK102

 Parameter
 Results
 LOQ/CL
 DL
 Units

 Diesel Range Organics
 10.0U
 20.0
 6.20
 mg/Kg

**Surrogates** 

5a Androstane (surr) 76.5 60-120 %

**Batch Information** 

Analytical Batch: XFC12126 Prep Batch: XXX34262
Analytical Method: AK102 Prep Method: SW3550C

Instrument: HP 6890 Series II FID SV D R Prep Date/Time: 9/28/2015 5:31:35PM

Analyst: NLL Prep Initial Wt./Vol.: 30 g Analytical Date/Time: 10/4/2015 1:34:00AM Prep Extract Vol: 1 mL

Print Date: 10/27/2015 1:52:30PM



Blank Spike ID: LCS for HBN 1155497 [XXX34262]

Blank Spike Lab ID: 1293749

Date Analyzed: 10/04/2015 01:44

Spike Duplicate ID: LCSD for HBN 1155497

[XXX34262]

Spike Duplicate Lab ID: 1293750

Matrix: Soil/Solid (dry weight)

QC for Samples: 1155497001, 1155497002, 1155497003, 1155497004, 1155497005, 1155497009,

1155497010, 1155497014, 1155497015, 1155497016, 1155497017

## Results by AK102

	E	Blank Spike	(mg/Kg)	Spike Duplicate (mg/Kg)					
<u>Parameter</u>	Spike	Result	Rec (%)	<u>Spike</u>	Result	Rec (%)	CL	RPD (%)	RPD CL
Diesel Range Organics	167	137	82	167	136	82	(75-125)	0.74	(< 20 )
Surrogates									
5a Androstane (surr)	3.33	86.1	86	3.33	87.5	88	(60-120)	1.50	

### **Batch Information**

Analytical Batch: **XFC12126** Analytical Method: **AK102** 

Instrument: HP 6890 Series II FID SV D R

Analyst: NLL

Prep Batch: XXX34262
Prep Method: SW3550C

Prep Date/Time: 09/28/2015 17:31

Spike Init Wt./Vol.: 167 mg/Kg Extract Vol: 1 mL Dupe Init Wt./Vol.: 167 mg/Kg Extract Vol: 1 mL

Print Date: 10/27/2015 1:52:33PM



Blank ID: MB for HBN 1721488 [XXX/34262]

Blank Lab ID: 1293748

QC for Samples:

1155497001, 1155497002, 1155497003, 1155497004, 1155497005, 1155497008, 1155497009, 1155497010, 1155497014,

Matrix: Soil/Solid (dry weight)

1155497015, 1155497016, 1155497017

Results by AK103

ParameterResultsLOQ/CLDLUnitsResidual Range Organics10.0U20.06.20mg/Kg

**Surrogates** 

n-Triacontane-d62 (surr) 84.2 60-120 %

**Batch Information** 

Analytical Batch: XFC12126 Prep Batch: XXX34262
Analytical Method: AK103 Prep Method: SW3550C

Instrument: HP 6890 Series II FID SV D R Prep Date/Time: 9/28/2015 5:31:35PM

Analyst: NLL Prep Initial Wt./Vol.: 30 g Analytical Date/Time: 10/4/2015 1:34:00AM Prep Extract Vol: 1 mL

Print Date: 10/27/2015 1:52:35PM



Blank Spike ID: LCS for HBN 1155497 [XXX34262]

Blank Spike Lab ID: 1293749

Date Analyzed: 10/04/2015 01:44

Spike Duplicate ID: LCSD for HBN 1155497

[XXX34262]

Spike Duplicate Lab ID: 1293750

Matrix: Soil/Solid (dry weight)

QC for Samples: 1155497001, 1155497002, 1155497003, 1155497004, 1155497005, 1155497008, 1155497009,

1155497010, 1155497014, 1155497015, 1155497016, 1155497017

#### Results by AK103

	F	Blank Spike	(ma/Ka)	9	nika Dunlic	ate (mg/Kg)			
		•				, , ,	0.1	DDD (0()	555 61
<u>Parameter</u>	<u>Spike</u>	Result	<u>Rec (%)</u>	<u>Spike</u>	Result	Rec (%)	<u>CL</u>	<u>RPD (%)</u>	RPD CL
Residual Range Organics	167	153	92	167	157	94	(60-120)	2.60	(< 20)
Surrogates									
n-Triacontane-d62 (surr)	3.33	77.6	78	3.33	80.1	80	(60-120)	3.20	

#### **Batch Information**

Analytical Batch: **XFC12126** Analytical Method: **AK103** 

Instrument: HP 6890 Series II FID SV D R

Analyst: NLL

Prep Batch: XXX34262
Prep Method: SW3550C

Prep Date/Time: 09/28/2015 17:31

Spike Init Wt./Vol.: 167 mg/Kg Extract Vol: 1 mL Dupe Init Wt./Vol.: 167 mg/Kg Extract Vol: 1 mL

Print Date: 10/27/2015 1:52:36PM



Blank ID: MB for HBN 1721563 [XXX/34274]

Blank Lab ID: 1294085

QC for Samples:

1155497006, 1155497007, 1155497011, 1155497012

Matrix: Soil/Solid (dry weight)

Results by AK102

LOQ/CL Results <u>Units</u> <u>Parameter</u> DL 20.0U DRO Silica Gel 40.0 12.4 mg/Kg

**Surrogates** 

5a Androstane (surr) 93.8 70-125 %

**Batch Information** 

Analytical Batch: XFC12133 Prep Batch: XXX34274

Analytical Method: AK102

Instrument: HP 7890A FID SV E F

Analyst: KJO

Analytical Date/Time: 10/4/2015 11:15:00PM

Prep Method: SW3550C w/SG Cleanup Prep Date/Time: 9/30/2015 8:29:19AM

Prep Initial Wt./Vol.: 30 g Prep Extract Vol: 2 mL

Print Date: 10/27/2015 1:52:39PM



Blank Spike ID: LCS for HBN 1155497 [XXX34274]

Blank Spike Lab ID: 1294086

Date Analyzed: 10/04/2015 23:36

Spike Duplicate ID: LCSD for HBN 1155497

[XXX34274]

Spike Duplicate Lab ID: 1294087

Matrix: Soil/Solid (dry weight)

QC for Samples: 1155497006, 1155497007, 1155497011, 1155497012

#### Results by AK102

( -									
	E	Blank Spike	(mg/Kg)	S	pike Duplic	ate (mg/Kg)			
<u>Parameter</u>	<u>Spike</u>	Result	Rec (%)	<u>Spike</u>	Result	Rec (%)	CL	RPD (%)	RPD CL
DRO Silica Gel	333	342	103	333	335	101	(70-125)	2.00	(< 20 )
Surrogates									
5a Androstane (surr)	6.67	98.4	98	6.67	99.3	99	(70-125)	0.82	

#### **Batch Information**

Analytical Batch: XFC12133

Analytical Method: AK102

Instrument: HP 7890A FID SV E F

Analyst: KJO

Prep Batch: XXX34274

Prep Method: SW3550C w/SG Cleanup

Prep Date/Time: 09/30/2015 08:29

Spike Init Wt./Vol.: 333 mg/Kg Extract Vol: 2 mL Dupe Init Wt./Vol.: 333 mg/Kg Extract Vol: 2 mL

Print Date: 10/27/2015 1:52:41PM



Blank ID: MB for HBN 1721563 [XXX/34274]

Blank Lab ID: 1294085

QC for Samples:

1155497006, 1155497007, 1155497011, 1155497012

Matrix: Soil/Solid (dry weight)

Results by AK103

 Parameter
 Results
 LOQ/CL
 DL
 Units

 RRO Silica Gel
 20.0U
 40.0
 12.4
 mg/Kg

**Surrogates** 

n-Triacontane-d62 (surr) 94.4 70-125 %

**Batch Information** 

Analytical Batch: XFC12133

Analytical Method: AK103

Instrument: HP 7890A FID SV E F

Analyst: KJO

Analytical Date/Time: 10/4/2015 11:15:00PM

Prep Batch: XXX34274

Prep Method: SW3550C w/SG Cleanup Prep Date/Time: 9/30/2015 8:29:19AM

Prep Initial Wt./Vol.: 30 g Prep Extract Vol: 2 mL

Print Date: 10/27/2015 1:52:43PM



Blank Spike ID: LCS for HBN 1155497 [XXX34274]

Blank Spike Lab ID: 1294086

Date Analyzed: 10/04/2015 23:36

Spike Duplicate ID: LCSD for HBN 1155497

[XXX34274]

Spike Duplicate Lab ID: 1294087

Matrix: Soil/Solid (dry weight)

QC for Samples: 1155497006, 1155497007, 1155497011, 1155497012

#### Results by AK103

	В	lank Spike	(mg/Kg)	S	pike Duplic	ate (mg/Kg)			
<u>Parameter</u>	<u>Spike</u>	Result	Rec (%)	<u>Spike</u>	Result	Rec (%)	CL	RPD (%)	RPD CL
RRO Silica Gel	333	337	101	333	333	100	(70-125)	1.30	(< 20 )
Surrogates									
n-Triacontane-d62 (surr)	6.67	93.4	93	6.67	93.2	93	(70-125)	0.20	

#### **Batch Information**

Analytical Batch: **XFC12133** Analytical Method: **AK103** 

Instrument: HP 7890A FID SV E F

Analyst: KJO

Prep Batch: XXX34274

Prep Method: SW3550C w/SG Cleanup Prep Date/Time: 09/30/2015 08:29

Spike Init Wt./Vol.: 333 mg/Kg Extract Vol: 2 mL Dupe Init Wt./Vol.: 333 mg/Kg Extract Vol: 2 mL

Print Date: 10/27/2015 1:52:46PM



Blank ID: MB for HBN 1721564 [XXX/34275]

Blank Lab ID: 1294088

QC for Samples:

1155497006, 1155497007, 1155497011, 1155497012

Matrix: Soil/Solid (dry weight)

#### Results by AK102

LOQ/CL Results <u>Units</u> <u>Parameter</u> DL Diesel Range Organics 20.0U 40.0 12.4 mg/Kg

**Surrogates** 

5a Androstane (surr) 103 60-120 %

#### **Batch Information**

Analytical Batch: XFC12133 Prep Batch: XXX34275 Analytical Method: AK102 Prep Method: SW3550C

Instrument: HP 7890A FID SV E F Prep Date/Time: 9/30/2015 8:29:31AM

Analyst: KJO Prep Initial Wt./Vol.: 30 g

Analytical Date/Time: 10/4/2015 5:09:00PM Prep Extract Vol: 2 mL

Print Date: 10/27/2015 1:52:48PM



Blank Spike ID: LCS for HBN 1155497 [XXX34275]

Blank Spike Lab ID: 1294089

Date Analyzed: 10/04/2015 17:46

Spike Duplicate ID: LCSD for HBN 1155497

[XXX34275]

Spike Duplicate Lab ID: 1294090

Matrix: Soil/Solid (dry weight)

QC for Samples: 1155497006, 1155497007, 1155497011, 1155497012

#### Results by AK102

	E	Blank Spike	(mg/Kg)	S	pike Duplic	ate (mg/Kg)			
<u>Parameter</u>	<u>Spike</u>	Result	Rec (%)	<u>Spike</u>	Result	Rec (%)	CL	RPD (%)	RPD CL
Diesel Range Organics	333	367	110	333	350	105	(75-125)	4.80	(< 20 )
Surrogates									
5a Androstane (surr)	6.67	102	102	6.67	99.1	99	(60-120)	3.10	

#### **Batch Information**

Analytical Batch: **XFC12133** Analytical Method: **AK102** 

Instrument: HP 7890A FID SV E F

Analyst: KJO

Prep Batch: XXX34275
Prep Method: SW3550C

Prep Date/Time: 09/30/2015 08:29

Spike Init Wt./Vol.: 333 mg/Kg Extract Vol: 2 mL Dupe Init Wt./Vol.: 333 mg/Kg Extract Vol: 2 mL

Print Date: 10/27/2015 1:52:50PM



Blank ID: MB for HBN 1721564 [XXX/34275]

Blank Lab ID: 1294088

QC for Samples:

1155497006, 1155497007, 1155497011, 1155497012

Matrix: Soil/Solid (dry weight)

#### Results by AK103

ParameterResultsLOQ/CLDLUnitsResidual Range Organics20.0U40.012.4mg/Kg

**Surrogates** 

n-Triacontane-d62 (surr) 102 60-120 %

#### **Batch Information**

Analytical Batch: XFC12133 Analytical Method: AK103

Instrument: HP 7890A FID SV E F

Analyst: KJO

Analytical Date/Time: 10/4/2015 5:09:00PM

Prep Batch: XXX34275 Prep Method: SW3550C

Prep Date/Time: 9/30/2015 8:29:31AM

Prep Initial Wt./Vol.: 30 g Prep Extract Vol: 2 mL

Print Date: 10/27/2015 1:52:52PM



Blank Spike ID: LCS for HBN 1155497 [XXX34275]

Blank Spike Lab ID: 1294089

Date Analyzed: 10/04/2015 17:46

Spike Duplicate ID: LCSD for HBN 1155497

[XXX34275]

Spike Duplicate Lab ID: 1294090

Matrix: Soil/Solid (dry weight)

QC for Samples: 1155497006, 1155497007, 1155497011, 1155497012

#### Results by AK103

	Е	Blank Spike	(mg/Kg)	s	pike Duplic	ate (mg/Kg)			
<u>Parameter</u>	<u>Spike</u>	Result	Rec (%)	<u>Spike</u>	Result	Rec (%)	<u>CL</u>	RPD (%)	RPD CL
Residual Range Organics	333	353	106	333	336	101	(60-120)	5.00	(< 20 )
Surrogates									
n-Triacontane-d62 (surr)	6.67	103	103	6.67	99.8	100	(60-120)	3.50	

#### **Batch Information**

Analytical Batch: **XFC12133** Analytical Method: **AK103** 

Instrument: HP 7890A FID SV E F

Analyst: KJO

Prep Batch: XXX34275
Prep Method: SW3550C

Prep Date/Time: 09/30/2015 08:29

Spike Init Wt./Vol.: 333 mg/Kg Extract Vol: 2 mL Dupe Init Wt./Vol.: 333 mg/Kg Extract Vol: 2 mL

Print Date: 10/27/2015 1:52:54PM



Blank ID: MB for HBN 1723058 [XXX/34452]

Blank Lab ID: 1298665

QC for Samples: 1155497013

Matrix: Soil/Solid (dry weight)

#### Results by AK102

 Parameter
 Results
 LOQ/CL
 DL
 Units

 DRO Silica Gel
 20.0U
 40.0
 12.4
 mg/Kg

**Surrogates** 

5a Androstane (surr) 76.3 70-125 %

#### **Batch Information**

Analytical Batch: XFC12174 Analytical Method: AK102

Instrument: HP 7890A FID SV E F

Analyst: KJO

Analytical Date/Time: 10/20/2015 6:36:00PM

Prep Batch: XXX34452

Prep Method: SW3550C w/SG Cleanup Prep Date/Time: 10/19/2015 12:44:56PM

Prep Initial Wt./Vol.: 30 g Prep Extract Vol: 2 mL

Print Date: 10/27/2015 1:52:56PM



Blank Spike ID: LCS for HBN 1155497 [XXX34452]

Blank Spike Lab ID: 1298666 Date Analyzed: 10/20/2015 18:56

QC for Samples: 1155497013

Spike Duplicate ID: LCSD for HBN 1155497

[XXX34452]

Spike Duplicate Lab ID: 1298667 Matrix: Soil/Solid (dry weight)

#### Results by AK102

	E	Blank Spike	(mg/Kg)	S	pike Duplic	ate (mg/Kg)			
<u>Parameter</u>	<u>Spike</u>	Result	Rec (%)	<u>Spike</u>	Result	Rec (%)	CL	RPD (%)	RPD CL
DRO Silica Gel	333	264	79	333	291	87	(70-125)	9.70	(< 20 )
Surrogates									
5a Androstane (surr)	6.67	86.6	87	6.67	93.6	94	(70-125)	7.80	

#### **Batch Information**

Analytical Batch: **XFC12174** Analytical Method: **AK102** 

Instrument: HP 7890A FID SV E F

Analyst: KJO

Prep Batch: XXX34452

Prep Method: SW3550C w/SG Cleanup Prep Date/Time: 10/19/2015 12:44

Spike Init Wt./Vol.: 333 mg/Kg Extract Vol: 2 mL Dupe Init Wt./Vol.: 333 mg/Kg Extract Vol: 2 mL

Print Date: 10/27/2015 1:52:59PM



Blank ID: MB for HBN 1723058 [XXX/34452]

Blank Lab ID: 1298665

QC for Samples: 1155497013

Matrix: Soil/Solid (dry weight)

#### Results by AK103

 Parameter
 Results
 LOQ/CL
 DL
 Units

 RRO Silica Gel
 20.0U
 40.0
 12.4
 mg/Kg

**Surrogates** 

n-Triacontane-d62 (surr) 83 70-125 %

#### **Batch Information**

Analytical Batch: XFC12174 Analytical Method: AK103

Instrument: HP 7890A FID SV E F

Analyst: KJO

Analytical Date/Time: 10/20/2015 6:36:00PM

Prep Batch: XXX34452

Prep Method: SW3550C w/SG Cleanup Prep Date/Time: 10/19/2015 12:44:56PM

Prep Initial Wt./Vol.: 30 g Prep Extract Vol: 2 mL

Print Date: 10/27/2015 1:53:01PM



Blank Spike ID: LCS for HBN 1155497 [XXX34452]

Blank Spike Lab ID: 1298666 Date Analyzed: 10/20/2015 18:56

QC for Samples: 1155497013

Spike Duplicate ID: LCSD for HBN 1155497

[XXX34452]

Spike Duplicate Lab ID: 1298667 Matrix: Soil/Solid (dry weight)

#### Results by AK103

	Е	Blank Spike	(mg/Kg)	s	pike Duplic	ate (mg/Kg)			
<u>Parameter</u>	<u>Spike</u>	Result	Rec (%)	<u>Spike</u>	Result	Rec (%)	CL	RPD (%)	RPD CL
RRO Silica Gel	333	301	90	333	306	92	(70-125)	1.60	(< 20 )
Surrogates									
n-Triacontane-d62 (surr)	6.67	84.8	85	6.67	88.1	88	(70-125)	3.80	

#### **Batch Information**

Analytical Batch: **XFC12174** Analytical Method: **AK103** 

Instrument: HP 7890A FID SV E F

Analyst: KJO

Prep Batch: XXX34452

Prep Method: SW3550C w/SG Cleanup Prep Date/Time: 10/19/2015 12:44

Spike Init Wt./Vol.: 333 mg/Kg  $\,$  Extract Vol: 2 mL Dupe Init Wt./Vol.: 333 mg/Kg  $\,$  Extract Vol: 2 mL  $\,$ 

Print Date: 10/27/2015 1:53:03PM



Blank ID: MB for HBN 1723077 [XXX/34453]

Blank Lab ID: 1298757

QC for Samples: 1155497013

Matrix: Soil/Solid (dry weight)

#### Results by AK102

ParameterResultsLOQ/CLDLUnitsDiesel Range Organics20.0U40.012.4mg/Kg

**Surrogates** 

5a Androstane (surr) 96.9 60-120 %

#### **Batch Information**

Analytical Batch: XFC12174 Analytical Method: AK102

Instrument: HP 7890A FID SV E F

Analyst: KJO

Analytical Date/Time: 10/21/2015 4:01:00AM

Prep Batch: XXX34453 Prep Method: SW3550C

Prep Date/Time: 10/19/2015 12:44:17PM

Prep Initial Wt./Vol.: 30 g Prep Extract Vol: 2 mL

Print Date: 10/27/2015 1:53:05PM



Blank Spike ID: LCS for HBN 1155497 [XXX34453]

Blank Spike Lab ID: 1298758 Date Analyzed: 10/21/2015 04:21

QC for Samples: 1155497013

Spike Duplicate ID: LCSD for HBN 1155497

[XXX34453]

Spike Duplicate Lab ID: 1298759 Matrix: Soil/Solid (dry weight)

#### Results by AK102

	В	lank Spike	(mg/Kg)	s	pike Duplic	ate (mg/Kg)			
<u>Parameter</u>	<u>Spike</u>	Result	Rec (%)	<u>Spike</u>	Result	Rec (%)	CL	RPD (%)	RPD CL
Diesel Range Organics	333	321	96	333	326	98	(75-125)	1.50	(< 20 )
Surrogates									
5a Androstane (surr)	6.67	102	102	6.67	105	105	(60-120)	2.20	

#### **Batch Information**

Analytical Batch: **XFC12174** Analytical Method: **AK102** 

Instrument: HP 7890A FID SV E F

Analyst: KJO

Prep Batch: XXX34453
Prep Method: SW3550C

Prep Date/Time: 10/19/2015 12:44

Spike Init Wt./Vol.: 333 mg/Kg Extract Vol: 2 mL Dupe Init Wt./Vol.: 333 mg/Kg Extract Vol: 2 mL

Print Date: 10/27/2015 1:53:07PM



Blank ID: MB for HBN 1723077 [XXX/34453]

Blank Lab ID: 1298757

QC for Samples: 1155497013

Matrix: Soil/Solid (dry weight)

#### Results by AK103

ParameterResultsLOQ/CLDLUnitsResidual Range Organics20.0U40.012.4mg/Kg

**Surrogates** 

n-Triacontane-d62 (surr) 98.4 60-120 %

#### **Batch Information**

Analytical Batch: XFC12174 Analytical Method: AK103

Instrument: HP 7890A FID SV E F

Analyst: KJO

Analytical Date/Time: 10/21/2015 4:01:00AM

Prep Batch: XXX34453 Prep Method: SW3550C

Prep Date/Time: 10/19/2015 12:44:17PM

Prep Initial Wt./Vol.: 30 g Prep Extract Vol: 2 mL

Print Date: 10/27/2015 1:53:09PM



Blank Spike ID: LCS for HBN 1155497 [XXX34453]

Blank Spike Lab ID: 1298758 Date Analyzed: 10/21/2015 04:21

QC for Samples: 1155497013

Spike Duplicate ID: LCSD for HBN 1155497

[XXX34453]

Spike Duplicate Lab ID: 1298759 Matrix: Soil/Solid (dry weight)

#### Results by AK103

	E	Blank Spike	(mg/Kg)	S	pike Duplic	ate (mg/Kg)			
<u>Parameter</u>	<u>Spike</u>	Result	Rec (%)	<u>Spike</u>	Result	Rec (%)	CL	RPD (%)	RPD CL
Residual Range Organics	333	319	96	333	320	96	(60-120)	0.37	(< 20 )
Surrogates									
n-Triacontane-d62 (surr)	6.67	97.3	97	6.67	97.3	97	(60-120)	0.02	

#### **Batch Information**

Analytical Batch: **XFC12174** Analytical Method: **AK103** 

Instrument: HP 7890A FID SV E F

Analyst: KJO

Prep Batch: **XXX34453**Prep Method: **SW3550C** 

Prep Date/Time: 10/19/2015 12:44

Spike Init Wt./Vol.: 333 mg/Kg Extract Vol: 2 mL Dupe Init Wt./Vol.: 333 mg/Kg Extract Vol: 2 mL

Print Date: 10/27/2015 1:53:11PM



SHANNON & WILSON, I Geotechnical and Environmental Consu	NC. CHA	IN-OI	F-CI	JST	ODY	RE	CORI	D	Labora Attn:_	atory.	SGS Page of 2
400 N. 34th Street, Suite 100 Seattle, WA 98103 (206) 632-8020  2043 Westport Center St. Louis, MO 63146-3 (314) 699-9660	564 Pasco, WA 99301 (509) 946-6309		e A		•	Analy	sis Paramete	ers/Sample C e preservativ	Container D		-
2355 Hill Road Fairbanks, AK 99709 (907) 479-0600 5430 Fairbanks Street Anchorage, AK 99518 (907) 561-2120				//		<u>~</u>		S) A	2/1 2/1	$\overline{/}$	
3990 Collins Way, Suite 100 Lake Oswego, OR 97035 Denver, CO 80204 (503) 223-6147 (303) 825-3800		Date	/2/					FY/U		<u></u>	Remarks/Matrix
Sample Identity Lab No.		mpled	500 Sp	<u>/ Q`</u>	<u>/ 💸 </u>	<u>/</u>	30 / E	T Jos		\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	Remarks/Matrix
HTHY - PPSI/PPSII-B () A-	b 08:32 9	117/15	X	X	X	×	(   X	ļ		2	SOIL
- PPS1/PPS11-3-A 2/A-	08:42		111	1_							
- PPS10-D (3)A-1	08:52										
-PPS10-1-B (4)A-	3 09:40										
-PPS10-2-B (5)A-	B 09:00									1	
- PPS10-3-0 (6)A-1	3 09:35							X			
- PPS 10 - 3 - DX (1)A - P	09:37							X		1	
- PPS10-4-B (8)A-	09:18										
- PPS12-C (9)A-B	10:01										
- PPS12-2-A (10)A-1	10:09	<u> </u>	<u>                                      </u>	<u> </u>	4	1	4			T .	<b>+</b>
Project Information	Sample Receipt	F	Reling	uished	Bý:		Reling	uished B	y: 2.		Relinguished By: 3.
	umber of Containers	Signa	ture:	Ī	ime: 10 ·01		Signature:	Time	):	Sigi	nature: Time:
	eals/Intact? Y/N/NA	Printe	d-Name:		Date: 9/27	1,0	Printed Name:	Date		Prin	nted Name: Date:
7	ed Good Cond./Cold y Method:	TR	FOU ON	_ CROS			rimod riamo.	Date			ned Name.
Grigoring Project: 163 L2 140 42	•	Comp	any:		<del></del>		Company:	•		Cor	mpany:
719.74	hipping bill, if any)	<u>     </u>  \$6	4 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	in Estim	V142-14-13	63.41	Section Const.	1 4 2 3 3 4 3		ra lauran	
Instructions		Signa	W. a	ed By:	ime:		ACADE CARREST TAR ST. ACAD. A	red By:	2.4		Received By: 3,
Requested Turnaround Time: STANDALL Special Instructions:	<b>)</b>	Sigria	ult.				Signature:	Time	i	- Sign	resture: Time: (00)
LEVEL 2		Printe	d Name:		)ate:	_	Printed Name:	Date	:	- 123	ited Name: Date: 9/22/15
Distribution: White - w/shipment - returned to Shan Yellow - w/shipment - for consignee fil Pink - Shannon & Wilson - Job File		port Comp	any:				Company:			Co	mpany: 9eg/: 4/58lat

# 1155497

SHANNON & WILSON, INC. Geotechnical and Environmental Consultants	CHAIN	<b>N-OF-</b> C	UST	ODY	REC	ORE	)	Labor	ratory	SGS Page 2 of 2
400 N. 34th Street, Suite 100 Seattle, WA 98103 (206) 632-8020  2043 Westport Center Drive St. Louis, MO 63146-3564 (314) 699-9660	2705 Saint Andrews L Pasco, WA 99301-337 (509) 946-6309	oop, Suite A '8			Analysis l		s/Sample (	_:Attn   Container	LOK	<u></u>
2355 Hill Road Fairbanks, AK 99709 (907) 479-0600  3990 Collins Way, Suite 100 Lake Oswego, OR 97035 (503) 223-6147  5430 Fairbanks Street, Suite 3 Anchorage, AK 99518 (907) 561-2120  1321 Bannock Street, Suite 200 Denver, CO 80204 (303) 825-3800	) Date	. <u>/</u> :		, i				Silver (Section )		Authorite Co.
Sample Identity vip 10/27/15 Lab No.	Time Sampl	ed Co	100 AD	Q.Q.S	\ (&		* 40	/ ,	\3\gamma\2	Remarks/Matrix
17247-PP512-3-C-13 (4) A-B	10:20 9/17			×	×	X	×		2_	SOIL
- PPS12-3-CX (2)A-B	10:22		<del>                                      </del>				×			
- PPS13 - C-11 ( A - B	10:40									
- PPS13-1-A (4) A-15	10:50								T	
-PPS13-2-B (5)A-B	10:59									
-TFI (6)A-B	13:14	_								
-TF2 DA-B	13:21	1	1	1	1	1			1	<b>1</b>
V-TB1 (18)A	13:30 —				×	X			1	TRIP BLANK
										20,00
Project Information Samp	ole Receipt	Relin	quished	i By:	1.	Relinqu	ished E	By: ₹ 2.*		Relinquished By: 3.
Project Number: 32-1-17747 Total Number		Signature:		Time: _ /0 : 4	2/ Sign	ature:	Time	9:	Sig	nature: Time:
Project Name: Pitkas Point COC Seals/Int		Printed Kam	: 1	Date: _ <u>1</u> /7	2/15 Print	ted Name:	Date	<del></del>	Prir	nted Name: Date:
Contact: TMT, TWC Received Good Ongoing Project? Yes No Delivery Meth		Thom	CHERRY							
Sampler: TWC (attach shipping	bill, if any)	Company:	f		Con	npany:			Cor	mpany:
Instructions	The state of the s	Rece	ived By		i.	Receive	ed By:	2.		Received By: 3.
Requested Turnaround Time: STANDARD	The state of the s	Signature:	State and State of St	Time:	20,000	ature:	Time		- P. W. (1995)	pature: Time: 10:01
Special Instructions:		Printed Nam	e. L	Date:	Drina	ed Name:	Date		16	Kales Cleda
LEVEL 2		Iod Ham				ou name:	Date	·		ted Name: Pate: 1/24/15
Distribution: White - w/shipment - returned to Shannon & W Yellow - w/shipment - for consignee files Pink - Shannon & Wilson - Job File	ilson w/ laboratory report	Company:			Com	pany:				mpany: Absent Seat



# 1155497



## SAMPLE RECEIPT FORM

Review Criteria:	Yes	N/A	No	Comments/Action Taken:
Were <b>custody seals</b> intact? Note # & location, if applicable. COC accompanied samples?	7	<b>√</b>		Exemption permitted if sampler hand carries/delivers.
<b>Temperature blank</b> compliant* (i.e., 0-6°C after CF)?	7	$\Box$		Exemption permitted if chilled & collected <8 hrs ago.
If $>$ 6°C, were samples collected $<$ 8 hours ago?		7	Ħ	
If $< 0$ °C, were all sample containers ice free?		$\overline{\mathbf{V}}$		
Cooler ID: 1 @ 1.8 w/ Therm.ID: D3				
Cooler ID:				
Cooler ID: (a) w/ Therm.ID:				
Cooler ID: (a) w/ Therm.ID:				
Cooler ID: (a) w/ Therm.ID:				
If samples are received without a temperature blank, the "cooler				
temperature" will be documented in lieu of the temperature blank &				Note: Identify containers received at non-compliant
"COOLER TEMP" will be noted to the right. In cases where neither a temp blank nor cooler temp can be obtained, note "ambient" or "chilled."				temperature. Use form FS-0029 if more space is needed.
Delivery method (specify all that apply):  Client (hand carried)				
□USPS □ Lynden □ AK Air □ Alert Courier				
□UPS □FedEx □RAVN □C&D Delivery				
☐Carlile ☐Pen Air ☐Warp Speed☐Other:				
→ For WO# with airbills, was the WO# & airbill				
info recorded in the Front Counter eLog?		$\checkmark$		
	Yes	N/A	No	
Were samples received within hold time?	<b>V</b>			Note: Refer to form F-083 "Sample Guide" for hold times.
Do samples <b>match COC*</b> (i.e., sample IDs, dates/times collected)?				Note: If times differ <1hr, record details and login per COC.
Were analyses requested unambiguous?	<b>√</b>			
Were samples in <b>good condition</b> (no leaks/cracks/breakage)?	<b>\</b>			
Packing material used (specify all that apply): Bubble Wrap				
Separate plastic bags Vermiculite Other:				
Were <b>proper containers</b> (type/mass/volume/preservative*) used?	<b>√</b>			Exemption permitted for metals (e.g., 200.8/6020A).
Were <b>Trip Blanks</b> (i.e., VOAs, LL-Hg) in cooler with samples?		Ц	$\sqcup$	
Were all VOA vials <b>free of headspace</b> (i.e., bubbles <a>6 mm</a> )?		$\checkmark$	Щ	
Were all soil VOAs <b>field extracted</b> with MeOH+BFB?	<b>V</b>		Ш	
For preserved waters (other than VOA vials, LL-Mercury or				
microbiological analyses), was <b>pH verified and compliant</b> ?		<b>V</b>	H	
If pH was adjusted, were bottles flagged (i.e., stickers)?  For <b>special handling</b> (e.g., "MI" soils, foreign soils, lab filter for	Ш	<b>V</b>	Ш	
dissolved, lab extract for volatiles, Ref Lab, limited volume),				
were bottles/paperwork flagged (e.g., sticker)?		$\checkmark$		
For RUSH/SHORT Hold Time, were COC/Bottles flagged		<u>v</u>		
accordingly? Was Rush/Short HT email sent, if applicable?		$\checkmark$		
For SITE-SPECIFIC QC, e.g. BMS/BMSD/BDUP, were		<u>V</u>		
containers / paperwork flagged accordingly?	П	$\checkmark$		
For any question answered "No," has the PM been notified and				SRF Completed by: D.C 09/22/2015
the problem resolved (or paperwork put in their bin)?	П	$\checkmark$		PM notified:
Was PEER REVIEW of sample numbering/labeling completed?	7	Ħ	〒	Peer Reviewed by: VDL
Additional notes (if applicable):				1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
reditional notes (if applicable).				
			_	
Note to Client: Any "no" answer above indicates non-complete	liance	with s	tanda	rd procedures and may impact data quality.



## **Sample Containers and Preservatives**

Container Id	Preservative	Container Condition	Container Id	Preservative	Container Condition
1155497001-A	No Preservative Required	OK		· · · · · · · · · · · · · · · · · · ·	
1155497001-B	Methanol field pres. 4 C	OK			
1155497002-A	No Preservative Required	OK			
1155497002-B	Methanol field pres. 4 C	OK			
1155497003-A	No Preservative Required	OK			
1155497003-B	Methanol field pres. 4 C	OK			
1155497004-A	No Preservative Required	OK			
1155497004-B	Methanol field pres. 4 C	OK			
1155497005-A	No Preservative Required	OK			
1155497005-B	Methanol field pres. 4 C	OK			
1155497006-A	No Preservative Required	OK			
1155497006-B	Methanol field pres. 4 C	OK			
1155497007-A	No Preservative Required	OK			
1155497007-B	Methanol field pres. 4 C	OK			
1155497008-A	No Preservative Required	OK			
1155497008-B	Methanol field pres. 4 C	OK			
1155497009-A	No Preservative Required	OK			
1155497009-B	Methanol field pres. 4 C	OK			
1155497010-A	No Preservative Required	OK			
1155497010-B	Methanol field pres. 4 C	OK			
1155497011-A	No Preservative Required	OK			
1155497011-B	Methanol field pres. 4 C	OK			
1155497012-A	No Preservative Required	OK			
1155497012-B	Methanol field pres. 4 C	OK			
1155497013-A	No Preservative Required	OK			
1155497013-B	Methanol field pres. 4 C	OK			
1155497014-A	No Preservative Required	OK			
1155497014-B	Methanol field pres. 4 C	OK			
1155497015-A	No Preservative Required	OK			
1155497015-B	Methanol field pres. 4 C	OK			
1155497016-A	No Preservative Required	OK			
1155497016-В	Methanol field pres. 4 C	OK			
1155497017-A	No Preservative Required	OK			
1155497017-В	Methanol field pres. 4 C	OK			
1155497018-A	Methanol field pres. 4 C	OK			

9/22/2015 94 of 109

<u>Container Id Preservative Container Condition Container Id Preservative Container Condition</u>

#### **Container Condition Glossary**

Containers for bacteriological, low level mercury and VOA vials are not opened prior to analysis and will be assigned condition code OK unless evidence indicates than an inappropriate container was submitted.

- OK The container was received at an acceptable pH for the analysis requested.
- PA The container was received outside of the acceptable pH for the analysis requested. Preservative was added upon receipt and the container is now at the correct pH. See the Sample Receipt Form for details on the amount and lot # of the preservative added.
- PH The container was received outside of the acceptable pH for the analysis requested. Preservative was added upon receipt, but was insufficient to bring the container to the correct pH for the analysis requested. See the Sample Receipt Form for details on the amount and lot # of the preservative added.
- BU The container was received with headspace greater than 6mm.

9/22/2015 95 of 109

# **CHROMATOGRAMS**

Quantitation Report (QT Reviewed)

Data Path : Y:\10\SE\DATA\100415\

Data File : SE1004\_028.D
Signal(s) : FID1A.ch

Acq On : 4 Oct 2015 6:27 pm

Operator : KJO

Sample : 1155497006

Misc :

ALS Vial : 67 Sample Multiplier: 1


Integration File: events.e

Quant Time: Oct 06 11:07:55 2015

Quant Method: Y:\10\SE\METHOD\SEF2015-1002A.M
Quant Title: DRO/RRO by Method AK 102/103
QLast Update: Sat Oct 03 14:49:07 2015

Response via : Initial Calibration

Integrator: ChemStation



(QT Reviewed) Quantitation Report

Data Path :  $Y:\10\SE\DATA\100415\$ 

Data File : SE1004\_062.D Signal(s) : FID1A.ch

Acq On : 5 Oct 2015 12:17 am

Operator : KJO

Sample : 1155497006 SG

Misc

ALS Vial : 82 Sample Multiplier: 1


Integration File: events.e

Quant Time: Oct 06 11:19:19 2015

Quant Method: Y:\10\SE\METHOD\SEF2015-1002A.M Quant Title : DRO/RRO by Method AK 102/103 QLast Update : Sat Oct 03 14:49:07 2015

Response via : Initial Calibration

Integrator: ChemStation



Data Path : Y:\10\SE\DATA\100415\

Data File : SE1004\_030.D
Signal(s) : FID1A.ch

Acq On : 4 Oct 2015 6:48 pm

Operator : KJO

Sample : 1155497007

Misc :

ALS Vial : 68 Sample Multiplier: 1


Integration File: events.e

Quant Time: Oct 05 10:23:59 2015

Quant Method: Y:\10\SE\METHOD\SEF2015-1002.M Quant Title: DRO/RRO by Method AK 102/103 QLast Update: Sat Oct 03 14:49:07 2015

Response via : Initial Calibration

Integrator: ChemStation



Quantitation Report (QT Reviewed)

Data Path : Y:\10\SE\DATA\100415\

Data File : SE1004\_064.D
Signal(s) : FID1A.ch

Acq On : 5 Oct 2015 12:37 am

Operator : KJO

Sample : 1155497007 SG

Misc :

ALS Vial : 83 Sample Multiplier: 1


Integration File: events.e

Quant Time: Oct 06 11:21:22 2015

Quant Method: Y:\10\SE\METHOD\SEF2015-1002A.M
Quant Title: DRO/RRO by Method AK 102/103
QLast Update: Sat Oct 03 14:49:07 2015

Response via : Initial Calibration

Integrator: ChemStation



Quantitation Report (QT Reviewed)

Data Path : Y:\10\SE\DATA\100415\

Data File : SE1004\_032.D
Signal(s) : FID1A.ch

Acq On : 4 Oct 2015 7:08 pm

Operator : KJO

Sample : 1155497011

Misc :

ALS Vial : 69 Sample Multiplier: 1


Integration File: events.e

Quant Time: Oct 06 11:09:34 2015

Quant Method: Y:\10\SE\METHOD\SEF2015-1002A.M
Quant Title: DRO/RRO by Method AK 102/103
QLast Update: Sat Oct 03 14:49:07 2015

Response via : Initial Calibration

Integrator: ChemStation



(QT Reviewed) Quantitation Report

Data Path :  $Y:\10\SE\DATA\100415\$ 

Data File : SE1004\_066.D Signal(s) : FID1A.ch

Acq On : 5 Oct 2015 12:58 am

Operator : KJO

Sample : 1155497011 SG

Misc

ALS Vial : 84 Sample Multiplier: 1


Integration File: events.e

Quant Time: Oct 06 11:21:52 2015

Quant Method: Y:\10\SE\METHOD\SEF2015-1002A.M Quant Title : DRO/RRO by Method AK 102/103QLast Update : Sat Oct 03 14:49:07 2015

Response via : Initial Calibration

Integrator: ChemStation



(QT Reviewed) Quantitation Report

Data Path :  $Y:\10\SE\DATA\100415\$ 

Data File: SE1004\_034.D Signal(s) : FID1A.ch

Acq On : 4 Oct 2015 7:29 pm

Operator : KJO

Sample : 1155497012

Misc

ALS Vial : 70 Sample Multiplier: 1


Integration File: events.e

Quant Time: Oct 06 11:10:05 2015

Quant Method: Y:\10\SE\METHOD\SEF2015-1002A.M Quant Title : DRO/RRO by Method AK 102/103 QLast Update : Sat Oct 03 14:49:07 2015

Response via : Initial Calibration

Integrator: ChemStation



Quantitation Report (QT Reviewed)

Data Path : Y:\10\SE\DATA\100415\

Data File: SE1004\_068.D Signal(s) : FID1A.ch

: 5 Oct 2015 1:19 am Acq On

Operator : KJO

Sample : 1155497012 SG

Misc

ALS Vial : 85 Sample Multiplier: 1


Integration File: events.e

Quant Time: Oct 06 11:22:28 2015

Quant Method: Y:\10\SE\METHOD\SEF2015-1002A.M Quant Title : DRO/RRO by Method AK 102/103QLast Update : Sat Oct 03 14:49:07 2015

Response via : Initial Calibration

Integrator: ChemStation



Quantitation Report (QT Reviewed)

Data Path : Y:\10\SE\DATA\102015\

Data File : SE1020\_054.D
Signal(s) : FID1A.ch

Acq On : 21 Oct 2015 5:03 am

Operator : KJO

Sample : (1155497013)

Misc :

ALS Vial : 38 Sample Multiplier: 1


Integration File: events.e

Quant Time: Oct 21 14:21:16 2015

Quant Method: Y:\10\SE\METHOD\SEF2015-1002D.M
Quant Title: DRO/RRO by Method AK 102/103
QLast Update: Sat Oct 03 14:49:07 2015

Response via : Initial Calibration

Integrator: ChemStation



(QT Reviewed) Quantitation Report

Data Path : Y:\10\SE\DATA\102015\

Data File : SE1020\_046.D Signal(s) : FID1A.ch

Acq On : 20 Oct 2015 8:11 pm

Operator : KJO

Sample : 1155497013 SG

Misc

ALS Vial : 34 Sample Multiplier: 1


Integration File: events.e

Quant Time: Oct 21 14:20:10 2015

Quant Method: Y:\10\SE\METHOD\SEF2015-1002D.M Quant Title : DRO/RRO by Method AK 102/103 QLast Update : Sat Oct 03 14:49:07 2015

Response via : Initial Calibration

Integrator: ChemStation



Alkane markers

Data Path : Z:\10\SE\DATA\100114.SEC\

Data File: 01010.D Signal(s) : FID2B.ch

Acq On : 1 Oct 2014 12:24 pm

Operator : MCM Sample : NAS

Misc


ALS Vial : 2 Sample Multiplier: 1

Integration File: events.e Quant Time: Oct 02 09:20:42 2014

Quant Method: Z:\09\SE\METHOD\SER2014-092914.M

Quant Title : DRO/RRO by Method AK 102/103 QLast Update : Tue Sep 30 07:30:38 2014 Response via : Initial Calibration

Integrator: ChemStation



Quantitation Report (QT Reviewed)

Data Path : Z:\08\SE\DATA\SE080214\

Data File : 0208.D
Signal(s) : FID2B.ch

Acq On : 3 Aug 2014 1:18 am

Operator : EAB
Sample : CCVB DRO Standard - long run

Misc :

ALS Vial : 3 Sample Multiplier: 1


Integration File: events.e

Quant Time: Aug 04 08:43:05 2014

Quant Method: Z:\08\SE\METHOD\SER 2014-0729A.M Quant Title: DRO/RRO by Method AK 102/103 QLast Update: Wed Jul 30 10:02:06 2014

Response via : Initial Calibration

Integrator: ChemStation



Quantitation Report (Not Reviewed)

Data Path : Z:\08\SE\DATA\SE080414\

Data File : 0409.D
Signal(s) : FID2B.ch

Acq On : 4 Aug 2014 10:05 am

Operator : EAB Sample : CCVR

Misc : RRO standard - long run

ALS Vial : 4 Sample Multiplier: 1


Integration File: events.e

Quant Time: Aug 04 10:29:44 2014

Quant Method: Z:\08\SE\METHOD\SER 2014-0729A.M Quant Title: DRO/RRO by Method AK 102/103 QLast Update: Wed Jul 30 10:02:06 2014

Response via : Initial Calibration

Integrator: ChemStation



## LABORATORY DATA REVIEW CHECKLIST

**Completed by:** Trevor Crosby **Title:** Environmental Scientist

**Date:** October 30, 2015

CS Report Name: Site Assessment, Pitkas Point School Site, Pitkas Point, Alaska

Laboratory Report Date: October 27, 2015

Consultant Firm: Shannon & Wilson, Inc.

**Laboratory Name:** SGS North America Inc. **Laboratory Report Number:** 1155497

**ADEC File Number:** 2444.57.001 **ADEC Hazard ID Number:** 26405

(**NOTE**: *NA* = not applicable; Text in *italics* added by Shannon & Wilson, Inc.)

## 1. <u>Laboratory</u>

a. Did an ADEC CS approved laboratory receive and <u>perform</u> all of the submitted sample analyses? Yes/ No / NA

Comments: Yes, SGS North America, Inc. (SGS) received the samples and performed submitted sample analyses.

**b.** If the samples were transferred to another "network" laboratory or sub-contracted to an alternate laboratory, was the laboratory performing the analyses ADEC CS-approved? **Yes / No (NA)** 

Comments: The samples were not transferred to another "network" laboratory or subcontracted to an alternate laboratory.

## 2. Chain of Custody (COC)

a. COC information completed, signed, and dated (including released/received by)? Yes/ No / NA

Comments:

**b.** Correct analyses requested? Yes / No / NA Comments:

## 3. Laboratory Sample Receipt Documentation

a. Sample/cooler temperature documented and within range at receipt  $(4^{\circ} \pm 2^{\circ} \text{ C})$ ? Yes (No) NA

Comments: The cooler temperature was 1.8° C upon receipt at SGS.

- **b.** Sample preservation acceptable acidified waters, Methanol-preserved VOC soil (GRO, BTEX, VOCs, etc.)? **Yes/ No / NA**
- c. Sample condition documented broken, leaking (soil MeOH), zero headspace (VOC vials)? Yes/No/NA
   Comments: SGS specifies that samples were received in good condition on the Sample Receipt Form (SRF).
- d. If there were any discrepancies, were they documented (e.g., incorrect sample containers/preservation, sample temperatures outside range, insufficient sample size, missing samples)? Yes/ No / NA

  Comments: The cooler temp was outside the QC range at SGS. The laboratory noted that the sample time for one sample did not match the COC. The sample was logged in under the ID listed on the sample jar.
- **e.** Data quality or usability affected? Please explain. Comments: Although the cooler temperature was less than the QC range, the sample receipt form does not indicated that the samples were frozen. Therefore, data quality/usability is considered unaffected.

## 4. Case Narrative

- a. Present and understandable? Yes/ No / NA Comments:
- **b.** Discrepancies, errors or QC failures noted by the lab? **Yes/No/NA** Comments: *The following QC failures were noted by the lab:* 
  - GRO surrogate 4-bromofluorobenzene (BFB) recovery for Project Samples PPS10-D, PPS10-3-D, and PPS10-3-DX (Duplicate sample of PPS10-D) are biased high due to sample matrix.
  - DRO surrogate 5a-androstane recovery for Project Sample PPS10-1-B is outside QC criteria (biased low) due to sample dilution (20 times).
  - RRO surrogate n-triacontane recovery for Project Sample PPS10-1-B is outside QC criteria (biased low) due to sample dilution (20 times).
  - Amended sampled ID/Times for Project Samples PPS10-1-B, PPS13-C, and PPS12-3-C
  - Project Sample PPS12-3-C analyzed outside hold time
  - Added DRO/RRO and DRO/RRO Silica Gel for Project Sample PPS12-3-C.
- c. Were corrective actions documented? Yes No NA Comments:
- **d.** What is the effect on data quality/usability, according to the case narrative? Comments: *The case narrative does not comment on the data quality/usability.*

## **5. Sample Results**

**a.** Correct analyses performed/reported as requested on COC? **Yes (No) NA** (please explain)

Comments: DRO/RRO and DRO/RRO Silica Gel analysis for Sample PPS12-3-C was indicated on the COC but was not conducted by the laboratory. A revised laboratory report including the results for this sample was issued on October 27, 2015.

- **b.** All applicable holding times met? **Yes No NA** Comments: *DRO/RRO and DRO/RRO Silica Gel analysis for Sample PPS12-3-C was conducted outside hold time due to a laboratory error.*
- c. All soils reported on a dry-weight basis? Yes No / NA Comments:
- **d.** Are the reported LOQs less than the Cleanup Level or the minimum required detection level for the project? **Yes** / **No** / **NA**Comments: LOQs and reporting limits are less than cleanup levels where applicable (for non-detect results)
- e. Data quality or usability affected? NA Comments: DRO/RRO and DRO/RRO Silica Gel results for Sample PPS12-3-C may be biased low due to the hold time exceedance.

## 6. QC Samples

#### a. Method Blank

- i. One method blank reported per matrix, analysis, and 20 samples?Yes/ No / NAComments:
- ii. All method blank results less than LOQ? Yes/No/NA Comments:
  - GRO, P & M xylene, and toluene were detected at estimated concentrations of 1.50 mg/kg, 0.0168 mg/kg, and 0.0138 mg/kg, respectively in the method blank for Trip Blank TB1.
  - GRO and toluene were detected at estimated concentrations of 1.47 mg/k and 0.0113 mg/kg, respectively in the method blank for Project Samples PPS1/PPS11-B, PPS1/PPS11-3-A, PPS10-1-B, PPS10-2-D, PPS10-3-D, PPS10-3-DX, PPS10-4-B, PPS12-C, PPS12-2-A, PPS13-C, and PPS12-3-CX.
  - GRO, P & M xylene, and toluene were detected at estimated concentrations of 1.01 mg/kg, 0.0155 mg/kg, and 0.0125 mg/kg, respectively in the method blank for Project Samples PPS12-3-C, PPS13-1-A, PPS13-2-B, TF1, and TF2.
  - *GRO* was detected at 1.45 J in the method blank for Project Sample PPS10-D.

**iii.** If above LOQ, what samples are affected? Comments: *See above*.

iv. Do the affected sample(s) have data flags? Yes No / NA

Comments: Although the reported concentrations in the above soil method blanks are less than their respective LOQs, the samples associated with these method blanks are "B" flagged when the reported sample concentration is within 10x the reported method blank concentration. If both the sample and method blank concentrations are reported at levels less than the LOQ, the sample concentration is reported as non-detect at the LOQ. If the reported sample concentration is greater than the LOQ and less than 5x the method blank concentration, the sample concentration is greater than 5x the method blank concentration and less than or equal to 10x the method blank concentration, the sample concentration is reported at the detected sample concentration is reported at the detected sample concentration. See Table 2 of the report.

If so, are the data flags clearly defined? Yes/No/NA Comments: See above.

v. Data quality or usability affected? Yes / No (NA) Comments: See above.

## b. Laboratory Control Sample/Duplicate (LCS/LCSD)

- i. Organics One LCS/LCSD reported per matrix, analysis, and 20 samples? (LCS/LCSD required per AK methods, LCS required per SW846) Yes No / NA Comments: One LCS/LCSD pair reported per analysis and 20 samples for GRO, DRO, RRO, and BTEX analyses.
- ii. Metals/Inorganics One LCS and one sample duplicate reported per matrix, analysis and 20 samples? Yes / No NA Comments: *Inorganic analyses not performed*.
- iii. Accuracy All percent recoveries (%R) reported *and within method or laboratory limits?* And project specified DQOs, if applicable. (AK petroleum methods: AK101 60%-120%, AK102 75%-125%, AK103 60%-120%; all other analyses see the laboratory QC pages) Yes / No / NA Comments:
- iv. Precision All relative percent differences (RPDs) reported and less than method or laboratory limits? And project specified DQOs, if applicable. RPD reported from LCS/LCSD, MS/MSD, and or sample/sample duplicate. (AK Petroleum methods 20%; all other analyses see the laboratory QC pages) Yes/No/NA (please explain) Comments:

v. If %R or RPD is outside of acceptable limits, what samples are affected? NA Comments: See above.

vi. Do the affected samples(s) have data flags? Yes / No (NA) Comments: See above.

If so, are the data flags clearly defined? **Yes / No NA** Comments: *See above*.

vii. Data quality or usability affected? Explain. NA Comments: See above.

## c. Surrogates - Organics Only

- i. Are surrogate recoveries reported for organic analyses, field, QC, and laboratory samples? Yes/ No / NA
  Comments:
- ii. Accuracy All percent recoveries (%R) reported and within method or laboratory limits? And project specified DQOs if applicable. (AK Petroleum methods 50-150 %R; all other analyses see the laboratory report pages) Yes No/NA Comments: Recovery of DRO and RRO surrogates 5a-androstane and n-triacontane in Project Sample PPS10-1-B are below QC criteria due to sample dilution. The project samples are considered unaffected. Recovery of GRO surrogate 4-bromofluorobenzene (BFB) recovery for Project Samples PPS10-D, PPS10-3-D, and PPS10-3-DX are above QC criteria due to matrix interference.
- iii. Do the sample results with failed surrogate recoveries have data flags? Yes/ No / NA Comments: See above.

If so, are the data flags clearly defined? Yes / No / NA Comments: See above.

- iv. Data quality or usability affected? Explain. Yes/No/NA
  Comments: The associated GRO results are considered a biased high estimate and flagged "J+" in Table 2 of the Report. Because the reported results are less than the ADEC cleanup level, potential high bias should not affect the data usability for this project.
- d. Trip Blank Volatile analyses only (GRO, BTEX, VOCs, etc.) Soil
  - i. One trip blank reported per matrix, analysis and cooler? Yes/ No / NA Comments:
  - ii. Is the cooler used to transport the trip blank and volatile samples clearly indicated on the COC? Yes / No (NA)

Comments: Only one cooler was submitted to the laboratory.

iii. All results less than LOQ? Yes / No / NA Comments:

- iv. If above LOQ, what samples are affected? NA Comments:
- v. Data quality or usability affected? Explain. NA Comments: See above.

## e. Field Duplicate

- One field duplicate submitted per matrix, analysis and 10 project samples?
   Yes/ No / NA
   Comments: A field duplicate was submitted per 10 project samples for GRO, DRO, RRO, and BTEX analysis.
- ii. Were the field duplicates submitted blind to the lab? Yes/No/NA Comments: Sample PPS12-3-C is a field duplicate of PPS12-3-CX.
- iii. Precision All relative percent differences (RPDs) less than specified DQOs? (Recommended: 30% for water, 50% for soil) Yes/No/NA Comments: RPDs for DRO and RRO Silica Gel is greater than 50% (64%). RPDs for DRO and RRO were less than the DQOs. GRO, Benzene, toluene, ethylbenzene, total xylene analytes could not be calculated due to non-detect results for the primary and duplicate samples.
- iv. Data quality or usability affected? Explain. (NA)

  Comments: The DRO concentrations in the primary (PPS12-3-C) and field duplicate (PPS12-3-CX) soil samples are both greater than the ADEC Method 2 cleanup level and the results are considered usable. However, the DRO Silica Gel concentration in the primary sample (PPS12-3-C; 155 mg/kg) is less than the ADEC Method 2 cleanup level while the duplicate sample (PPS12-3-CX; 301 mg/kg) is above than the ADEC Method 2 cleanup level potentially impacting the use of the data to determine if DRO Silica Gel concentrations in soils at PPS12-3-C are above cleanup levels. In addition, the duplicate sample (PPS12-3-CX) result is potentially biased low due to hold time exceedance which may have impacted the RPD between the samples. Therefore, in our opinion, no non-conformances that would adversely affect the quality or usability of the data were noted.
- **f. Decontamination or Equipment Blank** (if not applicable, a comment stating why must be entered below)

**Yes** / **No** (NA) Collecting and submitting a decontamination or equipment blank was not included in the ADEC-approved project scope.

i. All results less than LOQ? Yes / No NA Comments: See above.

ii. If results are above LOQ, what samples are affected? NA Comments: See above.

iii. Data quality or usability affected? Explain. NA Comments: See above.

## 7. Other Data Flags/Qualifiers (ACOE, AFCEE, Lab-specific, etc.)

a. Are they defined and appropriate? Yes / No / NA
Comments: Laboratory-applied data flags are defined on page 3 of the SGS report.

SHANNON & WILSON, INC.

## APPENDIX D

EHS-ALASKA, INC., HAZARDOUS MATERIALS ASSESSMENT – PITKAS POINT SCHOOL SITE HAZMAT SURVEY

## HAZARDOUS MATERIALS ASSESSMENT

# PITKAS POINT SCHOOL SITE HAZMAT SURVEY

PITKAS POINT, ALASKA

Surveyed September 16, 2015

Report Date January 20, 2016

EHS, ALASKA, INC.
ENGINEERING, HEALTH & SAFETY CONSULTANTS
11901 BUSINESS BLVD., SUITE 208
EAGLE RIVER, ALASKA 99577-7701

## HAZARDOUS MATERIALS ASSESSMENT PITKAS POINT SCHOOL SITE HAZMAT SURVEY

## PITKAS POINT, ALASKA

## **TABLE OF CONTENTS**

			PAGE NO.
OVE	RVIEV	/	3
A.	GEN	ERALIZED REQUIREMENTS FOR HAZARDOUS MATERIALS	3
B.	BUIL	DING DESCRIPTION	4
C.	SAM	PLING AND ANALYSIS	5
٥.	1.	Asbestos-Containing Materials	
	2.	Lead-Containing Materials	
	3.	Suspect Fungal Growth	6
D.	SUR	VEY RESULTS	6
	1.	Asbestos-Containing Materials	
	2.	Asbestos in Dusts	
	3.	Lead-Containing Materials	
	4.	PCB-Containing Materials	
	5.	Mercury-Containing Materials	
	6. 7	Other Hazardous Materials	
_	7.	Suspect Fungal Growth	
E.		ULATORY CONSTRAINTS	
	1. 2.	Asbestos-Containing Materials	
	2. 3.	Dusts with Asbestos  Lead-Containing Materials	
	3. 4.	PCB-Containing Materials	
	5.	Mercury-Containing Materials	
	6.	Other Hazardous Materials	
	7.	Suspect Fungal Growth	
F.	REC	OMMENDATIONS	
	1.	Asbestos-Containing Materials	
	2.	Dusts with Asbestos	
	3.	Lead-Containing Materials	23
	4.	PCB-Containing Materials	
	5.	Mercury-Containing Materials	
	6.	Other Hazardous Materials	
	7.	Suspect Fungal Growth	
G.		TATIONS	
	1.	Accuracy of Information	
	2.	Site Conditions	
	3.	Changing Regulatory Constraints	25
		APPENDICES	
		Asbestos Bulk Field Survey Data Sh	
		Lead	
		Drawings	
Appe	endix E	Order of Mag	gnitude Cost Estimate

## HAZARDOUS MATERIALS ASSESSMENT PITKAS POINT SCHOOL SITE HAZMAT SURVEY

#### PITKAS POINT, ALASKA

#### **OVERVIEW**

At the request of the Alaska Department of Environmental Conservation (ADEC), EHS-Alaska, Inc. (EHS-Alaska) conducted limited investigations of the Main School Building and two other structures known as Teacher Housing Unit 1 and Teacher Housing Unit 2 at the Pitkas Point school site, located in Pitkas Point, Alaska. The investigation consisted of limited surveys of each building to determine the presence of asbestos-containing materials (ACM), and other potentially hazardous materials, including suspect fungal growth, for the purpose of determining which buildings were safe for use by the Pitkas Point community. The limited investigation did not meet the requirements of NESHAP which is required prior to building renovation or demolition. Mr. Chris T. Ottosen of EHS-Alaska conducted the inspections in September 2015.

#### A. GENERALIZED REQUIREMENTS FOR HAZARDOUS MATERIALS

Potentially hazardous materials have been identified in each of the three structures surveyed. Those materials include asbestos, lead, polychlorinated bi-phenyls (PCBs), mercury, and radioactive materials. Not all materials were tested for potentially hazardous components, other potentially hazardous materials, including those exterior to the building, such as contamination from underground fuel tanks may be present, but are not part of this report.

Buildings or portions of buildings that were constructed prior to 1978 which are residences, or contain day care facilities, kindergarten classes or other activities frequently visited by children under 6 years of age are classified as *child occupied facilities*. All work classified as "renovations" or disturbing more than 6 square feet of lead-based painted surfaces per room for interior activities or more than 20 square feet for exterior activities in child occupied facilities must comply with the requirements of 40 CFR 745. None of these structures are classified as a *child occupied facility* and therefore the requirements of 40 CFR 745 are not applicable.

Only the materials that will be directly affected by future projects are required to be removed. The removal and disposal of potentially hazardous materials are highly regulated, and it is anticipated that removal and disposal of asbestos, lead and chemical hazards would be conducted by a subcontractor to the general contractor who is qualified for such removal. It is anticipated that the general contractor and other trades would be able to conduct their work using engineering controls and work practices to control worker exposure and to keep airborne contaminants out of other areas of the building and the school site.

Settled and concealed dusts in areas not subject to routine cleaning are present throughout the buildings, including the roof, and inside and on top of architectural, mechanical, electrical, and structural elements, and those dusts are assumed to contain regulated air contaminants. This should not be read to imply that there is an existing hazard to persons entering the buildings (persons entering the building as opposed to construction workers working in the affected areas). However, depending on the specific work items involved and on the means and methods employed when working in the affected areas, construction workers could be exposed to regulated air contaminants from those dusts in excess of the OSHA Permissible Exposure Limits (PELs).

The settled and concealed dusts were examined by an EPA Certified Building Inspector but were not sampled. The inspector determined that the dusts are not "asbestos debris" from an asbestos-containing building material (ACBM). The inspector also determined that the dusts are unlikely to contain more than one percent (1%) asbestos by weight, and therefore are not an asbestos-containing material (ACM). Reference 40 CFR 763.83.

"Awareness training" (typically 2 hours) and possibly respiratory protection would be required for all Contractor Personnel who would be disturbing the dusts. The extent of the training and protective measures would depend upon the airborne concentrations measured during air monitoring of the contractors work force, which would depend on the means and methods employed to control the dusts. The air monitoring may be discontinued following a "negative exposure assessment" showing that worker exposures are below the OSHA permissible exposure limits for the type of work and means and methods employed. Previous air monitoring from similar jobs with similar conditions may be used as historical data to establish a "negative exposure assessment".

## B. BUILDING DESCRIPTION

## **Main School Building**

The Main School Building was originally constructed in 1980, with an addition to the northwest in 1984. The building is currently unoccupied and without utilities, with the exception of the Server Room which still has electricity.

The building is elevated above grade and supported by pilings. The pilings are connected to various structural members below the building which provide a foundation for the remainder of the structure. The floor structure consists of a plywood base covered by a poly vapor barrier with another layer of plywood on top of an insulated joist space. Walls were typically of wood framed construction, with various other structural members supporting the second floor. The exterior was clad with a T1-11 wood siding, and the roofs were of either a corrugated metal or metal "zip-rib" style.

Interior floor finishes were typically of carpet in classroom and office areas, with the bathrooms having sheet vinyl, the main entrance vestibule and hallway had a brick type decorative ceramic floor tile, and the remainder of the building having 12" x 12" decorative vinyl floor tiles. In some areas, older floor finishes were left in place and covered over by newer floor finishes.

Walls were typically of gypsum wall board, with bathroom areas having either a decorative wall tile or "Marlite" finish directly on top of the gypsum wall board. One classroom area had a wooden wainscot, and the Gym had a carpeted wall panel covering the bottom eight feet of the wall. Ceilings throughout were of gypsum wall board.

The building was heated by a hydronic heating system, with each era having its own boiler. The building did not appear to have any form of mechanical ventilation with the exception of bathroom exhaust fans and the fume hood in the Kitchen.

The building was generally in fair condition with only minor areas of water damage noted. Roof leaks in the Mechanical Room above the Kitchen have resulted in damage to the Mechanical Room, the Kitchen, and an adjacent classroom to the south. Multiple trash cans or buckets were placed in the Mechanical Room to catch the water but have overflowed causing more damage. There was also water damage noted in the Gym where daylight was visible through cracks in the gypsum board wall and ceiling. This appears to have been caused by building settling and a lack of exterior siding or other protection. In both areas, water has damaged a variety of building components including ceilings, walls, floors, light fixtures, etc. Suspect fungal growth was noted in both of these locations.

#### Teacher Housing Units 1 & 2

The Teacher Housing Units appear to have been built at the same time considering they have nearly identical floor plan configurations and building materials. According to aerial photography of the site, the units appear to have been built around 1979 or 1980. It appeared that additional information on these structures was present in the AHERA documentation found at the site, but this information was not provided to EHS after multiple requests.

The units were elevated above grade and supported by wood piers. The piers connected to wood girders under the buildings which provided a foundation for the remainder of the structures. The floor structures

appeared to have been made of one layer of plywood over an insulated joist space. Walls were of wood framed construction, and roofs were of a corrugated metal.

Interior floor finishes were mainly of carpet, with sheet vinyl in the Arctic Entry, Kitchen, Bathroom, and Boiler Room. In some areas, older floor finishes were left in place and covered by newer floor finishes.

Walls were typically of an 1/8" prefabricated decorative wood panel nailed directly to wood framing, with the east side of the Kitchen/Living Room areas having a vinyl covered gypsum wall board glued to a plywood underlayment, the Bathroom having "Marlite" panels glued to a plywood underlayment, and the Boiler Room having all gypsum board.

Ceilings throughout consisted of a 12" x 12" acoustic ceiling tile. In Teacher Housing Unit 1 the tiles used a combination of staples and "puck" mastic to secure the tiles directly to the plywood ceiling. No mastic was noted on the tiles in Teacher Housing Unit 2. In both units, the Boiler Room had a gypsum board ceiling.

The units were heated by a hydronic heating system, with each unit having its own boiler.

Both Teacher Housing Units were in disrepair and should not be entered by unprotected workers. There was no access to the Attic, but it appears that a combination of roof leaks, lack of ventilation, and environmental conditions have trapped moisture in the units resulting in extensive fungal growth due to the various forms of water damage and intrusion. All surfaces and materials interior to the units have visible fungal growth and are moisture laden.

#### C. SAMPLING AND ANALYSIS

## 1. Asbestos-Containing Materials

The surveys included sampling of suspect ACM materials that had not been sampled in prior asbestos surveys, or samples of materials where previous sampling had been inconsistent. Refer to the AHERA asbestos management plans available for review in the Lower Yukon School District offices for information on previous sampling which is not included in this report. Additional testing of materials pertinent to the project, including asbestos and lead samples was conducted and is included in this report.

The samples were analyzed for the presence of asbestos by polarized light microscopy (PLM), the method of analysis recommended by the U.S. Environmental Protection Agency (EPA) to determine the composition of suspected asbestos-containing materials (EPA method 600/M4-82-020). Only materials containing more than 1% total asbestos were classified as "asbestos-containing" based on EPA and the Occupational Safety and Health Administration (OSHA) criteria. Samples that were analyzed to have less than 10% asbestos were "point-counted" by the laboratory for more accuracy. Samples that are listed as having a "Trace by Point Count" had asbestos fibers found in the material, but the fibers were not present at the counting grids. Table 1 in Part D below contains a summary list of the asbestos bulk samples and the applicable results.

The Bulk Asbestos samples were analyzed for asbestos content by International Asbestos Testing Laboratories (IATL), Mt. Laurel, New Jersey a National Voluntary Laboratory Accreditation Program - (NVLAP) accredited laboratory.

EPA regulations under 40 CFR 763 requires the use of Polarized Light Microscopy (PLM) to determine whether or not a material contains asbestos. While PLM analysis does a good job for most materials, it does have some limitations, both in the size of the fibers that are visible under a standard optical microscope, and because the organic matrix that the fibers are bound within can obscure the fibers. At the discretion of the building inspector and the client, some types of samples may be analyzed or reanalyzed by what is called TEM NOB, or Transmission Electron Microscopy for Non-Friable Organically

Bound materials. TEM NOB is the definitive method for determining if asbestos is present, but TEM NOB use is not required by the EPA. TEM NOB analysis was not done for this project.

Field survey data sheets and laboratory reports of the bulk samples are included in Appendix A. Drawings showing sample locations are included as Appendix D.

#### 2. Lead-Containing Materials

Nearly all surfaces in the buildings were coated with paint and most surfaces had been repainted. EHS-Alaska tested paint throughout the buildings using an XLp300A X-Ray Fluorescence (XRF) lead paint analyzer (Serial # 81530 with software version 5.2F). EHS-Alaska had also previously tested paint throughout portions of the Main School Building using an XLi303AW X-Ray Fluorescence (XRF) lead paint analyzer (Serial # 14311 with software version 5.2C). Refer to the Lead Paint Screening Table in Appendix C that identifies the surfaces tested, and the results. All surfaces may not have been tested and therefore additional sampling may be required to refute the presence of lead-based paints. The Paint Test Locations are shown in Appendix D.

EPA and the Department of Housing and Urban Development (HUD) have defined lead-based paint as any paint or other surface coating that contains lead equal to or in excess of 1.0 milligram per square centimeter (mg/cm²) or 0.5 percent by weight. XRF results are classified as positive (lead is present at 1.0 mg/cm² or greater), negative (less than 1.0 mg/cm² of lead was present) or inconclusive (the XRF could not make a conclusive positive or negative determination). Tests that were invalid due to operator error are shown as void tests.

A Performance Characteristic Sheet (PCS) for the NITON XIi303AW and NITON XLp300A is available upon request. This PCS data provides supplemental information to be used in conjunction with Chapter 7 of the "HUD Guidelines". Performance parameters provided in the PCS are applicable when operating the instrument using the manufacturer's instructions and the procedures described in Chapter 7 of the "HUD Guidelines". The instrument was operated in accordance with manufacturer's instructions and Chapter 7 of the HUD Guidelines. No substrate correction is required for this instrument. There is no inconclusive classification for this instrument when using the 1.0 mg/cm² threshold.

#### 3. Suspect Fungal Growth

The investigation included a visual examination of the buildings for suspect fungal growth. Many different types of fungal growth were noted throughout both units, but no samples were authorized for this project, and therefore identification of these fungi is unknown. Moisture readings were not taken from the Teacher Housing Units since most building materials were water saturated with visible condensation on the interior sides of the windows and other surfaces.

#### D. SURVEY RESULTS

#### 1. Asbestos-Containing Materials

Asbestos field survey data sheets and laboratory reports are included as Appendix A. Refer to Appendix D for sample locations. The following Table 1A lists the samples taken in September 2015 in the Main School Building, and the results of the laboratory analysis.

TABLE 1A - Main School Building

SAMPLE NUMBER	MATERIAL	LOCATION	ASBESTOS CONTENT
PKP0915-A01	(SV1) Sheet vinyl, tan with brown swirl pattern; with yellow mastic; with white mastic	From southeast corner of Bathroom – Photo 311	None Detected All Layers
PKP0915-A02	Yellow mastic for ceramic wall tile	At damaged area of north wall behind urinal in Bathroom – Photo 312	None Detected
PKP0915-A03	White gypsum wall board	From behind ceramic wall tile at penetration for heat piping on south wall in Bathroom – Photo 313	None Detected
PKP0915-A04	Brown mastic for ceramic floor tile	At damaged area of flooring at entrance into school – Photo 314	None Detected
PKP0915-A05	Yellow mastic for "Marlite" wall panel (do not analyze "Marlite" wall panel)	At stub wall next to showers in Girl's Bathroom – Photo 374	None Detected
PKP0915-A06	Yellow mastic for carpet	At entrance to first floor Classroom at southwest corner of building – Photo 376	None Detected
PKP0915-A07	Brown gypsum wall board	At damaged area of north wall next to entrance into Kitchen in large Classroom on first floor – Photo 420	None Detected
PKP0915-A08	(FT3) Floor tile, 12"x12" tan with brown and white streaks	From damaged area of flooring near center of Kitchen – Photo 421	None Detected
PKP0915-A09	(FT2) Floor tile, 12"x12" tan with light and dark streaks; with tan mastic	From damaged area of flooring near door at southeast corner of Gym – Photo 431	None Detected Both Layers
PKP0915-A10	White gypsum wall board	At base of west wall at damaged area in Gym – Photo 448	None Detected
PKP0915-A11	Yellow mastic for wall carpet	At base of west wall at damaged area in Gym – Photo 448	None Detected
PKP0915-A12	White wall texture	At area of peeling paint on south side of second floor Office across the hall from the Server Room – Photo 522	None Detected
PKP0915-A13	White wall texture	Under window on south side of second floor hallway near Server Room – Photo 523	None Detected
PKP0915-A14	Black putty	On wood support for A/C unit on south side of Server Room – Photo 524	None Detected
PKP0915-A15	Floor tile, 12"x12" pink with white and black streaks; with tan mastic	Near door on west side of second floor Storage Room – Photo 525	None Detected Both Layers

SAMPLE NUMBER	MATERIAL	LOCATION	ASBESTOS CONTENT
PKP0915-A16	Floor tile, 12"x12" pink with white and black streaks; with tan mastic	On east side of second floor Storage Room – Photo 526	None Detected Both Layers
PKP0915-A17	Yellow mastic for carpet	Near center of Library – Photo 562	None Detected
PKP0915-A18	White wall texture	At damaged area of wall above door at northeast corner of Library – Photo 612	None Detected

The sampling and results of the laboratory analysis in Table 1B below was performed by EHS in July 2011 at the Main School Building as part of the design services for a school upgrades project. The school was shut down shortly after that survey, and the design was never finished. The materials that were sampled during that survey are still present at the school and are included here to supplement the sampling performed in September 2015. That survey also included an inspection of the School Shop to the north of the Main School Building and a Tank Farm at the northeast corner of the school site, but the sampling information for those buildings are not included here. Asbestos field survey data sheets and laboratory reports are included in Appendix A. Refer to Appendix D for sample locations.

TABLE 1B – Main School Building

SAMPLE NUMBER	MATERIAL	LOCATION	ASBESTOS CONTENT
PKP-0711-A01	Carpet mastic, brown	Special Ed classroom, northeast ceiling section	None Detected
PKP-0711-A02	Joint compound, white	Special Ed Classroom, west wall, mid span	None Detected
PKP-0711-A03	Sink undercoating, white	Special Ed classroom, south wall sink	4.1% Chrysotile
PKP-0711-A04	Cove base mastic, tan	Behind entry open door from corridor	None Detected
PKP-0711-A05	Gypsum wall board, white	Corridor wall outside special education classroom	None Detected
PKP-0711-A06	Carpet mastic, tan	Northeast classroom, center of floor	None Detected
PKP-0711-A07	Joint compound, white	Northeast classroom, North wall, below window	None Detected
PKP-0711-A08	Joint compound, white	Inside wall of classroom at doorway from corridor	None Detected
PKP-0711-A09	Joint compound, white	Northwest vestibule above bench	None Detected
PKP-0711-A10	Sink undercoating, white	Northeast wing of building, south classroom, sink at west wall	3.8% Chrysotile
PKP-0711-A11	Cove base mastic, yellow and joint compound, white	Partition wall at end of counter in northeast section, south classroom.	Mastic: ND JC: ND

SAMPLE NUMBER	MATERIAL	LOCATION	ASBESTOS CONTENT
PKP-0711-A12	Cove base, brown	Partition wall at end of counter in northeast section, south classroom	None Detected
PKP-0711-A13	Joint compound, white	south wall in north east section of building, south classroom	None Detected
PKP-0711-A14	Sheet vinyl and mastic, SV-1 tan with brown swirls	Faculty bathroom	SV: ND Mastic: ND
PKP-0711-A15	Tile grout, tan granular	Faculty bathroom, east wall	None Detected
PKP-0711-A16	Door frame sealant, brown	Doorway frame in faculty bathroom	None Detected
PKP-0711-A17	Joint compound, white	Corridor wall at base of stairs to library	None Detected
PKP-0711-A18	Carpet mastic, yellow	Edge of carpet at doorway to gymnasium	Cement: ND Mastic: ND
PKP-0711-A19	Joint compound, white	Corridor wall outside janitor closet	None Detected
PKP-0711-A20	Sheet vinyl and mastic, SV-2 grey pebble mosaic	Edge of floor in janitor closet	SV: 40% Chrysotile Mastic: ND
PKP-0711-A21	Floor tile and mastic, FT- 1 12x12 white w/ grey streaks	Edge of corridor flooring at doorway to janitor closet	Tile: 1.6% Chrysotile Black: 3.2% Chrysotile Yellow: ND
PKP-0711-A22	Joint compound white	Corridor wall outside storage area, south west section of building, north end, north wall of corridor	None Detected
PKP-0711-A23	Joint compound, white	Soffit across from principal's office door, entry area to south west classroom	None Detected
PKP-0711-A24	Cove base, brown	South wall of south west classroom, under radiator	None Detected
PKP-0711-A25	Cove base mastic, brown and yellow	South wall of south west classroom, under radiator	Brown: ND Yellow: ND
PKP-0711-A26	Joint compound white	North wall of south west classroom below light switch	None Detected
PKP-0711-A27	Window glazing, grey	West wall of south west classroom	8.9% Chrysotile
PKP-0711-A28	Floor tile and mastic, FT-1	Floor tile section in classroom outside kitchen area.	Tile: 1.7% Chrysotile Mastic: 1.9% Chrysotile
PKP-0711-A29	Sink undercoating white	Kitchen area in south west classroom	3.9% Chrysotile

SAMPLE NUMBER	MATERIAL	LOCATION	ASBESTOS CONTENT
PKP-0711-A30	Marlite mastic, janitor's closet	South wall of janitor closet	None Detected
PKP-0711-A31	Floor tile, 12x12 tan w/ light and dark streaks, with tan mastic	Gymnasium floor	Tile: ND Mastic: ND
PKP-0711-A32	Floor tile and mastic, FT-3 tan with light and dark streaks	Kitchen area under deep sink	Tile: ND Mastic: ND
PKP-0711-A33	Cove base, black and mastic, brown	Kitchen area at base of cabinet under deep sink	CB: ND Mastic: ND
PKP-0711-A34	Marlite mastic, yellow	Back wall of kitchen area at doorway to classroom	None Detected
PKP-0711-A35	Wall carpet mastic, tan	Gymnasium wall under basketball net outside kitchen	Mastic: ND JC: ND
PKP-0711-A36	Sheet vinyl and mastic, 8" square, cream and grey (SV-3)	Boys locker room entry floor.	SV: ND Mastic: ND
PKP-0711-A37	Sheet vinyl and mastic (SV-2)	Boys locker room entry floor, under SV-3	30% Chrysotile
PKP-0711-A38	Cove Base mastic, brown	Gymnasium storage closet, back wall	None Detected
PKP-0711-A39	Joint compound, white	Storage closet at diagonal ceiling corner	None Detected
PKP-0711-A40	Sheet vinyl and mastic, pink white and grey confetti (SV-4)	Girls locker room floor	SV: ND Mastic: ND
PKP-0711-A41	Joint compound, white	South west section of school, north room (storage area) at corner wall inside doorway	None Detected
PKP-0711-A42	Marlite mastic, yellow	Add on storage area at north end of south west section of building, west wall at damage area	None Detected
PKP-0711-A43	Gypsum wall board, white	Add on storage area at north end of south west section of building, west wall at damage area	None Detected
PKP-0711-A44	Wall texture, white	First floor stair way landing next to faculty bathroom, east wall	None Detected
PKP-0711-A45	Wall texture, white	Second floor, wall along second level stairway to library	None Detected
PKP-0711-A46	Joint compound, white	Second floor, Corner wall at top of stairs in library	None Detected
PKP-0711-A47	Carpet mastic, yellow	Second floor, floor at top of stairs from first floor in library	None Detected
PKP-0711-A48	Wall texture, white	Second floor, Wall outside mechanical room in library	None Detected

SAMPLE NUMBER	MATERIAL	LOCATION	ASBESTOS CONTENT
PKP-0711-A49	Joint compound and wall texture	Second floor, corner wall outside mechanical room in library	None Detected
PKP-0711-A50	Stair tread, tan vinyl	First floor steps from kitchen to mechanical room	1.7% Chrysotile
PKP-0711-A51	Stair tread mastic	First floor steps from kitchen to mechanical room	None Detected
PKP-0711-A52	Joint compound, white with tan paint	Second level, south wall of storage area at top of stairs from kitchen	None Detected
PKP-0711-A53	Joint compound, tan	Second level mechanical room at top of stairs from kitchen, above boiler	None Detected
PKP-0711-A54	Joint compound and wall texture, white	Second floor, inside office at north end of library, east wall	None Detected
PKP-0711-A54a	Joint compound and Wall texture, white	Second floor, outside wall of center office	None Detected

Table 1C includes samples taken in September 2015 in Teacher Housing Unit 1, and the results of the laboratory analysis. Asbestos field survey data sheets and laboratory reports are included in Appendix A. Refer to Appendix D for sample locations.

**TABLE 1C – Teacher Housing Unit 1** 

SAMPLE NUMBER	MATERIAL	LOCATION	ASBESTOS CONTENT
PKPTH0915-A01	(HSV3) Hidden sheet vinyl, beige with brown flower pattern	Teacher Housing Unit #1 – Hidden under newer sheet vinyl in Entryway – Photo 108	None Detected
PKPTH0915-A02	(SV1) Sheet vinyl, white with blue specks and diamond/block pattern	Teacher Housing Unit #1 – In Entryway in – Photo 108	None Detected
PKPTH0915-A03	(SV1) Sheet vinyl, white with blue specks and diamond/block pattern	Teacher Housing Unit #1 – At carpet to sheet vinyl transition between Kitchen and Hallway – Photo 109	None Detected
PKPTH0915-A04	(HSV2) Hidden sheet vinyl, brown 1/8" chip pattern	Teacher Housing Unit #1 – Hidden under newer sheet vinyl at carpet to sheet vinyl transition between Kitchen and Hallway – Photo 109	None Detected
PKPTH0915-A05	(HSV1) Hidden sheet vinyl, yellow/brown "alligator" pattern	Teacher Housing Unit #1 – Hidden under newer sheet vinyl at carpet to sheet vinyl transition between Kitchen and Hallway – Photo 109	None Detected

SAMPLE NUMBER	MATERIAL	LOCATION	ASBESTOS CONTENT
PKPTH0915-A06	(HSV1) Hidden sheet vinyl, yellow/brown "alligator" pattern	Teacher Housing Unit #1 – Hidden under carpet in Hallway at entrance to Bathroom – Photo 111	None Detected
PKPTH0915-A07	(SV2) Sheet vinyl, white with blue 4"x4" square pattern and decorative blue and red flowers pattern	Teacher Housing Unit #1 – At entrance into Bathroom – Photo 111	None Detected
PKPTH0915-A08	(SV2) Sheet vinyl, white with blue 4"x4" square pattern and decorative blue and red flowers pattern	Teacher Housing Unit #1 – At entrance into Boiler Room – Photo 112	None Detected
PKPTH0915-A09	Off-white vinyl covered gypsum wall board; with yellow mastic; with off-white wallpaper	Teacher Housing Unit #1 – On east wall of Kitchen – Photo 114	None Detected All Layers
PKPTH0915-A10	Off-white vinyl covered gypsum wall board; with yellow mastic	Teacher Housing Unit #1 – On east wall of Living Room – Photo 113	None Detected Both Layers
PKPTH0915-A11	Dark brown mastic for glued-on ceiling tile (do not analyze cellulose board ceiling tile)	Teacher Housing Unit #1 – Loose on glued-on ceiling tile laying on floor near entrance in Bedroom 01 – Photo 115	None Detected
PKPTH0915-A12	Dark brown mastic for glued-on ceiling tile (do not analyze cellulose board ceiling tile)	Teacher Housing Unit #1 – From ceiling near south wall in Bedroom 03 – Photo 116	None Detected
PKPTH0915-A13	Dark brown mastic for glued-on ceiling tile (do not analyze cellulose board ceiling tile)	Teacher Housing Unit #1 – From ceiling near north wall in Bathroom – Photo 126	None Detected
PKPTH0915-A14	White gypsum wall board	Teacher Housing Unit #1 – From damaged area of east wall in Boiler Room – Photo 121	None Detected
PKPTH0915-A15	White joint compound	Teacher Housing Unit #1 – From damaged area of east wall in Boiler Room – Photo 117	None Detected
PKPTH0915-A16	White joint compound	Teacher Housing Unit #1 – From damaged area of north wall in Boiler Room – Photo 118	None Detected
PKPTH0915-A17	White joint compound	Teacher Housing Unit #1 – From damaged area of wall at northwest corner of Boiler Room – Photo 119	None Detected
PKPTH0915-A18	Yellow mastic for "Marlite" wall panel	Teacher Housing Unit #1 – From north wall of Bathroom – Photo 127	None Detected

SAMPLE NUMBER	MATERIAL	LOCATION	ASBESTOS CONTENT
PKPTH0915-A19	Dark brown 6" cove base; with off-white mastic	Teacher Housing Unit #1 – From base of shower enclosure in Bathroom – Photo 128	None Detected Both Layers
PKPTH0915-A20	Black undercoating for stainless steel sink	Teacher Housing Unit #1 – On bottom of stainless steel sink in Kitchen – Photo 129	1.9% Chrysotile
PKPTH0915-A21	Black 4" cove base; with off-white mastic	Teacher Housing Unit #1 – From base of cabinetry in Kitchen – Photo 130	None Detected Both Layers
PKPTH0915-A22	Grey gummy window glazing compound	Teacher Housing Unit #1 – From wood framed window on east wall of Living Room – Photo 156	10% Chrysotile
PKPTH0915-A23	Hard white window glazing compound	Teacher Housing Unit #1 – From wood framed window on north wall of Bedroom 03 – Photo 157	None Detected

Table 1D includes samples taken in September 2015 in Teacher Housing Unit 2, and the results of the laboratory analysis. Asbestos field survey data sheets and laboratory reports are included in Appendix A. Refer to Appendix D for sample locations.

TABLE 1D - Teacher Housing Unit 2

SAMPLE NUMBER	MATERIAL	LOCATION	ASBESTOS CONTENT
PKPTH0915-A24	(SV1) Sheet vinyl, white with blue specks and diamond/block pattern	Teacher Housing Unit #2 – From north side of Kitchen – Photo 221	None Detected
PKPTH0915-A25	(SV3) Yellow with square and rectangles pattern	Teacher Housing Unit #2 – From entrance to Restroom – Photo 222	None Detected
PKPTH0915-A26	(SV3) Yellow with square and rectangles pattern	Teacher Housing Unit #2 – At damaged area of floor near center of Boiler Room – Photo 224	None Detected
PKPTH0915-A27	Hard white window glazing compound	Teacher Housing Unit #2 – From wood framed window on south side of Living Room – Photo 227	None Detected
PKPTH0915-A28	Grey gummy window glazing compound	Teacher Housing Unit #2 – From wood framed window on east side of Living Room – Photo 229	10% Chrysotile
PKPTH0915-A29	Black undercoating for stainless steel sink	Teacher Housing Unit #2 – On bottom of stainless steel sink in Kitchen – Photo 230	1.5% Chrysotile

SAMPLE NUMBER	MATERIAL	LOCATION	ASBESTOS CONTENT
PKPTH0915-A30	Black 4" cove base; with off-white mastic	Teacher Housing Unit #2 – From base of cabinetry in Kitchen – Photo 231	None Detected Both Layers
PKPTH0915-A31	Dark brown 4" cove base; with brown mastic	Teacher Housing Unit #2 – From base of wall next to door on south side of Bathroom – Photo 232	None Detected Both Layers
PKPTH0915-A32	White joint compound	Teacher Housing Unit #2 – From damaged area of wall on east side of Boiler Room – Photo 233	None Detected
PKPTH0915-A33	White joint compound	Teacher Housing Unit #2 – From damaged area of wall at northeast corner of Boiler Room – Photo 234	None Detected
PKPTH0915-A34	White joint compound	Teacher Housing Unit #2 – From damaged area of wall at northwest corner of Boiler Room – Photo 235	None Detected
PKPTH0915-A35	White gypsum wall board	Teacher Housing Unit #2 – From damaged area of wall on east side of Boiler Room – Photo 236	None Detected
PKPTH0915-A36	Yellow mastic for "Marlite" wall panel (do not analyze "Marlite")	Teacher Housing Unit #2 – From west wall of Bathroom – Photo 238	None Detected
PKPTH0915-A37	Off-white vinyl covered gypsum wall board; with yellow mastic	Teacher Housing Unit #2 – From east wall of Living Room – Photo 239	None Detected Both Layers
PKPTH0915-A38	Off-white vinyl covered gypsum wall board; with yellow mastic	Teacher Housing Unit #2 – From east wall of Kitchen – Photo 240	None Detected Both Layers

The following materials have been found to contain asbestos in this or previous surveys, or were assumed to contain asbestos.

## **Main School Building**

- Various colors and patterns of 12" x 12" floor tiles and associated asbestos-containing black mastic.
- 2. Various colors and patterns of sheet vinyl.
- 3. Tan stair tread on stairs leading to Mechanical Room from Kitchen.
- 4. Grey putty-like window glazing compounds at older windows.
- 5. White undercoatings on stainless steel sinks.
- 6. High temperature wiring insulation at incandescent and fluorescent light fixtures.
- 7. Flange gaskets and valve packings on piping (assumed).
- 8. Boiler gaskets and sealants (assumed).
- 9. Sealants on "zip-rib" roofing seams (assumed).
- 10. Patch tars and other sealants used on roofing components (assumed).

#### Teacher Housing Units 1 & 2

1. Black undercoating on stainless steel sink in Kitchen.

- 2. Grey putty-like window glazing compounds.
- 3. Boiler gaskets and sealants (assumed).
- 4. Vermiculite insulation at flue enclosure in Attic, and hidden in floor space (assumed).
- 5. Patch tars and other sealants used on roofing components (assumed).

The following materials have been found to be asbestos-free in this or previous surveys, but is not to be considered a complete list of asbestos-free materials.

#### Main School Building

- "Marlite" mastics.
- Joint compound and gypsum board throughout all eras.
- · Cove base mastics throughout all eras.
- Wall texture compounds throughout all eras.
- · Wall carpet mastic in the Gym.

## Teacher Housing Units 1 & 2

- Joint compound and gypsum board, including the vinyl covered gypsum wall board.
- Glued-on ceiling tile mastic (Teacher Housing Unit 1 only).
- "Marlite" mastic.
- All sheet vinyls that are not concealed under a plywood subfloor (if present).

The asbestos-containing materials discovered during this or previous surveys are discussed below.

## **Main School Building**

#### Floor Tile and Mastic

Various colors and patterns of 12" x 12" asbestos-containing floor tiles and associated black mastic were located in the 1980 portion of the school. Some of the tiles and mastic were concealed under newer floor finishes, and not all tiles contained asbestos. The floor tiles were generally in good condition. One exception was in the large classroom on the southeast side of the building where the asbestos-containing floor tiles have lost adhesion due to water intrusion and become damaged due to doors being opened and foot traffic. The other two areas noted were in the Gym along the east wall where the tiles had again lost adhesion due to water intrusion and become damaged. Floor tiles are not considered friable unless damaged, and the floor tile mastic is not considered friable. Any loose tiles should be abated by properly trained workers prior to building re-occupancy.

#### **Sheet Vinyl**

Various colors and patterns of sheet vinyl exist throughout the school. Only one pattern was found to be asbestos-containing and was located the Girl's Bathroom, the Boy's Bathroom, and the adjacent Janitor's Closet. This sheet vinyl was hidden under newer non-asbestos sheet vinyl in both the Girl's and Boy's Bathrooms. The sheet vinyl was generally in good condition and is not considered friable unless damaged. The sheet vinyl does not require any corrective action prior to building re-occupancy.

#### **Tan Stair Tread**

An asbestos-containing tan stair tread was used on the stairs leading from the Kitchen to the upstairs Mechanical Room. The stair tread was in poor condition, and although not considered friable, should be abated by properly trained workers prior to building re-occupancy.

## **Window Glazing Compounds**

Older windows at the building have a grey putty-like asbestos-containing window glazing compound. This material is used between the window glazing and retainers that hold the glazing in place. This material was in good condition and is not considered friable and does not require any corrective action prior to building re-occupancy.

### **Sink Undercoating**

An asbestos-containing white undercoating was used on the bottom of stainless steel sinks throughout the building. This material was in good condition and is not considered friable and does not require any corrective action prior to building re-occupancy.

## **High Temperature Wire Insulation**

Wires were visually inspected at various locations throughout the school. Asbestos-containing wire insulation was noted at a heat detector that was most likely used as an incandescent light fixture in the past, and inside of a fluorescent light fixture where it was used to connect fixtures together. The wire insulation was in good condition and is typically not considered friable and does not require any corrective action prior to building re-occupancy.

#### Flange Gaskets and Valve Packing

Due to the difficulty of sampling flange gaskets and valve packing, and the variability between gaskets that are original vs. replacement gaskets, etc., gaskets and valve packing on mechanical equipment and piping throughout the building are assumed to be asbestos-containing. These materials were in good condition but may become friable during removal for replacement. The gaskets and packings do not require any corrective action prior to building re-occupancy.

#### **Boiler Gaskets and Sealants**

Gaskets and sealants on the boilers are assumed to be asbestos-containing. These materials were in good condition but may become friable during removal for replacement. The gaskets and sealants do not require any corrective action prior to building re-occupancy.

#### "Zip-rib" Sealants

The roof was constructed of a "Zip-rib" style roof which commonly uses asbestos-containing sealants on the seams of the "eyes". The roof was not accessed during the site visit but is assumed to have used the asbestos-containing sealants on the seams of the "eyes". This material is not friable and does not require any corrective action prior to building re-occupancy.

## **Patch Tars and Other Sealants on Roofing Components**

Roofs commonly have various types of sealants and/or tars from either original construction or repairs made over time, and these materials commonly contain asbestos. The roof was not accessed during the site visit but is assumed to have asbestos-containing tars and sealants. These materials are not considered friable and do not require any corrective action prior to building re-occupancy.

## **Teacher Housing Units 1 & 2**

#### Sink Undercoating

An asbestos-containing black undercoating was used on the bottom of the stainless steel sink in the Kitchen. This material was in good condition and is not considered friable. However, due to the extensive fungal growth at the units, it is presumed the sink would be removed during any mold remediation activities by properly trained workers.

#### **Window Glazing Compounds**

Older windows in the units have a grey putty-like asbestos-containing window glazing compound. This material is used between the window glazing and retainers that hold the glazing in place. This material was in good condition and is not considered friable. However, due to the extensive fungal growth at the units, it is presumed the windows would be removed during any mold remediation activities by properly trained workers.

#### **Boiler Gaskets and Sealants**

Gaskets and sealants on the boilers are assumed to be asbestos-containing. These materials were in good condition but may become friable during removal for replacement. However, due to the extensive fungal growth at the units, it is presumed the boiler would be removed during any mold remediation activities by properly trained workers.

#### Vermiculite

There was no way to access the attic or floor spaces in either unit to inspect for the presence of Vermiculite insulation. The boiler enclosure and floor spaces are assumed to have an asbestos-containing loose fill Vermiculite insulation. Vermiculite is considered friable and is assumed to be in good condition. However, due to the extensive fungal growth at the units, it is presumed this material would be removed during any mold remediation activities by properly trained workers.

## **Patch Tars and Other Sealants on Roofing Components**

Roofs commonly have various types of sealants and/or tars from either original construction or repairs made over time, and these materials commonly contain asbestos. The roof was not accessed during the site visit but is assumed to have asbestos-containing tars and sealants. These materials are not considered friable and do not require any corrective action prior to building re-occupancy. However, due to the extensive fungal growth at the units which, in part, is likely caused by roof leaks, this material would likely require disturbance during roof repair or replacement activities.

#### 2. Asbestos in Dusts

The settled and concealed dusts were examined by an EPA Certified Building Inspector but no samples for asbestos in dusts were authorized for this project. Based on their visual inspection and experience from similar buildings, the inspector determined that the typical settled and concealed dusts are not "asbestos debris" from an asbestos-containing building material (ACBM). Based on similar sampling from similar buildings, the inspector also determined that the dusts are unlikely to contain more than one percent (1%) asbestos by weight, and therefore are not an asbestos-containing material (ACM).

## 3. Lead-Containing Materials

#### Lead-Testing

EHS-Alaska tested paint and other materials throughout the buildings using a NITON XRF lead paint analyzer. At the Main School Building, lead in paints tested varied from a trace amount to 3.3 mg/cm². Lead in other materials tested varied from a trace amount to 38.1 mg/cm². At Teacher Housing Units 1 & 2, lead in paints tested varied from a trace amount to 0.04 mg/cm². Only trace amounts of lead were found in other materials tested at Teacher Housing Units 1 & 2. Refer to the Lead Paint Screening Table in Appendix C that identifies the surfaces tested, and the results. The Paint Test Locations are shown in the Drawings in Appendix D.

#### **Paints**

There were varying lead contents found in the paints, based on what surfaces they are on, with most surfaces containing little lead (but are still classified as lead-containing materials by OSHA). In the Main School Building, the highest levels of lead were found on painted metal piping, with lower levels on walls and other painted surfaces, and lowest levels on pre-finished materials. In Teacher Housing Units 1 & 2, low levels of lead were found on all painted surfaces tested.

Lead based paints (paint containing more than 1.0 mg/cm² of lead) were identified in the Main School Building on painted metal piping in the Kitchen and Mechanical Room above. It is anticipated that other painted metal piping or equipment may be painted with lead-based paint. Lead was detected at very low levels in most of the painted floor, wall and ceiling surfaces. Low levels of lead found by XRF testing does not mean that the paints are free of lead, the paints may contain lead. However, these paints may not present a hazard to occupants or workers performing renovation or demolition if lead-safe work practices are followed.

#### **Ceramic Wall Tile and Glazing**

Relatively high concentrations of lead were found in the glazing of ceramic plumbing fixtures. The glazing of older ceramic sinks and hand dryers contained high lead levels. The concentrations of lead in ceramic glazing compounds should not be compared to lead-based paint criteria, as the glazing is inherently less likely to cause lead to be present in dusts or on surfaces, where it can be ingested. Lead in ceramic tile

glazing may not pose a hazard to occupants, or workers performing renovation or demolition if lead-safe work practices are followed. All ceramic fixtures in the facility should be assumed to contain lead.

#### **Plastic Components**

Relatively high concentrations of lead were found in plastic components at the Main School Building, such as "Formica" plastic laminate panels. The concentrations of lead in plastic compounds should not be compared to lead-based paint criteria. Lead in plastic compounds may have surface deterioration and if not cleaned regularly, lead may be present in dusts or on surfaces, where it can be ingested. Lead in plastic compounds may not pose a hazard to occupants, or workers performing renovation or demolition if good work practices are followed.

#### Metallic Lead in Batteries, Pipe Solder and Flashing

Metallic lead items identified in the Main School Building included assumed lead solder at copper piping, poured lead sealants at bell and spigot joints of waste and vent piping, and lead acid batteries in emergency lights and other battery backup equipment. In Teacher Housing Units 1 & 2, only assumed lead solder at copper piping was identified. If any of these lead-containing items are removed from the buildings they should be recycled or disposed of as hazardous waste.

#### 4. PCB-Containing Materials

#### **Light Ballasts**

Older fluorescent lights typically have PCB-containing ballasts. PCB-containing ballasts in fluorescent lights were banned in 1978, but manufacturers were allowed to use up existing stocks, and lights may have been reused from other facilities. The survey included examination of what were considered to be representative light fixtures, but not all fixtures were able to be accessed. All lights shall be inspected if removed or relocated. Unless ballasts were marked "No PCBs," they must be assumed to contain PCBs and must be disposed of as a hazardous waste when removed for disposal. Fluorescent light fixtures with PCB-containing ballasts were found in Teacher Housing Unit 2. In the Main School Building and in Teacher Housing Unit 1, only fluorescent light fixtures marked "No PCBs" were found.

Older HID lights may have PCB-containing ballasts. Due to height restrictions and sealed ballast enclosures, the HID fixtures were not able to be accessed. All HID lights shall be inspected during removal or relocation. If ballasts are not marked "No PCBs," we suggest contacting the manufacturer of the lights to determine if the ballasts contain PCB's, or assume that they contain PCB's and be disposed of as a hazardous waste.

## 5. Mercury-Containing Materials

#### Fluorescent Lamps

Fluorescent lamps use mercury to excite the phosphor crystals that coat the inside of the lamp. These lamps contain from 15 to 48 milligrams of mercury depending on their age and manufacturer.

#### **Thermostats**

Older thermostats or other electrical switches that contain mercury were noted in the Main School Building and Teacher Housing Units 1 & 2.

#### **High Intensity Discharge Lamps**

High Intensity Discharge (HID) lamps use mercury and sodium vapors in the lamp, and also typically have lead-containing solders at the bases. These lamps contain varying amounts of mercury depending on their age and manufacturer. Several HID fixtures and lamps on the exterior of the Main School Building were broken.

If any mercury-containing items are removed, they are required to be disposed of as hazardous waste or recycled.

#### 6. Other Hazardous Materials

#### Smoke detectors

Several smoke detectors that may contain radioactive materials were noted in the Main School Building and in Teacher Housing Units 1 & 2. If any radioactive items are removed from the buildings, they are required be disposed of as hazardous waste or recycled.

#### **Soil Contamination**

The scope of work for EHS-Alaska, Inc. did not include investigation of soils for petroleum or other contaminations.

## Refrigerants

A refrigeration system labeled "R404A" was noted in on the exterior of a cooler that was in an area that was deemed unsafe to access at the Main School Building. An air conditioning unit was found in the Server Room of the Main School Building that may contain ozone depleting refrigerants. Ozone depleting substances (ODS) are regulated by the EPA and must be removed by certified technicians prior to equipment disposal.

#### Glycol

The existing heating system is assumed to contain heating system glycol. Any glycol removed from the heating system shall be recovered and properly disposed of or recycled.

## 7. Suspect Fungal Growth

The investigation included a visual examination of the buildings for suspect fungal growth. Teacher Housing Units 1 and 2 were both in disrepair, with strong moldy and musky odors and visible fungal growth on nearly all surfaces and materials interior to the units. Many different types of fungal growth were noted throughout both units, but no samples were authorized for this project, and therefore identification of these fungi is unknown. Moisture readings were not taken from the Teacher Housing Units since most building materials were water saturated with visible condensation on the interior sides of the windows and other surfaces. The source of water intrusion appears to be from a combination of roof leaks, lack of ventilation, and environmental conditions.

The Main School Building was generally in fair condition with relatively small visible areas of water damage noted. Roof leaks in the Mechanical Room above the Kitchen have resulted in damage to the Mechanical Room, the Kitchen, and an adjacent classroom to the south. Multiple trash cans or buckets were placed in the Mechanical Room to catch the water but have overflowed causing more damage. There was also water damage noted in the Gym where daylight was visible through cracks in the gypsum board wall and ceiling. This appears to have been caused by building settling and a lack of exterior siding or other protection. In both areas, water has damaged a variety of building components including ceilings, walls, floors, light fixtures, etc. Suspect fungal growth was noted in both of these locations.

#### E. REGULATORY CONSTRAINTS

#### 1. Asbestos-Containing Materials

The Federal Occupational Safety and Health Administration (29 CFR 1926.1101) and the State of Alaska Department of Labor (8 AAC 61) have promulgated regulations requiring testing for airborne asbestos fibers; setting allowable exposure limits for workers potentially exposed to airborne asbestos fibers; establishing contamination controls, work practices, and medical surveillance; and setting worker certification and protection requirements. These regulations apply to all workplace activities involving asbestos-containing materials.

The EPA regulations, issued as Title 40 of the Code of Federal Regulations, Part 61 (40 CFR 61) under the National Emission Standards for Hazardous Air Pollutants (NESHAP) established procedures for

handling ACM during asbestos removal and waste disposal. These regulations required an owner (or the owner's contractor) to notify the EPA of asbestos removal operations and to establish responsibility for the removal, transportation, and disposal of asbestos. It is recommended that clearance sampling which complies with the EPA's Asbestos Hazard Emergency Response Act (AHERA) protocol be required following removal of asbestos-containing materials to document that the asbestos has been properly removed.

Additionally, the NESHAP regulations address three categories of ACM in a building being demolished:

- Friable, or regulated ACM (RACM) which must be removed from a building before the building is demolished
- 2. Category I non-friable ACM (resilient flooring, asphalt roofing products, packing and gaskets)
- 3. Category II non-friable ACM (non-friable ACM other than Category I ACM).

If allowed by the disposal site, the EPA allows Category I and II non-friable ACM to remain in a building during demolition if: (1) Category I ACM is not in poor condition and is not friable and (2) the probability is low that Category II ACM will become crumbled, pulverized or reduced to powder during demolition. The condition of the ACM and method of demolition will generally determine if Category I and II non-friable ACM may be left in the building during demolition. This EPA standard also requires that no visible emissions be generated from the ACM during removal and transportation and does not allow intentional burning of any building containing ACM.

The EPA regulations require an owner (or the owner's contractor) to notify the EPA of asbestos removal operations and to establish responsibility for the removal, transportation, and disposal of asbestos-containing materials.

The disposal of asbestos waste is regulated by the EPA, the Alaska Department of Environmental Conservation, and the disposal site operator. Wastes being transported to the disposal site must be sealed in leak tight containers prior to disposal and must be accompanied by disposal permits and waste manifests.

#### 2. Dusts with Asbestos

Settled and concealed dusts above ceilings, and at other areas that are not routinely cleaned (such as inside ducts and at roofs, etc.) are assumed to have measurable concentrations of asbestos. Based on sampling of similar settled and concealed dusts at similar buildings, those dusts are assumed to contain less than 1 percent asbestos. Normal settled and concealed dusts are distinct and treated differently from debris resulting from damaged asbestos-containing materials.

Background levels of asbestos in dusts for a particular location will depend on many factors, including whether or not asbestos occurs naturally in soils in the area.

#### Likely sources of asbestos in dusts include natural occurrences of asbestos

The types of asbestos found in settled and concealed dusts often contain actinolite, anthophylite, and tremolite forms of asbestos which are not commonly found in bulk samples taken of materials from buildings. Those forms of asbestos may come from natural occurrences of asbestos in an outside source, such as rock or ore deposits, which appear to be common in Alaska.

Because the type of disturbance, concentration of asbestos in the dusts, cohesiveness of the dusts and room sizes will change, the airborne asbestos levels expected during any future project will depend on the contractor's means and methods of conducting the work. The mere presence of asbestos in the dusts does not necessarily imply that a "hazard" exists which would require the use of specially trained workers to "abate" the "hazard". All dusts will likely be required to be removed from the areas where asbestoscontaining materials are being removed (abatement areas) in order to achieve clearances. The dusts in the other areas would need to be controlled so as to limit worker exposures and prevent contamination of

other areas of the building.

There is no established correlation between settled or adhered dusts with measureable concentrations of asbestos and airborne concentrations. The definition in the OSHA regulations of asbestos-containing materials as those materials that contain 1 percent or more asbestos by weight, apply to cohesive materials and not to dusts. The OSHA regulations are essentially "performance based", if workers are exposed above the permissible exposure limits, then all of the requirements in the regulations become effective.

## 3. Lead-Containing Materials

The EPA Standard 40 CFR 745, Lead-Based Paint Poisoning Prevention in Certain Residential Structures, defines lead-based paint hazards and regulates lead based paint activities in target housing and child-occupied facilities. The requirements of this regulation include training certification, pre-work notifications, work practice standards and record keeping. Areas typically classified as child occupied facilities may include but are not limited to: day care facilities, preschools, kindergarten classrooms, restrooms, multipurpose rooms, cafeterias, gyms, libraries and other areas routinely used by children under 6 years of age. New training requirements for Firms (Contractors) and Renovators (Workers) became effective on April 22, 2010. The buildings are not classified as a child occupied facility, therefore the requirements of 40 CFR 745 do not apply.

Federal OSHA (29 CFR 1926.62) and the State of Alaska (8 AAC Chapter 61) have promulgated regulations that apply to all construction work where employees may be exposed to lead. The disturbance of any surfaces painted with lead-containing paint requires lead-trained personnel, personnel protective procedures, and air monitoring until exposure levels can be determined. If initial monitoring verifies that the work practices being used are not exposing workers, monitoring and protection procedures may be relaxed. Experience has shown that some paints in most buildings will contain low concentrations of lead and disturbance of those paints are still regulated under the OSHA lead standard, 29 CFR 1926.62. Low levels of lead found by XRF testing does not mean that the paints are free of lead, the paints may contain lead, and OSHA regulations apply anytime measurable amounts of lead are present in paints.

Settled and concealed dust above ceilings, and at other areas that are not routinely cleaned are assumed to have measurable concentrations of lead. Background levels of lead in dusts for a particular location will depend on many factors, including whether or not engines utilizing leaded gasoline were run in or near a building, and upon the age of the building, and thus the age of the dusts. Because the type of disturbance, quantity of lead dusts, cohesiveness of the dusts and room sizes will change, the airborne lead levels expected during any future project will depend on the contractor's means and methods of conducting the work. The mere presence of lead in the dusts does not necessarily imply that a "hazard" exists which would require the use of specially trained workers to "abate" the "hazard".

There is no established correlation between settled or adhered lead dust concentrations and airborne concentrations. The OSHA regulations are essentially "performance based", if workers are exposed above the permissible exposure limits, then all of the requirements in the regulations become effective.

The EPA requires that actual construction or demolition debris that contains lead or lead-containing paint or other heavy metals be tested using the TCLP test to determine if the waste must be treated as hazardous waste. All federal, state and local standards regulating lead and lead-containing wastes are required to be followed during any future renovation or demolition at the buildings.

There are no hazardous waste landfills in Alaska and the lead-containing wastes (if shown to be hazardous waste) would have to be packaged for shipping and disposal. This report assumes that disposal would take place in Seattle or elsewhere in the Pacific Northwest.

## 4. PCB-Containing Materials

The EPA has promulgated regulations (40 CFR Part 761) that cover the proper handling and disposal of PCB-containing materials. PCB-containing equipment was found by this survey in Teacher Housing Unit 2, and any removed PCB-containing equipment is required to be disposed of at fully permitted hazardous waste facilities. If any PCB-containing equipment is discovered at the Main School Building or Teacher Housing Unit 1, and if they will be removed, those materials are required to be disposed of at fully permitted hazardous waste facilities. The EPA regulates liquid PCBs differently from non-liquid materials. Workers who remove or handle PCB-containing or PCB-contaminated materials or who transport or dispose of PCB wastes must be trained and certified in hazardous waste operations and emergency response (HAZWOPER) as required by 29 CFR 1910.120 and the State of Alaska Department of Labor (8 AAC 61). The Department of Transportation under 49 CFR Parts 100-199 regulates the marking, packaging, handling and transportation of hazardous materials. All federal, state and local standards regulating PCBs and PCB waste must be followed during this project.

## 5. Mercury-Containing Materials

Thermostats and mercury-containing lamps are classified by the EPA as Universal Wastes. The EPA encourages that all Universal Wastes be recycled in accordance with 40 CFR 273. Mercury and mercury-containing products are considered hazardous waste if TCLP testing of the waste for mercury confirms the mercury content to be greater than the EPA criteria of 0.2 mg/l.

#### 6. Other Hazardous Materials

#### Refrigerants

A cooler labeled "R404A" and an air conditioning unit were noted at the Main School Building. Typically, refrigeration and air conditioning systems with ODS shall be maintained in order to prevent discharge of ODS. Systems that are to be removed, or dismantled shall have refrigerants containing ODS recovered and disposed of or recycled in accordance with 40 CFR 82.

#### **Chemical Hazards**

The EPA has promulgated regulations (40 CFR Parts 260 to 299 amongst others) that cover the proper handling and disposal of waste chemicals, including listed wastes, which are ignitable, corrosive, reactive, toxic, or an acute hazardous waste or wastes that exhibit the characteristics of toxicity. All construction workers who are required to remove or handle chemical hazards or to transport or dispose of chemical wastes shall be trained and certified as required by the U.S. Department of Labor (29 CFR 1910.120) and the State of Alaska Department of Labor (8 AAC 61). Transportation of chemical hazards are regulated by Department of Transportation regulations under 49 CFR Parts 171 to 178 amongst others.

#### **Radioactive Materials**

Smoke detectors were present in the project area that may contain a radioactive material. If the detectors are of the ionization type they typically contain a small amount of Americium. If removed, the detectors should be returned to the owner for reuse or returned to the manufacturer for disposal or recycling. There are no licensed disposal facilities for radioactive wastes in Alaska.

## 7. Suspect Fungal Growth

Molds are found in virtually every environment and can be detected, indoors and outdoors, year round. Molds reproduce by means of tiny spores, which are extremely small and usually not visible to the naked eye. Mold spores spread by floating through outdoor and indoor air. Outdoors, molds play a part in nature by breaking down organic matter such as fallen leaves and dead trees. Mold may begin growing indoors when mold spores land on surfaces that are wet. Although there are thousands of types (genus-species) of molds, a relatively small number account for most indoor and water damage situations. Some mold are considered worse (more allergenic or toxic) than others. The most "common" mold Cladosporium is widespread inside and outside and is typically not considered as bad as some other molds. The wet "black" molds Chaetomium and Stachybotrys often occur on sheetrock and are

considered problem molds. They have large spores and tend not to occur at high levels in the air unless disturbed. They require very damp conditions for growth. The most common "problem" molds are Aspergillus-Penicillium. They are considered "opportunistic" molds and require only moderately damp conditions for growth. They have very small spores which easily become airborne.

Currently, there are no federal standards or recommendations for acceptable exposures to airborne concentrations of mold or mold spores. Research on the health effects of mold exposure is ongoing. According to the Occupational Safety and Health Administration (OSHA), most typical indoor air exposures to mold do not present a risk of adverse health effects. Molds can cause adverse effects by producing allergens (substances that can cause allergic reactions). For those people who are sensitive to molds, exposure can cause symptoms such as nasal stuffiness, eye irritation, wheezing, or skin irritation. Severe reactions may occur among workers exposed to large amounts of molds in occupational settings, such as farmers working around moldy hay. Severe reactions may include fever and shortness of breath. Potential health concerns as well as building damage are important reasons to prevent mold growth and to remediate existing problem areas. The advice of a medical professional should always be sought if there are any emerging health issues.

Since mold spores are ever-present in the environment, it is virtually impossible to make a building mold-free. The goal of any remediation efforts is to remove the mold "growth" after ensuring all moisture intrusion problems have been corrected. Workers who may disturb mold spores should use good work practices and follow the guidelines in IICRC S520, Standard and Reference Guide for Professional Mold Remediation.

#### F. RECOMMENDATIONS

#### 1. Asbestos-Containing Materials

The asbestos-containing materials identified in the buildings are typically in intact condition and are classified as non-friable ACM. All asbestos-containing materials that will be disturbed by any renovation or demolition work are required to be removed by trained asbestos workers.

#### 2. Dusts with Asbestos

Dusts with measurable concentrations of asbestos are assumed to be present, but are not classified as asbestos-containing materials, or as debris from asbestos-containing materials. Workers disturbing dusts are required to have hazard communication training in accordance with OSHA regulations, but are not required to receive 40 hours of training, which is required for asbestos workers. At least an initial exposure assessment or data from previous air monitoring is required to show that the contractor's chosen means and methods of controlling worker exposure to airborne contaminants below the OSHA permissible exposure limits (PELs) is required.

#### 3. Lead-Containing Materials

Federal OSHA (29 CFR 1926.62) and the State of Alaska (8 AAC Chapter 61) have promulgated regulations that apply to all construction work where employees may be exposed to lead, including disturbance of paints with low concentrations of lead.

The EPA Standard 40 CFR 745, Lead-Based Paint Poisoning Prevention in Certain Residential Structures, defines lead-based paint hazards and regulates lead based paint activities in target housing and child-occupied facilities. Contractors disturbing lead-based paints in target housing and child occupied facilities must comply with 40 CFR 745.

Worker exposure to lead may be able to be controlled below the OSHA permissible exposure limit if proper engineering controls and procedures are used during renovation. Lead is a potentially hazardous waste and the EPA requires that all wastes that contains lead be tested to determine if they must be

treated as hazardous waste. A TCLP test of the waste stream(s) produced by the Contractor's means and methods are required to be performed to determine if those wastes will be hazardous or non-hazardous.

#### 4. PCB-Containing Materials

If any PCB-containing ballasts are removed or replaced, they will need to be removed, handled, packaged and disposed of in accordance with all regulations.

## 5. Mercury-Containing Materials

If any mercury-containing materials are removed or replaced, they will need to be removed, handled, packaged and disposed of in accordance with all regulations. If mercury-containing lamps and thermostats are handled and disposed of in accordance with the Universal Waste Regulations, no TCLP test is required. If the Contractor chooses to perform a TCLP test of fluorescent lamps, the test shall be conducted in accordance with the requirements of ANSI/NEMA Standard Procedure for Fluorescent Lamp Sample Preparation and Toxicity Characteristic Leaching Procedure, C78.LL 1256-2003 or latest version.

#### 6. Other Hazardous Materials

If any radioactive materials are removed or replaced, they will need to be removed, handled, packaged and disposed of in accordance with all regulations.

If the cooler labeled "R404A" or the air conditioning unit with ODS are removed or replaced, they will need to be handled, packaged and disposed of in accordance with all regulations.

## 7. Suspect Fungal Growth

EPA guide EPA 402-K-01-001, Mold Remediation in Schools and Commercial Buildings, sets forth recommendations regarding mold remediation and worker protection. It is recommended that an experienced, qualified contractor be hired to perform the work at the site in accordance with this guide, amongst other publications regarding mold remediation.

#### G. LIMITATIONS

The conclusions and recommendations contained in this report are based upon professional opinions with regard to the subject matter. These opinions have been arrived at in accordance with currently accepted environmental consulting and engineering standards and practices and are subject to the following inherent limitations:

## 1. Accuracy of Information

The laboratory reports utilized in this assessment were provided by the accredited laboratories cited in this report. Although the conclusions, opinions, and recommendations are based in part, on such information, our services did not include the verification of accuracy or authenticity of such reports. Should such information provided be found to be inaccurate or unreliable, EHS-Alaska, Inc. reserves the right to amend or revise its conclusions, opinions, and/or recommendations.

#### 2. Site Conditions

This limited survey did not include investigation of the entire site and may not be valid outside the survey area. The intent of this survey was to identify and verify present conditions of common hazardous materials that may be present at the site. This survey is not intended to be utilized as the sole design document for abatement. This survey was conducted while the site was unoccupied and without utilities.

All inspections were performed with furniture, equipment and/or stored items in place. The scope of work for this survey did not include identification of all potentially hazardous materials that may be present at this site, and was limited to the scope of work agreed upon with our client. Although a concerted effort was made to identify those common hazardous materials likely to be affected by any future project, some hazardous materials may have been hidden by furniture, equipment or stored items and may not have been identified. The survey investigated representative materials and items, such as lights and mechanical components. Variations may occur between materials and items that appear to be the same, but are actually of different construction or materials. Other asbestos-containing or potentially hazardous materials may be present in the facilities that were concealed by structural members, walls, ceilings or floor coverings, or in materials where testing was not conducted.

Additionally, the limited mold assessment included only visual evaluation of the Main School Building and Teacher Housing Units 1 & 2, and no other structures were included in the assessment. No air sampling was conducted to assess potential mold exposures to potential occupants or workers.

The findings we have presented within this report were based on limited research and on the visual inspection that was conducted at this site at the time and date specified. They should not be construed as a definite conclusion regarding the microbiological materials at this site. The data presented in this report should be considered representative of the time of our site inspection. Changes in site conditions can occur with time, because of natural variations in airborne concentrations, seasonal variations, differing airflow patterns through the buildings, and human activity. Actual conditions in areas not investigated may differ from those in this report.

Different people have highly variable reactions to microbial agents. None of the information contained herein should be construed as medical advice or a call to action for evacuation. Any decision relative to medical significance should be made by a qualified physician. The results given throughout this study are valid only for the locations and dates indicated. EHS-Alaska, Inc. is not responsible for any action, legal or otherwise, or lack of action resulting from the interpretation of data during this assessment.

EHS-Alaska, Inc. followed currently accepted industrial hygiene practices, including professional opinions based on observations. The recommendations were derived in part from the "Assessment, Remediation, and Post-Remediation Verification of Mold in Buildings," published in 2004 by the American Industrial Hygiene Association (AIHA), the New York City Department of Health "Guidelines on Assessment and Remediation of Fungi in Indoor Environments" updated in 2002 and "Bioaerosols: Assessment and Control", by the American Conference of Governmental Industrial Hygienists (ACGIH), published in 1999. These guidelines are generally accepted as "industry standard" for microbial remediation protocols. Other than this, no warranty is implied or intended.

## 3. Changing Regulatory Constraints

The regulations concerning hazardous materials are constantly changing, including the interpretations of the regulations by the local and national regulating agencies. Should the regulations or their interpretation be changed from our current understanding, EHS-Alaska, Inc. reserves the right to amend or revise its conclusions, opinions, and/or recommendations.

## **APPENDIX A**

Asbestos Bulk Sample Field Survey Data Sheets and Laboratory Reports



EHS-Alaska, Inc.
11901 Business Blvd., Suite 208, Eagle River, AK 99577
(907) 694-1383 • (907) 694-1382 fax
e-mail • ehsak@ehs-alaska.com

PROJECT NO:	PROJECT NAME:	FACILITY:			COLLECTION DATE:				
7395-01	Pitka's Point School Site Hazmat Survey	Main School Building			16/2015				
- CHAIN OF CUSTODY RECORD									
ANALYSIS	PLM BULK PLM DUST TEM BULK TYPE: TURNAROUND: DISPO		OSAL:	QUANTITY					
REQUESTED:	LEAD DUST LEAD TCLP LEAD P.		5 DAY NO	RMAL	18				
	TEM MICROVAC DUST (ASTM 5756) LEAD SPECIAL INSTRUCTIONS / COMMENTS:								
	L/ATL								
COLLECTED BY (signature)	COLLECTED BY (signature)  SELECTED LABORATORY  LAB: RETURN A SIGNED COPY OF THIS FORM WITH								
Christopher Ottosen  PRINTED NAME  SEP 2 2 2015  SAMPLES ACCEPTED BY  SAMPLES ACCEPTED BY									
**DO NOT ANALYZE FOAM PAINTS OR WOOD** Detected									
20110972/TBI24-11-146  CERT# / AHERA#  See sample location drawing for more detailed explanation of exact									
Fed Ex	loca	tions.	r more detailed exp	lanation	of exact				
SHIPPING METHOD	10 757 RMA QUE 15		10 est						
COURIER (signature)	DATE	- 9124115 (R	dbc 9-29-	15					
DATE/TIME //	- CM		7000 6 1-21-	/ <i>)</i>					
TWO SAMPLE NO	FIELD SURV	EY DATA							
EHS SAMPLE NO.  LAB ID NO	SAMPLE DESCRIPTION, (COLOR, MATERIAL TYPE, LAYERS, FRIABILITY)	LOCATION/CO (INCLUDING PHO	MMENTS DTO/XREF)	FOR	RESULTS EHS-ALASKA SE ONLY				
PKP0915-A01	(SV1) Sheet vinyl, tan with brown swirl	From southeast corner of	Bathroom – Photo	NP	ET PV				
5746675	pattern; with yellow mastic; with white	311			yprs				
PKP0915-A02					Dr.				
20, 61 g. English - And 1999-209-201	Yellow mastic for ceramic wall tile	At damaged area of north wall behind urinal in Bathroom – Photo 312		ND					
5746676	III Batilioolii – Filoto 312								
PKP0915-A03	White gypsum wall board	From behind ceramic wall tile at penetration		ND	7 - 34				
5746677	for heat piping on south wall in Bathroom – Photo 313								
PKP0915-A04	Brown mastic for ceramic floor tile  At damaged area of flooring at entrance i			ND					
5746678		,	100						
PKP0915-A05									
	Yellow mastic for "Marlite" wall panel (do not analyze "Marlite" wall panel)	At stub wall next to showers in Girl's Bathroom – Photo 374		ND	ND				
5746679	Not analyze Wante wan paner)	Datinooni – Tiloto 574	W 11						
PKP0915-A06	Yellow mastic for carpet	At entrance to first floor C		ND					
5746680		southwest corner of buildi	ng – Photo 376						
PKP0915-A07	Brown gypsum wall board	At damaged area of north	wall next to	ND					
	Sypoun Hair board	entrance into Kitchen in la		עטו					
5746681 PKP0915-A08		first floor – Photo 420	٠,						
	(FT3) Floor tile, 12"x12" tan with brown and white streaks  From damaged area of flooring near center of Kitchen – Photo 42.1								
5746682	witte streams	Kitchen – Photo 421	, ,		A. Balan				
PKP0915-A09	(FT2) Floor tile, 12"x12" tan with light and	From damaged area of flo	oring near door at	NDI	3.14				
5746683	dark streaks; with tan mastic	southeast corner of Gym -		ND 1	apris				
					U				



EHS-Alaska, Inc.
11901 Business Blvd., Suite 208, Eagle River, AK 99577
(907) 694-1383 • (907) 694-1382 fax
e-mail • ehsak@ehs-alaska.com

PROJECT NO:	PROJECT NAME:	FACILITY:	COLLECTION DATE:
7395-01	Pitka's Point School Site Hazmat Survey	Main School Building	09/16/2015
WW 6 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	FIELD SUR	VEY DATA	
FHS SAMPLE NO			PROVIE MO

7373-01	Fitka s Foint School Site Hazmat Survey	Main School Building	09/16/2015	
	FIELD SURV	VEY DATA		
EHS SAMPLE NO.  LAB ID NO	SAMPLE DESCRIPTION, (COLOR, MATERIAL TYPE, LAYERS, FRIABILITY)	LOCATION/COMMENTS (INCLUDING PHOTO/XREF)	RESULTS FOR EHS-ALASKA USE ONLY	
PKP0915-A10 <b>57466</b> 8 <b>4</b>	White gypsum wall board	At base of west wall at damaged area in Gym - Photo 448	ND	
PKP0915-A11	Yellow mastic for wall carpet	At base of west wall at damaged area in Gym - Photo 448	ND	
5746685 PKP0915-A12 5746686	White wall texture	At area of peeling paint on south side of second floor Office across the hall from the Server Room – Photo 522	NP	
PKP0915-A13 5746687	White wall texture	Under window on south side of second floor hallway near Server Room – Photo 523	ND	
PKP0915-A14 5746688	Black putty	On wood support for A/C unit on south side of Server Room – Photo 524	ND	
PKP0915-A15 5746689	Floor tile, 12"x12" pink with white and black streaks; with tan mastic	Near door on west side of second floor Storage Room – Photo 525	ND Boll Lagers	
PKP0915-A16 5746690	Floor tile, 12"x12" pink with white and black streaks; with tan mastic	On eest side of second floor Storage Room – Photo 526	ND Bill Layers	
PKP0915-A17 5746691	Yellow mastic for carpet	Near center of Library – Photo 562	ND	
PKP0915-A18 5746692	White gypsum wall board; with white wall texture	At damaged area of wall above door at northeast corner of Library – Photo 612	ND	
END	END	END		



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

% Non-Fibrous Material

100

% Non-Fibrous Material

Local: 856-231-9449 Fax: 856-231-9818

**Client:** EHS Alaska Incorporated **Report Date:** 9/28/2015

11901 Business Blvd., Ste 208

99577-7701 Pitka's Point School Site Eagle River AK **Project:** 

> **Project No.:** 7395-01

374723

Report No:

From SE Corner Of Bathrm

#### **BULK SAMPLE ANALYSIS SUMMARY**

Lab No .: 5746675

% Asbestos

**Analysis Performed By:** 

White Floor Tile **Description / Location:** 

Client No.: PKP0915-A01

% Asbestos % Non-Asbestos Fibrous Material Type Type

None Detected None Detected None Detected None Detected

White Mastic Lab No .: 5746675 **Description / Location:** Layer No.: 2

Client No.: PKP0915-A01 From SE Corner Of Bathrm

% Non-Asbestos Fibrous Material % Non-Fibrous Material % Asbestos Type Type

None Detected None Detected None Detected None Detected 100

Yellow Mastic Lab No.: 5746675 **Description / Location:** Layer No.: 3

Client No.: PKP0915-A01 From SE Corner Of Bathrm

% Non-Asbestos Fibrous Material % Non-Fibrous Material % Asbestos Type Type

None Detected None Detected None Detected None Detected 100

5746676 Yellow Mastic Lab No .: **Description / Location:** 

Type

R. McQuiggan

PKP0915-A02  $At\ Damaged Area NW all Behind Urinal Bathrm$ Client No.:

% Non-Asbestos Fibrous Material None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

> This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory.

> > Approved By:

Type

US EPA 600/R-93/116 by Polarized Light Microscopy, (ELAP 198.1 where applicable) **Analytical Method:** 

Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not **Comments:** 

quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of

the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing.

Frank E. Ehrenfeld, III Date: 9/28/2015 Laboratory Director



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285 Local: 856-231-9449

Fax: 856-231-9818

Client: EHS Alaska Incorporated **Report Date:** 9/28/2015

11901 Business Blvd., Ste 208

99577-7701 Pitka's Point School Site Eagle River AK **Project:** 

> **Project No.:** 7395-01

374723

**BULK SAMPLE ANALYSIS SUMMARY** 

Lab No .: 5746677

White Sheetrock **Description / Location:** 

Client No.: PKP0915-A03 Behind Ceramic Wall Tile Heat Pipe SWall Bathrm

Cellulose

Report No:

% Asbestos Type % Non-Asbestos Fibrous Material Type

Trace

Fibrous Glass

5746678 Lab No.:

None Detected

**Description / Location:** 

Brown Mastic

Client No.: PKP0915-A04 Damaged AreaOfFloorAtEntranceIntoSchool

% Asbestos

Type

None Detected

% Non-Asbestos Fibrous Material

Type

% Non-Fibrous Material

% Non-Fibrous Material

95

None Detected

None Detected

None Detected

None Detected

100

Lab No .:

5746679

**Description / Location:** 

Yellow Mastic

Client No.: PKP0915-A05 StubWall Next To Showers In Girls Bathrm

% Asbestos

Type

% Non-Asbestos Fibrous Material

Type

% Non-Fibrous Material

None Detected

None Detected

None Detected

None Detected

Lab No .:

5746680

**Description / Location:** 

Yellow Mastic

Client No.:

PKP0915-A06

Entrance To First Floor Classrm SW Corner Bldg

% Asbestos

Type

% Non-Asbestos Fibrous Material

Type

% Non-Fibrous Material

None Detected

None Detected

None Detected

None Detected

100

Accreditation

NIST-NVLAP No. 101165-0

NY-DOH No. 11021

AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory.

**Analytical Method:** 

US EPA 600/R-93/116 by Polarized Light Microscopy, (ELAP 198.1 where applicable)

**Comments:** 

Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing.

**Analysis Performed By:** 

R. McQuiggan

Date:

9/28/2015



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285 Local: 856-231-9449

Fax: 856-231-9818

Client: EHS Alaska Incorporated **Report Date:** 9/28/2015

11901 Business Blvd., Ste 208

99577-7701 Pitka's Point School Site Eagle River AK **Project:** 

> **Project No.:** 7395-01

374723

#### **BULK SAMPLE ANALYSIS SUMMARY**

Lab No .: 5746681

**Description / Location:** 

Lt Tan Sheetrock

Client No.: PKP0915-A07  $Damaged Area NW all Next To Kit Entrance 1 st\ Flr$ 

Report No:

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected

Cellulose Trace

Fibrous Glass 5

5746682 Lab No.:

**Description / Location:** 

Tan/Brown Floor Tile 12x12

Client No.: PKP0915-A08 Damaged AreaOfFlooringNearCenterKitchen

% Asbestos

Type

% Non-Asbestos Fibrous Material

Type

% Non-Fibrous Material

95

None Detected

None Detected

None Detected

None Detected

100

Lab No .:

5746683

**Description / Location:** 

Brown Floor Tile 12x12

Client No.: PKP0915-A09 DamagedAreaNearDoorSECornerGym

% Asbestos

Type

% Non-Asbestos Fibrous Material

Type

% Non-Fibrous Material

None Detected

None Detected

Cellulose

Lab No .:

5746683

**Description / Location:** 

Tan Mastic

Layer No.: 2

Client No.:

PKP0915-A09

DamagedAreaNearDoorSECornerGym

% Asbestos

Type

% Non-Asbestos Fibrous Material

Type

% Non-Fibrous Material

None Detected

None Detected

None Detected

None Detected

100

Accreditation

NIST-NVLAP No. 101165-0

NY-DOH No. 11021

AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory.

**Analytical Method:** 

US EPA 600/R-93/116 by Polarized Light Microscopy, (ELAP 198.1 where applicable)

**Comments:** 

Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing.

**Analysis Performed By:** 

R. McQuiggan

Date:

9/28/2015



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285 Local: 856-231-9449

% Non-Fibrous Material

Fax: 856-231-9818

Client: EHS Alaska Incorporated **Report Date:** 9/28/2015

11901 Business Blvd., Ste 208

99577-7701 Pitka's Point School Site Eagle River AK **Project:** 

> **Project No.:** 7395-01

374723

#### **BULK SAMPLE ANALYSIS SUMMARY**

Lab No .: 5746684

**Description / Location:** White Sheetrock

Client No.: PKP0915-A10 Base Of W Wall Damaged Area Gym

Report No:

% Asbestos % Non-Asbestos Fibrous Material Type

% Non-Fibrous Material Type

Fibrous Glass 2 None Detected None Detected 98

5746685 Lab No.:

Type

Yellow/Brown Mastic **Description / Location:** 

Client No.: PKP0915-A11

% Asbestos

Base Of W Wall Damaged Area Gym

Type

% Non-Asbestos Fibrous Material None Detected None Detected None Detected None Detected 100

White Texture Peeling Paint Lab No .: 5746686 **Description / Location:** 

Client No.: PKP0915-A12 SSide2ndFlrOfficeAcrossHallServerRm

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected

White Texture Lab No .: 5746687 **Description / Location:** 

PKP0915-A13 Under Window SSide 2nd Flr Hallway Server RmClient No.:

% Asbestos Type % Non-Asbestos Fibrous Material % Non-Fibrous Material Type

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021

AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory.

**Analytical Method:** 

US EPA 600/R-93/116 by Polarized Light Microscopy, (ELAP 198.1 where applicable)

**Comments:** 

Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing.

**Analysis Performed By:** R. McQuiggan



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285 Local: 856-231-9449

% Non-Fibrous Material

Fax: 856-231-9818

Client: EHS Alaska Incorporated Report Date: 9/28/2015

11901 Business Blvd., Ste 208

Eagle River AK 99577-7701 **Project:** Pitka's Point School Site

**Project No.:** 7395-01

374723

#### **BULK SAMPLE ANALYSIS SUMMARY**

**Lab No.:** 5746688

**Description / Location:** Grey Putty

Client No.: PKP0915-A14

WoodSupport For A/C UnitS SideServer Rm

Near Door W Side2nd Floor Storage Rm

Report No:

% Asbestos Type % Non-Asbestos Fibrous Material Type

Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected 5 Cellulose 95

Lab No.: 5746689 Description / Location: Pink/Grey Floor Tile 12x12

Client No.: PKP0915-A15

Near Door W Side2nd Floor Storage Rm

% Asbestos Type % Non-Asbestos Fibrous Material Type

None Detected None Detected None Detected 100

Lab No.: 5746689 Description / Location: Yellow Mastic Layer No.: 2

Client No.: PKP0915-A15

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method:

US EPA 600/R-93/116 by Polarized Light Microscopy, (ELAP 198.1 where applicable)

Comments:

Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing.

Analysis Performed By: R. McQuiggan



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285 Local: 856-231-9449

100

Fax: 856-231-9818

Client: EHS Alaska Incorporated **Report Date:** 

11901 Business Blvd., Ste 208

99577-7701 Pitka's Point School Site Eagle River AK **Project:** 

> **Project No.:** 7395-01

Report No:

9/28/2015

374723

#### **BULK SAMPLE ANALYSIS SUMMARY**

5746690 Lab No .:

Pink/Grey Floor Tile **Description / Location:** 

Client No.: PKP0915-A16 E Side 2nd Floor Storage Rm

% Asbestos % Non-Asbestos Fibrous Material % Non-Fibrous Material Type Type

None Detected None Detected None Detected None Detected

Yellow Mastic Lab No .: 5746690 **Description / Location:** Layer No.: 2

Client No.: PKP0915-A16 E Side 2nd Floor Storage Rm

% Non-Asbestos Fibrous Material % Non-Fibrous Material % Asbestos Type Type

None Detected None Detected None Detected None Detected 100

5746691 **Description / Location:** Yellow Mastic Lab No.:

PKP0915-A17 Client No.: Near Center Of Library

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected 5 Synthetic 95

White Texture 5746692 Lab No.: **Description / Location:** 

Client No.: PKP0915-A18 Damaged AreaWallAboveDoorNECornerLibrary

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

**Analytical Method:** US EPA 600/R-93/116 by Polarized Light Microscopy, (ELAP 198.1 where applicable)

Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing.

**Analysis Performed By:** R. McQuiggan

Date: 9/28/2015

**Comments:** 



PROJECT NO:	PROJECT NAME:	FACILITY:		COI	LECTION E:	
7395-01	Pitka's Point School Site Hazmat Survey   Teacher Housing Units 1				16/2015	
CHAIN OF CUSTODY RECORD						
ANALYSIS 🗵	PLM BULK PLM DUST TEM BU		TURNAROUND:	DISPOSAL:	QUANTITY	
REQUESTED:	LEAD DUST LEAD TCLP LEAD PI	PM SASBESTOS LEAD	5 DAY	NORMAL	38	
	TEM MICROVAC DUST (ASTM 5756)	CIAL INSTRUCTIONS / COM	IMENTS:			
	TATL					
Christopher Ottosen  SELECTED LABORATORY  LAB: RETURN A SIGNED COPY OF THIS FORM WITH  THE FINAL REPORT TO EHS-ALASKA, INC NOC NOC 1					VITH	
Christopher Ottose PRINTED NAME	SAMPLES ACCEPTED BY					
20110972/TBI24-11	1-146	O NOT ANALYZE FOA	M, PAINTS, OR	R WOOD**	Defected	
CERT# / AHERA#	b. Impropried 17	sample location drawing f	or more detailed	l explanation	of exact	
Fed Ex	locat	tions.	b) dha.			
SHIPPING METHOD	7571		K aveg-	19-15		
COURIER (signature) DATE/TIME	Ocam DATE 10	912416	Pin Sge	9/28/14	5	
	FIELD SURV	EY DATA	-			
EHS SAMPLE NO.  LAB ID NO	SAMPLE DESCRIPTION, (COLOR, MATERIAL TYPE, LAYERS, FRIABILITY)	LOCATION/CO (INCLUDING PR		FOR	RESULTS EHS-ALASKA USE ONLY	
PKPTH0915-A01	(HSV3) Hidden sheet vinyl, beige with	Teacher Housing Unit #	L – Hidden unde	No.		
5746693	brown flower pattern	newer sheet vinyl in Entr	ryway – Photo 1	08		
PKPTH0915-A02	(0)(1) (1) (1) (1) (1) (1)	T 1 TT ' TT ' II	(2),	, ,,,		
The second series where the second	(SV1) Sheet vinyl, white with blue specks and diamond/block pattern	Teacher Housing Unit #2 Photo 108	I – In Entryway	in – ND		
5746694	•		*			
PKPTH0915-A03	(SV1) Sheet vinyl, white with blue specks	Teacher Housing Unit #				
5746695	and diamond/block pattern	vinyl transition between  – Photo 109	Kitchen and Ha	llway		
PKPTH0915-A04	(HSV2) Hidden sheet vinyl, brown 1/8" chip	Teacher Housing Unit #			)	
rm40000	pattern; with tan mastic	newer sheet vinyl at carp				
5746696		transition between Kitch Photo 109	en and Hanway			
PKPTH0915-A05	(HSV1) Hidden sheet vinyl, yellow/brown	Teacher Housing Unit #1				
5746697	"alligator" pattern	newer sheet vinyl at carp transition between Kitch				
		Photo 109	en and Hanway.	_		
PKPTH0915-A06	(HSV1) Hidden sheet vinyl, yellow/brown	Teacher Housing Unit #1	– Hidden unde	r ND		
5746698	"alligator" pattern	carpet in Hallway at entr Photo 111	ance to Bathroon	m –		
PKPTH0915-A07	(SV2) Sheet vinyl, white with blue 4"x4"	Teacher Housing Unit #1	- At entrance i	nto ND		
5746699	square pattern and decorative blue and red flowers pattern	Bathroom – Photo 111				
PKPTH0915-A08	(SV2) Sheet vinyl, white with blue 4"x4"	Teacher Housing Unit #		nto NV		
5746700	square pattern and decorative blue and red flowers pattern	Boiler Room – Photo 112	2	•		



PROJECT NO:	PROJECT NAME:	FACILITY:	COLLECTION DATE:
7395-01	Pitka's Point School Site Hazmat Survey	Teacher Housing Units 1 & 2	09/16/2015
	FIELD SURV	VEY DATA	
EHS SAMPLE NO.  LAB ID NO	SAMPLE DESCRIPTION, (COLOR, MATERIAL TYPE, LAYERS, FRIABILITY)	LOCATION/COMMENTS (INCLUDING PHOTO/XREF)	RESULTS FOR EHS-ALASKA USE ONLY
PKPTH0915-A09 5746701	Off-white vinyl covered gypsum wall board; with yellow mastic, with off-white	Teacher Housing Unit #1 – On east wall of Kitchen – Photo 114	NDAII Layors
5746702	Off-white vinyl covered gypsum wall board; with yellow mastic	Teacher Housing Unit #1 – On east wall of Living Room – Photo 113	ND Both Laypes
PKPTH0915-A11 5746703	Dark brown mastic for glued-on ceiling tile (do not analyze particle board ceiling tile)	Teacher Housing Unit #1 – Loose on glued-on ceiling tile laying on floor near entrance in Bedroom 01 – Photo 115	ND
PKPTH0915-A12 5746704	Dark brown mastic for glued-on ceiling tile (do not analyze particle board ceiling tile)	Teacher Housing Unit #1 – From ceiling near south wall in Bedroom 03 – Photo 116	WD
PKPTH0915-A13 5746705	Dark brown mastic for glued-on ceiling tile (do not analyze particle board ceiling tile)	Teacher Housing Unit #1 – From ceiling near north wall in Bathroom – Photo 126	ND
PKPTH0915-A14 5746706	White gypsum wall board	Teacher Housing Unit #1 – From damaged area of east wall in Boiler Room – Photo 121	ND
PKPTH0915-A15 5746707	White joint compound	Teacher Housing Unit #1 – From damaged area of east wall in Boiler Room – Photo 117	ND
PKPTH0915-A16 5746708	White joint compound	Teacher Housing Unit #1 – From damaged area of north wall in Boiler Room – Photo 118	ND
PKPTH0915-A17 5746709	White joint compound	Teacher Housing Unit #1 – From damaged area of wall at northwest corner of Boiler Room – Photo 119	ND
5746710	Yellow mastic for "Marlite" wall panel	Teacher Housing Unit #1 – From north wall of Bathroom – Photo 127	ND
5746711	Dark brown 6" cove base; with off-white mastic	Teacher Housing Unit #1 – From base of shower enclosure in Bathroom – Photo 128	ND
PKPTH0915-A20 5746712	Black undercoating for stainless steel sink	Teacher Housing Unit #1 – On bottom of stainless steel sink in Kitchen – Photo 129	1.9% Chysotile
PKPTH0915-A21 5746713	Black 4" cove base; with off-white mastic	Teacher Housing Unit #1 – From base of cabinetry in Kitchen – Photo 130	MP Bith Largers 10%
PKPTH0915-A22 5746714	Grey gummy window glazing compound	Teacher Housing Unit #1 – From wood framed window on east wall of Living Room – Photo 156	10% Chasotile



PROJECT NO:	PROJECT NAME:	FACILITY:	COLLECTION DATE:
7395-01	Pitka's Point School Site Hazmat Survey	Teacher Housing Units 1 & 2	09/16/2015
	FIELD SURV	EY DATA	
EHS SAMPLE NO.  LAB ID NO	SAMPLE DESCRIPTION, (COLOR, MATERIAL TYPE, LAYERS, FRIABILITY)	LOCATION/COMMENTS (INCLUDING PHOTO/XREF)	RESULTS FOR EHS-ALASKA USE ONLY
PKPTH0915-A23 5746715	Hard white window glazing compound	Teacher Housing Unit #1 – From wood framed window on north wall of Bedroom 03 – Photo 157	ND
PKPTH0915-A24 5746716	(SV1) Sheet vinyl, white with blue specks and diamond/block pattern	Teacher Housing Unit #2 – From north side of Kitchen – Photo 221	M
PKPTH0915-A25 5746717	(SV3) Yellow with square and rectangles pattern	Teacher Housing Unit #2 – From entrance to Restroom – Photo 222	ND
PKPTH0915-A26 5746718	(SV3) Yellow with square and rectangles pattern	Teacher Housing Unit #2 – At damaged area of floor near center of Boiler Room – Photo 224	MD
PKPTH0915-A27 5746719	Hard white window glazing compound	Teacher Housing Unit #2 – From wood framed window on south side of Living Room – Photo 227	ND
PKPTH0915-A28 5746720	Grey gummy window glazing compound	Teacher Housing Unit #2 – From wood framed window on east side of Living Room – Photo 229	10% Chysotile
PKPTH0915-A29 5746721	Black undercoating for stainless steel sink	Teacher Housing Unit #2 – On bottom of stainless steel sink in Kitchen – Photo 230	1.5% Chrysofile
PKPTH0915-A30 5746722	Black 4" cove base; with off-white mastic	Teacher Housing Unit #2 – From base of cabinetry in Kitchen – Photo 231	ND Buth Layers
PKPTH0915-A31 5746723	Dark brown 4" cove base; with brown mastic	Teacher Housing Unit #2 – From base of wall next to door on south side of Bathroom – Photo 232	ND Boll Layers
PKPTH0915-A32 5746724	White joint compound	Teacher Housing Unit #2 – From damaged area of wall on east side of Boiler Room – Photo 233	ND
PKPTH0915-A33	White joint compound	Teacher Housing Unit #2 – From damaged area of wall at northeast corner of Boiler Room – Photo 234	ND
5746725 PKPTH0915-A34 5746726	White joint compound	Teacher Housing Unit #2 – From damaged area of wall at northwest corner of Boiler Room – Photo 235	NP
PKPTH0915-A35 5746727	White gypsum wall board	Teacher Housing Unit #2 – From damaged area of wall on east side of Boiler Room – Photo 236	NP
PKPTH0915-A36 5746728	Yellow mastic for "Marlite" wall panel (do not analyze "Marlite")	Teacher Housing Unit #2 – From west wall of Bathroom – Photo 238	M



PROJECT NO:	PROJECT NAME:	FACILITY:	COLLECTION DATE:
7395-01	Pitka's Point School Site Hazmat Survey	Teacher Housing Units 1 & 2	09/16/2015
	FIELD SURV	EY DATA	
EHS SAMPLE NO.  LAB ID NO	SAMPLE DESCRIPTION, (COLOR, MATERIAL TYPE, LAYERS, FRIABILITY)	LOCATION/COMMENTS (INCLUDING PHOTO/XREF)	RESULTS FOR EHS-ALASKA USE ONLY
PKPTH0915-A37 5746729	Off-white vinyl covered gypsum wall board; with yellow mastic	Teacher Housing Unit #2 – From east wall of Living Room – Photo 239	NDBoth Layers NDBoth Layers
PKPTH0915-A38 5746730	Off-white vinyl covered gypsum wall board; with yellow mastic	Teacher Housing Unit #2 – From east wall of Kitchen – Photo 240	ND Both Lazers
END	END	END	



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated **Report Date:** 9/28/2015

11901 Business Blvd., Ste 208

99577-7701 Teacher Housing Units 1&2 Eagle River AK **Project:** 

> **Project No.:** 7395-01

374724

Report No:

**BULK SAMPLE ANALYSIS SUMMARY** 

White Vinyl Sheet Flooring; Unit #1 Lab No .: 5746693 **Description / Location:** 

Client No.: PKPTH0915-A01 HiddenUnderNewerSheetVinylInEntryway

% Asbestos % Non-Asbestos Fibrous Material % Non-Fibrous Material Type Type

None Detected None Detected None Detected None Detected 100

Off-White Vinyl Sheet Flooring 5746694 Lab No.: **Description / Location:** 

Client No.: PKPTH0915-A02 Unit #1 In Entryway In

% Asbestos % Non-Asbestos Fibrous Material % Non-Fibrous Material Type Type

None Detected None Detected 20 Cellulose 70

> Fibrous Glass 10

Off-White Vinyl Sheet Flooring;Unit#1At Lab No .: 5746695 **Description / Location:** 

Client No.: PKPTH0915-A03 CarpetToSheetVinylTransitionBtwnKit&Hall

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

20 None Detected None Detected Cellulose

> Fibrous Glass 10

Off-White Vinyl Sheet Flooring;Unit#1 Lab No .: 5746696 **Description / Location:** 

Hidden Under Newer Sheet Vinyl At CarpetPKPTH0915-A04 Client No.:

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected 20 Cellulose

> Fibrous Glass 10

> > Approved By:

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

> This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory.


**Analytical Method:** US EPA 600/R-93/116 by Polarized Light Microscopy, (ELAP 198.1 where applicable)

Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not **Comments:** 

quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of

the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing.

S. Cone



Frank E. Ehrenfeld, III Laboratory Director

**Analysis Performed By:** 



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated Report Date: 9/28/2015

11901 Business Blvd., Ste 208

Eagle River AK 99577-7701 **Project:** Teacher Housing Units 1&2

**Project No.:** 7395-01

374724

Report No:

#### **BULK SAMPLE ANALYSIS SUMMARY**

Lab No.: 5746697 Description / Location: Tan Vinyl Sheet Flooring; Unit#1

Client No.: PKPTH0915-A05 HiddenUnderNewerSheetVinylAtCarpet

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected 100

Lab No.: 5746698 Description / Location: Tan Vinyl Sheet Flooring; Unit#1

Client No.: PKPTH0915-A06 HiddenUnderCarpetInHallwayAtEntToBathrm

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Lab No.: 5746699 Description / Location: Off-White Vinyl Sheet Flooring

Client No.: PKPTH0915-A07 Unit#1 At Entrance Into Bathrm

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected 20 Cellulose 70

10 Fibrous Glass

Lab No.: 5746700 Description / Location: Off-White Vinyl Sheet Flooring

Client No.: PKPTH0915-A08 Unit#1 At Entrance Into Boiler Rm

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected 20 Cellulose 70

10 Fibrous Glass

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method: US EPA 600/R-93/116 by Polarized Light Microscopy, (ELAP 198.1 where applicable)

Comments: Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not

quantification at <0.25% by volume is possible with this method. (PC) indicates strainled rount count wichou performed. (PC-1 race) means that assessos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing.

Analysis Performed By: S. Cone



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285 Local: 856-231-9449

% Non-Fibrous Material

95

Layer No.: 2

% Non-Fibrous Material

10

Layer No.: 3

100

ocal: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated Report Date: 9/28/2015

11901 Business Blvd., Ste 208

Eagle River AK 99577-7701 **Project:** Teacher Housing Units 1&2

**Project No.:** 7395-01

374724

#### **BULK SAMPLE ANALYSIS SUMMARY**

**Lab No.:** 5746701

**Description / Location:** Off-White Sheetrock

Client No.: PKPTH0915-A09

Unit#1 On East Wall Of Kitchen

% Asbestos Type

None Detected

Type

% Non-Asbestos Fibrous Material Type

5 Cellulose

Report No:

**Lab No.:** 5746701

None Detected

**Description / Location:** Off-White Wallpaper

Client No.: PKPTH0915-A09

Unit#1 On East Wall Of Kitchen

% Asbestos Type

% Non-Asbestos Fibrous Material Type

None Detected None Detected 90 Cellulose

**Lab No.:** 5746701

% Asbestos

**Description / Location:** Yellow Mastic

Unit#1 On East Wall Of Kitchen

Client No.: PKPTH0915-A09

% Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected

.....

Accreditation

NIST-NVLAP No. 101165-0

NY-DOH No. 11021

AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method:

US EPA 600/R-93/116 by Polarized Light Microscopy, (ELAP 198.1 where applicable)

Comments:

Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing.

Analysis Performed By: S. Cone



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285 Local: 856-231-9449

Fax: 856-231-9818

Client: EHS Alaska Incorporated Report Date: 9/28/2015

11901 Business Blvd., Ste 208

Eagle River AK 99577-7701 **Project:** Teacher Housing Units 1&2

**Project No.:** 7395-01

374724

Report No:

#### **BULK SAMPLE ANALYSIS SUMMARY**

Lab No.: 5746702 Description / Location: Off-White Sheetrock

Client No.: PKPTH0915-A10 Unit#1 On East Wall Of Living Rm

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected 5 Cellulose 90

5 Fibrous Glass

Lab No.:5746702Description / Location:Yellow MasticLayer No.:2

Client No.: PKPTH0915-A10 Unit#1 On East Wall Of Living Rm

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Lab No.: 5746703 Description / Location: Brown Mastic

Client No.: PKPTH0915-A11 Unit#1 LooseOnGlued-OnCeilingTile

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Lab No.: 5746704 Description / Location: Brown Mastic

Client No.: PKPTH0915-A12 Unit#1 FromCeilingNear S Wall In Bedrm03

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be repreduced greent in full, without written approval of the laboratory.

This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method: US EPA 600/R-93/116 by Polarized Light Microscopy, (ELAP 198.1 where applicable)

Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing.

Analysis Performed By: S. Cone

**Date:** 9/28/2015

**Comments:** 



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285 Local: 856-231-9449

Fax: 856-231-9818

Client: EHS Alaska Incorporated **Report Date:** 9/28/2015

11901 Business Blvd., Ste 208

99577-7701 Teacher Housing Units 1&2 Eagle River AK **Project:** 

> **Project No.:** 7395-01

374724

Report No:

#### **BULK SAMPLE ANALYSIS SUMMARY**

Brown Mastic

Lab No .: 5746705 **Description / Location:** 

Client No.: PKPTH0915-A13 Unit#1 FromCeilingNear N Wall In Bathrm

% Asbestos % Non-Asbestos Fibrous Material % Non-Fibrous Material Type Type

None Detected None Detected None Detected None Detected 100

White Sheetrock 5746706 Lab No.: **Description / Location:** 

Unit#1 FromDamagedAreaOfEWall InBoilerRm Client No.: PKPTH0915-A14

% Asbestos % Non-Asbestos Fibrous Material % Non-Fibrous Material Type Type

None Detected None Detected 5 Cellulose 90

Fibrous Glass

White Joint Compound Lab No .: 5746707 **Description / Location:** 

Client No.: PKPTH0915-A15 Unit#1 FromDamagedAreaOfEWall InBoilerRm

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

White Joint Compound Lab No .: 5746708 **Description / Location:** 

Unit#1 FromDamagedAreaOfNWall InBoilerRm PKPTH0915-A16 Client No.:

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

> This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory.

**Analytical Method:** US EPA 600/R-93/116 by Polarized Light Microscopy, (ELAP 198.1 where applicable)

**Comments:** 

Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing.

**Analysis Performed By:** S. Cone



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated Report Date: 9/28/2015

11901 Business Blvd., Ste 208

Eagle River AK 99577-7701 **Project:** Teacher Housing Units 1&2

**Project No.:** 7395-01

374724

Report No:

**BULK SAMPLE ANALYSIS SUMMARY** 

Lab No.: 5746709 Description / Location: White Joint Compound; Unit#1 From

Client No.: PKPTH0915-A17 DamagedAreaOfWall At NWCornerOfBoilerRm

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Lab No.: 5746710 Description / Location: Yellow Mastic

Client No.: PKPTH0915-A18 Unit #1 From N Wall Of Bathrm

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Lab No.: 5746711 Description / Location: Brown Cove Base;6"; Unit #1 From

Client No.: PKPTH0915-A19 Base Of Shower Enclosure In Bathrm

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Lab No.: 5746711 Description / Location: Yellow Mastic Layer No.: 2

Client No.: PKPTH0915-A19 Base Of Shower Enclosure In Bathrm

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be repreduced green in full, without written approved of the laboratory.

This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method: US EPA 600/R-93/116 by Polarized Light Microscopy, (ELAP 198.1 where applicable)

Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing.

Analysis Performed By: S. Cone

**Date:** 9/28/2015

**Comments:** 



% Asbestos

# CERTIFICATE OF ANALYSIS

9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

% Non-Fibrous Material

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated **Report Date:** 9/28/2015

11901 Business Blvd., Ste 208

Type

99577-7701 Teacher Housing Units 1&2 Eagle River AK **Project:** 

> **Project No.:** 7395-01

374724

Report No:

Type

#### **BULK SAMPLE ANALYSIS SUMMARY**

Black Mastic; Sink Undercoating Lab No .: 5746712 **Description / Location:** 

Client No.: PKPTH0915-A20 Unit#1;BottomOfStainlessSteelSinkInKit

% Asbestos % Non-Asbestos Fibrous Material % Non-Fibrous Material Type Type

PC 1.9 PC 98.1 Chrysotile None Detected None Detected

Black Cove Base;4" 5746713 Lab No.: **Description / Location:** 

Unit#1;Base Of Cabinetry In Kitchen Client No.: PKPTH0915-A21

% Non-Asbestos Fibrous Material None Detected None Detected None Detected None Detected 100

Yellow Mastic Lab No.: 5746713 **Description / Location:** Layer No.: 2

Unit#1;Base Of Cabinetry In Kitchen Client No.: PKPTH0915-A21

% Non-Asbestos Fibrous Material % Asbestos Type Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Grey Caulk; Unit #1 5746714 Lab No.: **Description / Location:** 

 $WoodFramed\ WindowOnEWallOfLivingRm$ Client No.: PKPTH0915-A22

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

Chrysotile None Detected None Detected 90

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

**Analytical Method:** US EPA 600/R-93/116 by Polarized Light Microscopy, (ELAP 198.1 where applicable)

> Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy

(TEM) is currently the only method that can pronounce materials as non-asbestos containing.

**Analysis Performed By:** S. Cone

Date: 9/28/2015

**Comments:** 



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285 Local: 856-231-9449

Fax: 856-231-9818

Client: EHS Alaska Incorporated **Report Date:** 9/28/2015

11901 Business Blvd., Ste 208

99577-7701 Teacher Housing Units 1&2 Eagle River AK **Project:** 

> **Project No.:** 7395-01

374724

#### **BULK SAMPLE ANALYSIS SUMMARY**

Lab No .: 5746715

**Description / Location:** 

White Caulk; Unit #1

WoodFramed WindowOnNWallOfBedrm03

% Asbestos

Client No.:

Type

PKPTH0915-A23

% Non-Asbestos Fibrous Material

Type

Report No:

% Non-Fibrous Material

None Detected

None Detected

None Detected

None Detected

100

Lab No.: Client No.: 5746716

**Description / Location:** 

Tan Vinyl Sheet Flooring

Unit #2 N Side Of Kitchen

% Asbestos

PKPTH0915-A24

% Non-Asbestos Fibrous Material

Type

% Non-Fibrous Material

Type None Detected

Cellulose

60

None Detected

30 10

Fibrous Glass

Lab No .:

5746717

**Description / Location:** 

Tan Vinyl Sheet Flooring

Client No.:

PKPTH0915-A25 Type

% Non-Asbestos Fibrous Material

Type

Unit #2 From Entrance To Restroom

% Non-Fibrous Material

% Asbestos None Detected

None Detected

None Detected

None Detected

Lab No .:

5746718

**Description / Location:** 

Tan Vinyl Sheet Flooring; Unit #2 At

Client No.:

PKPTH0915-A26

Damaged AreaOfFloorNearCenterOfBoilerRm

% Asbestos

Type

% Non-Asbestos Fibrous Material

Type

% Non-Fibrous Material

None Detected

None Detected

None Detected

None Detected

100

Accreditation

NIST-NVLAP No. 101165-0

NY-DOH No. 11021

AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory.

**Analytical Method:** 

US EPA 600/R-93/116 by Polarized Light Microscopy, (ELAP 198.1 where applicable)

**Comments:** 

Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing.

**Analysis Performed By:** 

S. Cone

Date:

9/28/2015



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285 Local: 856-231-9449

Fax: 856-231-9818

Client: EHS Alaska Incorporated Report Date: 9/28/2015

11901 Business Blvd., Ste 208

Eagle River AK 99577-7701 **Project:** Teacher Housing Units 1&2

**Project No.:** 7395-01

374724

#### **BULK SAMPLE ANALYSIS SUMMARY**

**Lab No.:** 5746719

.6719 **Description / Location:** 

White Glazing; Unit #2

Client No.: PKPTH0915-A27

WoodFramedWindowOnSSideOfLivingRm

Material Type

Type

Report No:

% Asbestos Type

% Non-Asbestos Fibrous Material

% Non-Fibrous Material

None Detected None Detected None Detected None Detected

Lab No.: 5746720 Description / Location: Grey Caulk; Unit #2, Wood Framed

Client No.: PKPTH0915-A28

WindowOnESideOfLivingRm

Type

% Asbestos

% Non-Asbestos Fibrous Material

% Non-Fibrous Material

100

10 Chrysotile None Detected None Detected 90

Lab No.: 5746721 Description / Location: Black Mastic; Unit #2, Bottom Of

Client No.: PKPTH0915-A29

Stainless Steel Sink In Kitchen

 % Asbestos
 Type
 % Non-Asbestos Fibrous Material
 Type
 % Non-Fibrous Material

PC 1.5 Chrysotile None Detected None Detected PC 98.5

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method:

US EPA 600/R-93/116 by Polarized Light Microscopy, (ELAP 198.1 where applicable)

Comments:

Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing.

Analysis Performed By: S. Cone



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated **Report Date:** 9/28/2015

11901 Business Blvd., Ste 208

99577-7701 Teacher Housing Units 1&2 Eagle River AK **Project:** 

> **Project No.:** 7395-01

374724

#### BULK SAMPLE ANALYSIS SUMMARY

Lab No .: 5746722

Client No.:

% Asbestos

PKPTH0915-A30

**Description / Location:** Black Cove Base

Unit #2, Base Of Cabinetry In Kitchen

Unit #2, Base Of Cabinetry In Kitchen

Report No:

% Asbestos % Non-Asbestos Fibrous Material Type

% Non-Fibrous Material Type

None Detected None Detected None Detected None Detected

Lab No .:

5746722

Type

**Description / Location:** 

Off-White Mastic

Layer No.: 2

% Non-Fibrous Material

100

100

Client No.: PKPTH0915-A30

% Non-Asbestos Fibrous Material

Type

None Detected None Detected None Detected None Detected

Lab No.: 5746723

Client No.: PKPTH0915-A31 **Description / Location:** Brown Cove Base; Unit #2, Base

Of WallNextToDoorOnSSideOfBathrm

% Asbestos Type

% Non-Asbestos Fibrous Material

Type

% Non-Fibrous Material 100

None Detected None Detected None Detected None Detected

Lab No.:

5746723

**Description / Location:** 

Brown Mastic

Layer No.: 2

Client No.:

PKPTH0915-A31

Of WallNextToDoorOnSSideOfBathrm

% Asbestos

Type

% Non-Asbestos Fibrous Material

Type

% Non-Fibrous Material

None Detected

None Detected

None Detected None Detected 100

Accreditation

#### NIST-NVLAP No. 101165-0

#### NY-DOH No. 11021

#### AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory.

**Analytical Method:** 

US EPA 600/R-93/116 by Polarized Light Microscopy, (ELAP 198.1 where applicable)

**Comments:** 

Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing.

**Analysis Performed By:** S. Cone



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285 Local: 856-231-9449

Fax: 856-231-9818

Client: EHS Alaska Incorporated **Report Date:** 9/28/2015

11901 Business Blvd., Ste 208

99577-7701 Teacher Housing Units 1&2 Eagle River AK **Project:** 

> **Project No.:** 7395-01

374724

Report No:

#### **BULK SAMPLE ANALYSIS SUMMARY**

White Joint Compound; Unit #2, Damaged Lab No .: 5746724 **Description / Location:** 

Client No.: PKPTH0915-A32 Area Of Wall On E Side Of Boiler Rm

% Asbestos % Non-Asbestos Fibrous Material Type % Non-Fibrous Material Type

None Detected None Detected None Detected None Detected 100

White Joint Compound; Unit #2, Damaged 5746725 Lab No.: **Description / Location:** 

Area Of Wall On NE Corner Of Boiler Rm Client No.: PKPTH0915-A33

% Asbestos % Non-Asbestos Fibrous Material % Non-Fibrous Material Type Type

None Detected None Detected None Detected None Detected 100

White Joint Compound; Unit #2, Damaged Lab No .: 5746726 **Description / Location:** 

Client No.: PKPTH0915-A34 Area Of Wall On NW Corner Of Boiler Rm

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected

White Sheetrock; Unit #2, Damaged Lab No .: 5746727 **Description / Location:** 

PKPTH0915-A35 Area Of Wall On E Side Of Boiler Rm Client No.:

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected Cellulose

> Fibrous Glass 5

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

**Analytical Method:** US EPA 600/R-93/116 by Polarized Light Microscopy, (ELAP 198.1 where applicable)

Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not **Comments:** quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of

the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing.

**Analysis Performed By:** S. Cone



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated **Report Date:** 9/28/2015

11901 Business Blvd., Ste 208

99577-7701 Teacher Housing Units 1&2 Eagle River AK **Project:** 

> **Project No.:** 7395-01

374724

Report No:

#### **BULK SAMPLE ANALYSIS SUMMARY**

Lab No .: 5746728

None Detected

**Description / Location:** 

Yellow Mastic

Client No.: PKPTH0915-A36 Unit #2 W Wall Of Bathrm

% Asbestos Type

None Detected

% Non-Asbestos Fibrous Material Type % Non-Fibrous Material 100

None Detected None Detected

White Sheetrock 5746729 Lab No.: **Description / Location:** 

Client No.: PKPTH0915-A37

Unit #2 E Wall Of Living Rm

% Asbestos % Non-Asbestos Fibrous Material Type

% Non-Fibrous Material Type

None Detected None Detected 5 Cellulose 5

Fibrous Glass

Lab No.: 5746729 **Description / Location:** 

Yellow Mastic

Layer No.: 2

% Non-Fibrous Material

100

90

Client No.: PKPTH0915-A37 Unit #2 E Wall Of Living Rm

% Asbestos Type

% Non-Asbestos Fibrous Material Type

None Detected None Detected None Detected None Detected

Accreditation

NIST-NVLAP No. 101165-0

NY-DOH No. 11021

AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory.

**Analytical Method:** 

US EPA 600/R-93/116 by Polarized Light Microscopy, (ELAP 198.1 where applicable)

**Comments:** 

Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing.

Analysis Performed By:	S. Cone
------------------------	---------



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285 Local: 856-231-9449

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated Report Date: 9/28/2015

11901 Business Blvd., Ste 208

Eagle River AK 99577-7701 **Project:** Teacher Housing Units 1&2

**Project No.:** 7395-01

374724

Report No:

#### **BULK SAMPLE ANALYSIS SUMMARY**

Lab No.: 5746730 Description / Location: White Sheetrock

Client No.: PKPTH0915-A38 Unit #2 E Wall Of Kitchen

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected 5 Cellulose 90

5 Fibrous Glass

Lab No.: 5746730 Description / Location: Yellow Mastic Layer No.: 2

Client No.: PKPTH0915-A38 Unit #2 E Wall Of Kitchen

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0

NY-DOH No. 11021

AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method:

US EPA 600/R-93/116 by Polarized Light Microscopy, (ELAP 198.1 where applicable)

Comments:

Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing.

Analysis Performed By: S. Cone

# RECEIVED



EHS-Alaska, Inc.

11901 Business Blvd., Suite 208, Eagle River, AK 99577 (907) 694-1383 • (907) 694-1382 fax

e-mail • ehsak@ehs-alaska.com

PROJECT NO: 7032-01	PROJECT NA Pitkas Po	ME: int School Renova	ıtion		ACILITY: Pitkas Point School		1	COLLECTION DATE:
		CHAII	OF CU	USTO	DY RECORD			
ANALYSIS X	PLM BULK	PLM DUST	Птем	M BULK	TYPE:	TURNAROUND:	DISPOSAL:	QUANTITY
REQUESTED:	LEAD DUST		LEA	AD PPM		2 DAYS	NORMAI	69
MILL	LY T.			SPECIA	L INSTRUCTIONS / CO	MMENTS:		
COLLECTED BY (signature)  Martin J. Lindeke PRINTED NAME  10164.01.17 CERT# / AHERA#	IATL -	ATL ELECTED LABORATORY 2 7 2011  AMPLES ACCEPTED BY ATE/TIME		THE	RETURN A SIGNE FINAL REPORT TO mple location drawing ns.	EHS-ALASKA	A, INC.	
FedEx SHIPPING METHOD 7950 (007) COURIER (signature) 7-2 (1) (2)	5899 _	NALYST'S SIGNATURE  US  PATE  7/3/11		fw. 1	20 8/2/11 27/287/1	ND =		ECTED,
		F	IELD SU	URVE	Y DATA			

FIELD SURVEY DATA					
EHS SAMPLE NO.  LAB ID NO	SAMPLE DESCRIPTION, (COLOR, MATERIAL TYPE, LAYERS, FRIABILITY)	LOCATION/COMMENTS (INCLUDING PHOTO/XREF)	RESULTS FOR EHS-ALASKA USE ONLY		
PKP-0711-A01 1375884	Carpet mastic, brown	Special Ed classroom, northeast ceiling section	ИО		
PKP-0711-A02 1375885	Joint compound, white	Special Ed Classroom, west wall, mid span	ND		
PKP-0711-A03 4375886	Sink undercoating, white	Special Ed classroom, south wall sink	4. 1 % chrysofile		
PKP-0711-A04 4375887	Cove base mastic, tan	Behind entry open door from corridor	ND		
PKP-0711-A05 4375888	Gypsum wall board, white	Corridor wall outside special education classroom	ИД		
PKP-0711-A06 4375889	Carpet mastic, tan	Northeast classroom, center of floor	ND		
PKP-0711-A07 4375890	Joint compound, white	Northeast classroom, North wall, below window	ND		
PKP-0711-A08 4375891	Joint compound, white	Inside wall of classroom at doorway from corridor	ИО		
PKP-0711-A09 4375892	Joint compound, white	Northwest vestibule above bench	ND		

# RECEIVED

AUG 2 2 2011



EHS-Alaska, Inc.

PROJECT NO:	PROJECT NAME:	FACILITY:	COLLECTION DATE:	
7032-01	Pitkas Point School Renovation Pitkas Point School		07/18/11	
*	FIELD SURV	VEY DATA		
EHS SAMPLE NO.  LAB ID NO	SAMPLE DESCRIPTION, (COLOR, MATERIAL TYPE, LAYERS, FRIABILITY)	LOCATION/COMMENTS (INCLUDING PHOTO/XREF)	RESULTS FOR EHS-ALASKA USE ONLY	
PKP-0711-A10 4375893	Sink undercoating, white	Northeast wing of building, south classroom, sink at west wall	3.8 % chrysotile	
PKP-0711-A11 4375894	Cove base mastic, yellow and joint compound, white	Partition wall at end of counter in northeast section, south classroom.	Mastic: NO	
PKP-0711-A12 4375895	Cove base, brown	Partition wall at end of counter in northeast section, south classroom	ИО	
PKP-0711-A13 4375896	Joint compound, white	south wall in north east section of building, south classroom	NO	
PKP-0711-A14 4375897	Sheet vinyl and mastic, SV-1 tan with brown swirls	Faculty bathroom	SV: ND MASTIC: ND	
PKP-0711-A15	Tile grout, tan granular	Faculty bathroom, east wall	ND	
PKP-0711-A16 4375899	Door frame sealant, brown	Doorway frame in faculty bathroom	ND	
PKP-0711-A17 4375900	Joint compound, white	Corridor wall at base of stairs to library	ND	
PKP-0711-A18 4375901	Carpet mastic, yellow	Edge of carpet at doorway to gymnasium	Cement: ND Mastic: ND	
PKP-0711-A19 4375902	Joint compound, white	Corridor wall outside janitor closet	ND	
PKP-0711-A20 4375903	Sheet vinyl and mastic, SV-2 grey pebble mosaic	Edge of floor in janitor closet	SV: 40 %	
PKP-0711-A21 4375904	Floor tile and mastic, FT-1 12x12 white w/ grey streaks	Edge of corridor flooring at doorway to janitor closet	TILE: 1.6 % BLK: 3.2 % YELLOW: ND	
PKP-0711-A22 4375905	Joint compound white	Corridor wall outside storage area, south west section of building, north end, north wall of corridor	ND	
PKP-0711-A23 4375906	Joint compound, white	Soffit across from principal's office door, entry area to south west classroom	ND	



PROJECT NO:	PROJECT NAME:	FACILITY:	COLLECTION DATE:	
7032-01	Pitkas Point School Renovation	Pitkas Point School	07/18/11	
	FIELD SURV	EY DATA		
EHS SAMPLE NO.  LAB ID NO	SAMPLE DESCRIPTION, (COLOR, MATERIAL TYPE, LAYERS, FRIABILITY)	LOCATION/COMMENTS (INCLUDING PHOTO/XREF)	RESULTS FOR EHS-ALASKA USE ONLY	
PKP-0711-A24 4375907	Cove base, brown	South wall of south west classroom, under radiator	ND	
PKP-0711-A25 4375908	Cove base mastic, brown and yellow	South wall of south west classroom, under radiator	BR: ND YEUW: ND	
PKP-0711-A26	Joint compound white	North wall of south west classroom below light switch	ND	
PKP-0711-A27 4375910	Window glazing, grey	West wall of south west classroom	8.9 % chrysotile	
PKP-0711-A28 4375911	Floor tile and mastic, FT-1	Floor tile section in classroom outside kitchen area.	TILE: 1.7 %	
PKP-0711-A29 4375912	Sink undercoating white	Kitchen area in south west classroom	3.9% chrysotile	
PKP-0711-A30 4375913	Marlite mastic, janitor's closet	South wall of janitor closet	ND	
PKP-0711-A31 4375914	Floor tile, 12x12 tan w/ light and dark streaks, with tan mastic	Gymnasium floor	TILE: ND	
PKP-0711-A32 4375915	Floor tile and mastic, FT-3 tan with light and dark streaks	Kitchen area under deep sink	TILE: ND	
PKP-0711-A33 4375916	Cove base, black and mastic, brown	Kitchen area at base of cabinet under deep sink	CB: ND	
PKP30711-A34 7	Marlite mastic, yellow	Back wall of kitchen area at doorway to classroom	ИО	
PKP-0711-A35 4375918	Wall carpet mastic, tan	Gymnasium wall under basketball net outside kitchen	MASTIC: ND	
PKP-0711-A36 4375919	Sheet vinyl and mastic, 8" square, cream and grey (SV-3)	Boys locker room entry floor.	SV: ND MASSIC: ND	
PKP-0711-A37 4375920	Sheet vinyl and mastic (SV-2)	Boys locker room entry floor, under SV-3	30 % chrysotile.	



EHS-Alaska, Inc.

11901 Business Blvd., Suite 208, Eagle River, AK 99577 (907) 694-1383 • (907) 694-1382 fax

e-mail • ehsak@ehs-alaska.com


PROJECT NO:	PROJECT NAME:	FACILITY:	COLLECTION DATE:	
7032-01	32-01 Pitkas Point School Renovation Pitkas Point School		07/18/11	
	FIELD SUR	VEY DATA		
EHS SAMPLE NO.  LAB ID NO	SAMPLE DESCRIPTION, (COLOR, MATERIAL TYPE, LAYERS, FRIABILITY)	LOCATION/COMMENTS (INCLUDING PHOTO/XREF)	RESULTS FOR EHS-ALASKA USE ONLY	
PKP-0711-A38 A375921	Cove Base mastic, brown	Gymnasium storage closet, back wall	ND	
PKP-0711-A39 4375922	Joint compound, white	Storage closet at diagonal ceiling corner	ND	
PKP-0711-A40 4375923	Sheet vinyl and mastic, pink white and grey confetti (SV-4)	Girls locker room floor	SV: ND MASTIC: ND	
PKP-0711-A41 4375924	Joint compound, white	South west section of school, north room (storage area) at corner wall inside doorway	ND	
PKP-0711-A42 4375925	Marlite mastic, yellow	Add on storage area at north end of south west section of building, west wall at damage area	ИВ	
PKP-0711-A43 4375926	Gypsum wall board, white	Add on storage area at north end of south west section of building, west wall at damage area	ИД	
PKP-0711-A44 4375927	Wall texture, white	First floor stair way landing next to faculty bathroom, east wall	ND	
PKP-0711-A45	Wall texture, white	Second floor, wall along second level stairway to library	NO	
4375928 PKP-0711-A46 4375929	Joint compound, white	Second floor, Corner wall at top of stairs in library	NO	
PKP-0711-A47 4375930	Carpet mastic, yellow	Second floor, floor at top of stairs from first floor in library	ND	
PKP-0711-A48 4375931	Wall texture, white	Second floor, Wall outside mechanical room in library	ND	
PKP-0711-A49 4375932	Joint compound and wall texture	Second floor, corner wall outside mechanical room in library	ND	
PKP-0711-A50 4375933	Stair tread, tan vinyl	First floor steps from kitchen to mechanical room	1.7% chrysotile	
PKP-0711-A51 4375934	Stair tread mastic	First floor steps from kitchen to mechanical room	ND	



# EHS, Alaska, Inc. 11901 Business Blvd., Suite 208, Eagle River, AK 99577

(907) 694-1383 • (907) 694-1382 fax e-mail • <u>ehsak@ehs-alaska.com</u>

PROJECT NO: 7032-01	PROJECT NAME: Pitkas Point School Renovation	FACILITY: Pitkas Point School	COLLECTION DATE: 07/18/11
4, 10	FIELD SURV	VEY DATA	
EHS SAMPLE NO.  LAB ID NO	SAMPLE DESCRIPTION, (COLOR, MATERIAL TYPE, LAYERS, FRIABILITY)	LOCATION/COMMENTS (INCLUDING PHOTO/XREF)	RESULTS FOR EHS-ALASKA USE ONLY
PKP-0711-A52 275935 PKP-0711-A53	Joint compound, white with tan paint	Second level, south wall of storage area at top of stairs from kitchen	ND
PKP-0711-A53 4375936	Joint compound, tan	Second level mechanical room at top of stairs from kitchen, above boiler	ND
PKP-0711-A54 4375937	Joint compound and wall texture, white	Second floor, inside office at north end of library, east wall	NO
PKP-0711-A54a 4375938	Joint compound and Wall texture, white	Second floor, outside wall of center office	ND
Mechanical Ca	bin		
PKP-0711-A55 4375939	Ceiling tile, 12x12, random dot and fissure, nailed on.	Shop building, north west corner room ceiling	NO
PKP-0711-A56 4375940	Joint compound, white	Shop building, north west corner room of building, at doorway	ND
PKP-0711-A57 4375941	Tarpaper, black	Edge of cabin roof at southwest corner of building	ND
PKP-0711-A58 4375942	Asphalt shingle, black with green granules	Edge of cabin roof at southwest corner of building	ND
PKP-0711-A59 4375943	Joint compound, white	Shop building, south west room, east wall	JC: NO
PKP-0711-A60 4375944	Floor tile, 12x12 clay color with light and dark streaks, and black mastic	Shop building floor of south west classroom	TILE: ND MASTIC: 3.1%
PKP-0711-A61 4375945	Floor tile and mastic, 12x12, clay color with light and dark streaks and tan mastic	Shop building floor at ski storage room	TILE: ND
PKP-0711-A62 4375946	Ceiling tile, 12x12 random dots and fissures, nailed on	Shop building, ski storeroom ceiling	ND
PKP-0711-A63 4375947	Furnace gasket, tan fiberboard	Shop building, boiler room at south end of building	ND
PKP-0711-A64 4375948	Gypsum wall board, white	Shop building at south end of building	ND



PROJECT NO:	PROJECT NAME:	FACILITY:	COLLECTION DATE:
7032-01	Pitkas Point School Renovation	Pitkas Point School	07/18/11
	FIELD SUF	RVEY DATA	
EHS SAMPLE NO.  LAB ID NO	SAMPLE DESCRIPTION, (COLOR, MATERIAL TYPE, LAYERS, FRIABILITY)	LOCATION/COMMENTS (INCLUDING PHOTO/XREF)	RESULTS FOR EHS-ALASKA USE ONLY
PKP-0711-A65 4375949	Joint compound, white	Shop building at south end of building	ND
PKP-0711-A66 4375950	Joint compound, white	Shop building, east wall of south room	JC: ND
PKP-0711-A67 4375951	Joint compound, white	Shop building, Partition wall between bathroom and ski store room	JC: ND
PKP-0711-A68 4375952	Fire door insulation, white	Shop building, Fire door at boiler room	Tr. Chrysotile Tr. Crocidalite 7.2 Amosit e
** End **			
	LS 7/301	7/	



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated Report Date: 7/30/2011

11901 Business Blvd., Ste 208

Eagle River AK 99577-7701 **Project:** Pitkas Point School

**Project No.:** 7032-01

247780

**BULK SAMPLE ANALYSIS SUMMARY** 

**Lab No.:** 4375884

Client No.: PKP-0711-A01

**Description / Location:** Brown Carpet Mastic

Special Ed Classroom, NE Ceiling Section

Report No:

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected Trace Cellulose 100

Lab No.: 4375885 Description / Location: White Joint Compound

Client No.: PKP-0711-A02

Special Ed Classroom, West Wall, Mid Span

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Lab No.: 4375886 Description / Location: Pink Mastic

Client No.: PKP-0711-A03

Special Ed Classroom, South Wall Sink

<u>% Asbestos Type</u> <u>% Non-Asbestos Fibrous Material Type</u> <u>% Non-Fibrous Material</u>

PC 4.1 Chrysotile None Detected None Detected PC 95.9

Lab No.: 4375887 Description / Location: Yellow Cove Base Mastic

Client No.: PKP-0711-A04 Behind Entry Open Door From Corridor

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC-Trace) represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable

layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based upon the sample matrix.

ased as a comming commune. Regulatory 2 min is oused upon the sample man.

L. Solebello Approved By:

Fal Frankl

Frank E. Ehrenfeld, III Laboratory Director

**Date:** 7/30/2011

**Analysis Performed By:** 



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated Report Date: 7/30/2011

11901 Business Blvd., Ste 208

Eagle River AK 99577-7701 **Project:** Pitkas Point School

**Project No.:** 7032-01

247780

Report No:

**BULK SAMPLE ANALYSIS SUMMARY** 

Lab No.: 4375888 Description / Location: Lt.Pink Sheetrock

Client No.: PKP-0711-A05 Corridor WallOutsideSpecialEduc.Classrm

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected 5 Fibrous Glass 95

 Lab No.:
 4375889
 Description / Location:
 Yellow Carpet Mastic

Client No.: PKP-0711-A06 NE Classroom, Center Of Floor

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Lab No.: 4375890 Description / Location: White Joint Compound

Client No.: PKP-0711-A07 NE Classroom, NorthWall,Below Window

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Lab No.:4375891Description / Location:White Joint Compound; Inside Wall

Client No.: PKP-0711-A08 Of Classroom At Doorway From Corridor

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

тых герон знан погое гертовисев ежерг игушт, минови мушен арргочагој иге шоогаоту.

Analytical Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC-Trace) represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be

used as a confirming technique. Regulatory Limit is based upon the sample matrix.

Analysis Performed By: L. Solebello

**Date:** 7/30/2011



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

100

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated **Report Date:** 7/30/2011

11901 Business Blvd., Ste 208

99577-7701 Pitkas Point School Eagle River AK **Project:** 

> **Project No.:** 7032-01

247780

Report No:

**BULK SAMPLE ANALYSIS SUMMARY** 

Lab No .: 4375892

White Joint Compound **Description / Location:** 

Client No.: PKP-0711-A09 Northwest Vestibule Above Bench

% Asbestos % Non-Asbestos Fibrous Material Type % Non-Fibrous Material Type

None Detected None Detected None Detected None Detected

Pink Mastic; NE Wing Of Building 4375893 Lab No.: **Description / Location:** 

PKP-0711-A10 South Classroom, Sink At West Wall Client No.:

% Asbestos % Non-Asbestos Fibrous Material % Non-Fibrous Material Type Type

PC 96.2 PC 3.8 Chrysotile None Detected None Detected

4375894 Yellow Cove Mastic; Partition Wall At Lab No .: **Description / Location:** 

Client No.: PKP-0711-A11 End Of Counter In NE Section, S. Classroom

% Non-Asbestos Fibrous Material % Asbestos Type Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected

White Joint Compuond 4375894 Lab No .: **Description / Location:** Layer No.: 2

Client No.: PKP-0711-A11 End Of Counter In NE Section, S. Classroom

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

> This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method: EPA 600/R-93/116

**Comments:** 

(PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC-Trace) represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based upon the sample matrix.

**Analysis Performed By:** L. Solebello

Date: 7/30/2011



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285 Local: 856-231-9449

Fax: 856-231-9818

Client: EHS Alaska Incorporated **Report Date:** 7/30/2011

11901 Business Blvd., Ste 208

99577-7701 Pitkas Point School Eagle River AK **Project:** 

> **Project No.:** 7032-01

247780

Report No:

**BULK SAMPLE ANALYSIS SUMMARY** 

Brown Cove Base; Partition Wall At Lab No .: 4375895 **Description / Location:** 

Client No.: PKP-0711-A12 End Of Counter In NE Section, S. Classroom

% Asbestos % Non-Asbestos Fibrous Material % Non-Fibrous Material Type Type

None Detected None Detected None Detected None Detected 100

White Joint Compound 4375896 Lab No.: **Description / Location:** 

PKP-0711-A13 S. Wall In NE SectionOf Bldg, S. Classroom Client No.:

% Asbestos % Non-Asbestos Fibrous Material % Non-Fibrous Material Type Type

None Detected None Detected None Detected None Detected 100

Lt. Tan Vinyl Sheet Flooring Lab No .: 4375897 **Description / Location:** 

Client No.: PKP-0711-A14 Faculty Bathroom

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected

Yellow Mastic 4375897 Lab No .: **Description / Location:** Layer No.: 2

Client No.: PKP-0711-A14 Faculty Bathroom

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

> This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method: EPA 600/R-93/116

> (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC-Trace) represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small

> asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based upon the sample matrix.

**Analysis Performed By:** L. Solebello

Date: 7/30/2011

**Comments:** 



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285 Local: 856-231-9449

100

% Non-Fibrous Material

Fax: 856-231-9818

Client: EHS Alaska Incorporated

11901 Business Blvd., Ste 208

99577-7701 Eagle River AK

**Report Date:** 7/30/2011

Pitkas Point School **Project:** 

247780

**Project No.:** 7032-01

Report No:

#### **BULK SAMPLE ANALYSIS SUMMARY**

4375898 Lab No .:

PKP-0711-A15

**Description / Location:** 

Tan Grout

Faculty Bathroom, East Wall

% Asbestos Type

% Non-Asbestos Fibrous Material

% Non-Fibrous Material Type

None Detected None Detected None Detected None Detected

Lab No.: Client No.:

% Asbestos

Client No.:

4375899

**Description / Location:** 

Brown Caulk

PKP-0711-A16 Doorway Frame In Faculty Bathroom

None Detected None Detected None Detected None Detected 100

% Non-Asbestos Fibrous Material

Lab No .: 4375900 **Description / Location:** 

Type

White Joint Compound

Client No.: PKP-0711-A17

Corridor Wall At Base OfStairsToLibrary

Type

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected 100 None Detected None Detected

Accreditation

**NIST-NVLAP No. 101165-0** 

NY-DOH No. 11021

AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method:

EPA 600/R-93/116

**Comments:** 

(PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC-Trace) represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based upon the sample matrix.

**Analysis Performed By:** L. Solebello

Date: 7/30/2011



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285 Local: 856-231-9449

Fax: 856-231-9818

Client: EHS Alaska Incorporated Report Date: 7/30/2011

11901 Business Blvd., Ste 208

Eagle River AK 99577-7701 **Project:** Pitkas Point School

**Project No.:** 7032-01

247780

Report No:

**BULK SAMPLE ANALYSIS SUMMARY** 

Lab No.: 4375901 Description / Location: White Cementitious

Client No.: PKP-0711-A18 Edge Of Carpet At Doorway To Gymnasium

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected 100

Lab No.:4375901Description / Location:Yellow MasticLayer No.:2

Client No.: PKP-0711-A18 Edge Of Carpet At Doorway To Gymnasium

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Lab No.: 4375902 Description / Location: White Joint Compound

Client No.: PKP-0711-A19 Corridor Wall Outside Janitor Closet

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC-Trace) represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be

used as a confirming technique. Regulatory Limit is based upon the sample matrix.

Analysis Performed By: L. Solebello

**Date:** 7/30/2011



Client No.:

**CERTIFICATE OF ANALYSIS** 

9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

Layer No.: 2

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated Report Date: 7/30/2011

11901 Business Blvd., Ste 208

Eagle River AK 99577-7701 **Project:** Pitkas Point School

**Project No.:** 7032-01

247780

Report No:

#### **BULK SAMPLE ANALYSIS SUMMARY**

Lab No.: 4375903 Description / Location:

Dk.Grey Vinyl Sheet Flooring

PKP-0711-A20 Edge Of Floor In Janitor Closet

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

40 Chrysotile Trace Cellulose 60

Lab No.: 4375903 Description / Location: Yellow Mastic

Client No.: PKP-0711-A20 Edge Of Floor In Janitor Closet

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

.....

Accreditation NIST-NVLAP No. 101165-0

NY-DOH No. 11021

AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

**Analytical Method:** 

EPA 600/R-93/116

**Comments:** 

(PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC-Trace) represents this limit of quantifation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based upon the sample matrix.

Analysis Performed By: L. Solebello

**Date:** 7/30/2011



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated **Report Date:** 7/30/2011

11901 Business Blvd., Ste 208

99577-7701 Eagle River AK

Report No: Pitkas Point School **Project:** 

247780

**Project No.:** 7032-01

## **BULK SAMPLE ANALYSIS SUMMARY**

Lab No .: 4375904

Client No.: PKP-0711-A21 **Description / Location:** 

Off-White Floor Tile; 12x12; Edge Of

Corridor Flooring At Doorway To Janitor Closet

% Asbestos Type

% Non-Asbestos Fibrous Material

Type

% Non-Fibrous Material

PC 1.6 Chrysotile None Detected

None Detected

PC 98.4

Lab No .:

4375904

**Description / Location:** 

Black Mastic

Layer No.: 2

Client No.:

PKP-0711-A21

% Non-Asbestos Fibrous Material

Corridor Flooring At Doorway To Janitor ClosetType

% Non-Fibrous Material

% Asbestos PC 3.2

Type Chrysotile

None Detected

None Detected

PC 96.8

Lab No.:

4375904

Yellow Mastic

Layer No.: 3

Client No.:

PKP-0711-A21

% Non-Asbestos Fibrous Material

Type

Corridor Flooring At Doorway To Janitor Closet

% Non-Fibrous Material

None Detected

% Asbestos

Type None Detected

None Detected

None Detected

100

Lab No .:

4375905

**Description / Location:** 

**Description / Location:** 

White Joint Compound; CorridorWall

Client No.: % Asbestos

PKP-0711-A22

% Non-Asbestos Fibrous Material

O/SStorageArea,SW SectionOfBldgN.End Type

% Non-Fibrous Material

None Detected

Type None Detected

None Detected

None Detected

100

Accreditation

**NIST-NVLAP No. 101165-0** 

NY-DOH No. 11021

AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method:

EPA 600/R-93/116

**Comments:** 

(PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC-Trace) represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based upon the sample matrix.

**Analysis Performed By:** 

L. Solebello

Date:

7/30/2011



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated **Report Date:** 7/30/2011

11901 Business Blvd., Ste 208

99577-7701 Pitkas Point School Eagle River AK **Project:** 

> **Project No.:** 7032-01

247780

Report No:

**BULK SAMPLE ANALYSIS SUMMARY** 

White Joint Compound; Soffit Across From Lab No .: 4375906 **Description / Location:** 

Client No.: PKP-0711-A23 Principal'sOfficeDoorEntryAreaToSWClass

% Asbestos % Non-Asbestos Fibrous Material % Non-Fibrous Material Type Type

100 None Detected None Detected None Detected None Detected

Brown Cove Base 4375907 Lab No.: **Description / Location:** 

PKP-0711-A24 S.WallOf SW Classroom, Under Radiator Client No.:

% Asbestos % Non-Asbestos Fibrous Material % Non-Fibrous Material Type Type

None Detected None Detected None Detected None Detected 100

4375908 Brown Cove Base Mastic Lab No .: **Description / Location:** 

Client No.: PKP-0711-A25 S.WallOf SW Classroom, Under Radiator

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected

Yellow Mastic 4375908 Lab No .: **Description / Location:** Layer No.: 2

Client No.: PKP-0711-A25 S. WallOf SW Classroom, Under Radiator

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

> This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method:

EPA 600/R-93/116

(PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC-Trace) **Comments:** represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based upon the sample matrix.

**Analysis Performed By:** L. Solebello



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated Report Date: 7/30/2011

11901 Business Blvd., Ste 208

Eagle River AK 99577-7701 **Project:** Pitkas Point School

**Project No.:** 7032-01

247780

Report No:

**BULK SAMPLE ANALYSIS SUMMARY** 

Lab No.: 4375909 Description / Location: White Joint Compound

Client No.: PKP-0711-A26 N.Wall Of SW Classroom, BelowLightSwitch

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Lab No.: 4375910 Description / Location: Grey Putty

Client No.: PKP-0711-A27 W.Wall Of SW Classroom

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

PC 8.9 Chrysotile None Detected None Detected PC 91.1

Lab No.: 4375911 Description / Location: Off-White Floor Tile; FloorTileSection

Client No.: PKP-0711-A28 In Classroom Outside Kitchen Area

ment No.: PRP-0/11-A28 in Classroom Outside Kitchen Area

<u>% Asbestos</u> <u>Type</u> <u>% Non-Asbestos Fibrous Material</u> <u>Type</u> <u>% Non-Fibrous Material</u>

PC 1.7 Chrysotile None Detected None Detected PC 98.3

Lab No.: 4375911 Description / Location: Black Mastic Layer No.: 2

Client No.: PKP-0711-A28 In Classroom Outside Kitchen Area

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

PC 1.9 Chrysotile None Detected None Detected PC 98.1

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC-Trace) represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable

represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based upon the sample matrix.

ased as a comming technique. Regulatory 2 min is caused upon the sample mans.

Analysis Performed By: L. Solebello



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated **Report Date:** 7/30/2011

11901 Business Blvd., Ste 208

Type

99577-7701 Pitkas Point School Eagle River AK **Project:** 

> **Project No.:** 7032-01

247780

Report No:

**BULK SAMPLE ANALYSIS SUMMARY** 

Lab No .: 4375912

% Asbestos

Pink Mastic; Sink Undercoating **Description / Location:** 

Kitchen Area In SW Classroom

Client No.: PKP-0711-A29

> % Non-Asbestos Fibrous Material Type

% Non-Fibrous Material PC 96.1

PC 3.9 Chrysotile None Detected None Detected

Yellow Marlite Mastic 4375913 Lab No.: **Description / Location:** 

PKP-0711-A30 South Wall In Janitor Closet Client No.:

% Asbestos % Non-Asbestos Fibrous Material % Non-Fibrous Material Type Type

None Detected None Detected None Detected None Detected 100

4375914 Tan Floor Tile; 12x12 Lab No .: **Description / Location:** 

Client No.: PKP-0711-A31 Gymnasium Floor

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected

4375914 Yellow Mastic Lab No .: **Description / Location:** Layer No.: 2

Client No.: PKP-0711-A31 Gymnasium Floor

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

> This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method: EPA 600/R-93/116

(PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC-Trace) **Comments:** represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable

layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based upon the sample matrix.

**Analysis Performed By:** L. Solebello



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated Report Date: 7/30/2011

11901 Business Blvd., Ste 208

Eagle River AK 99577-7701 **Project:** Pitkas Point School

**Project No.:** 7032-01

247780

Report No:

**BULK SAMPLE ANALYSIS SUMMARY** 

**Lab No.:** 4375915

PKP-0711-A32

None Detected

Type

**Description / Location:** Tan Floor Tile; 12x12

Kitchen Area Under Deep Sink

Kitchen Area Under Deep Sink

Type

% Asbestos Type

% Non-Asbestos Fibrous Material Type

None Detected None Detected

Lab No.:

% Asbestos

Lab No.:

Client No.:

None Detected

4375915

**Description / Location:** 

Yellow Mastic

Layer No.: 2

% Non-Fibrous Material

100

Client No.: PKP-0711-A32

% Non-Asbestos Fibrous Material

% Non-Fibrous Material

None Detected None Detected

None Detected

None Detected 100

Client No.: PKP-0711-A33

4375916

Description / Location: Black Cove Base; Kitchen Area

At Base Of Cabinet Under Deep Sink

% Asbestos Type

% Non-Asbestos Fibrous Material

Type

% Non-Fibrous Material

None Detected

None Detected

None Detected

None Detected

Lab No.:

4375916

**Description / Location:** 

Brown Mastic

Layer No.: 2

Client No.: % Asbestos

PKP-0711-A33

% Non-Asbestos Fibrous Material

% Non-Fibrous Material

None Detected

Type

None Detected

None Detected

Type

None Detected

At Base Of Cabinet Under Deep Sink

100

Accreditation

NIST-NVLAP No. 101165-0

NY-DOH No. 11021

AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

**Analytical Method:** 

EPA 600/R-93/116

Comments:

(PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC-Trace) represents this limit of quantifation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based upon the sample matrix.

**Analysis Performed By:** 

L. Solebello



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated **Report Date:** 7/30/2011

11901 Business Blvd., Ste 208

99577-7701 Eagle River AK **Project:** 

> **Project No.:** 7032-01

247780

Pitkas Point School

Report No:

**BULK SAMPLE ANALYSIS SUMMARY** 

4375917 Yellow Marlite Mastic; Back Wall Lab No .: **Description / Location:** 

Client No.: PKP-0711-A34 Of Kitchen Area At Doorway To Classroom

% Asbestos % Non-Asbestos Fibrous Material % Non-Fibrous Material Type Type

100 None Detected None Detected None Detected None Detected

Yellow Carpet Mastic; Gymnasium Wall 4375918 Lab No.: **Description / Location:** 

PKP-0711-A35 Under Basketball Net Outside Kitchen Client No.:

% Asbestos % Non-Asbestos Fibrous Material % Non-Fibrous Material Type Type

None Detected None Detected None Detected None Detected 100

White Joint Compound Lab No.: 4375918 **Description / Location:** Layer No.: 2

Under Basketball Net Outside Kitchen Client No.: PKP-0711-A35

% Asbestos % Non-Asbestos Fibrous Material Type Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation **NIST-NVLAP No. 101165-0** NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

> This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method: EPA 600/R-93/116

(PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC-Trace) **Comments:** represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable

layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be

used as a confirming technique. Regulatory Limit is based upon the sample matrix.

**Analysis Performed By:** L. Solebello



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated Report Date: 7/30/2011

11901 Business Blvd., Ste 208

Eagle River AK 99577-7701 **Project:** Pitkas Point School

**Project No.:** 7032-01

247780

Report No:

**BULK SAMPLE ANALYSIS SUMMARY** 

Lab No.: 4375919 Description / Location: Lt. Tan Vinyl Sheet Flooring

Client No.: PKP-0711-A36 Boys Locker Room Entry Floor

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected 15 Cellulose 80

5 Fibrous Glass

Lab No.: 4375919 Description / Location: Yellow Mastic Layer No.: 2

Client No.: PKP-0711-A36 Boys Locker Room Entry Floor

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Lab No.: 4375920 Description / Location: Dk.Grey Vinyl Sheet Flooring

Client No.: PKP-0711-A37 Boys Locker Room Entry Floor, UnderSV-3

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

30 Chrysotile Trace Cellulose 70

Lab No.: 4375921 Description / Location: Brown Cove Base Mastic

Client No.: PKP-0711-A38 Gymnasium Storage Closet, Back Wall

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC-Trace) represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be

used as a confirming technique. Regulatory Limit is based upon the sample matrix.

Analysis Performed By: L. Solebello



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

% Non-Fibrous Material

100

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated Report Date: 7/30/2011

11901 Business Blvd., Ste 208

Eagle River AK 99577-7701 **Project:** Pitkas Point School

**Project No.:** 7032-01

247780

**BULK SAMPLE ANALYSIS SUMMARY** 

**Lab No.:** 4375922

**Description / Location:** White Joint Compound

Client No.: PKP-0711-A39

Storage Closet At Diagonal CeilingCorner

Report No:

% Asbestos Type % Non-Asbestos Fibrous Material Type

None Detected None Detected None Detected None Detected

Lab No.: 4375923 Description / Location: Grey/Pink Vinyl Sheet Flooring

Client No.: PKP-0711-A40 Girls Locker Room Floor

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected 10 Cellulose 80

5 Fibrous Glass5 Synthetic

Lab No.: 4375923 Description / Location: Yellow Mastic Layer No.: 2

Client No.: PKP-0711-A40 Girls Locker Room Floor

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Lab No.: 4375924 Description / Location: Off-White Joint Compound; SW Section Of

Client No.: PKP-0711-A41 School,N.Room(StorageArea)AtCornerWall

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC-Trace) represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small

asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based upon the sample matrix.

ased as a comming termique. Regulatory 2 mile is oused upon the sample matrix

Analysis Performed By: L. Solebello



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285 Local: 856-231-9449

Fax: 856-231-9818

Client: EHS Alaska Incorporated Report Date: 7/30/2011

11901 Business Blvd., Ste 208

Eagle River AK 99577-7701

**Report No:** 247780

Pitkas Point School

**Project No.:** 7032-01

**Project:** 

**BULK SAMPLE ANALYSIS SUMMARY** 

Lab No.: 4375925 Description / Location: Yellow Mastic; Add On Storage Area At

Client No.: PKP-0711-A42 N.EndOfSWSectionOfBldgW.WallAtDamageArea

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected 100

Lab No.: 4375926 Description / Location: Off-White/TanSheetrockAddOnStorageAreaAt

Client No.: PKP-0711-A43 N.EndOfSWSectionOfBldgW.WallAtDamageArea

N.Endols wsecuololidag w. waliADalilageAlea

<u>% Asbestos</u> <u>Type</u> <u>% Non-Asbestos Fibrous Material</u> <u>Type</u> <u>% Non-Fibrous Material</u>

None Detected None Detected 5 Cellulose 95

Lab No.: 4375927 Description / Location: White Wall Texture; First Floor Stairway

Client No.: PKP-0711-A44 Landing Next To Faculty Bathroom, E.Wall

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Lab No.: 4375928 Description / Location: White Wall Texture; Second Floor

Client No.: PKP-0711-A45 Wall Along SecondLevelStairwayToLibrary

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC–Trace)

represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be

used as a confirming technique. Regulatory Limit is based upon the sample matrix.

Analysis Performed By: L. Solebello



Client No.:

% Asbestos

PKP-0711-A46

Type

**CERTIFICATE OF ANALYSIS** 

9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

% Non-Fibrous Material

100

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated Report Date: 7/30/2011

11901 Business Blvd., Ste 208

Eagle River AK 99577-7701 **Project:** Pitkas Point School

% Non-Asbestos Fibrous Material

**Project No.:** 7032-01

247780

Report No:

Type

**BULK SAMPLE ANALYSIS SUMMARY** 

Lab No.: 4375929 Description / Location: White Joint Compound; Second Floor

Corner Wall At Top Of Stairs In Library

None Detected None Detected None Detected None Detected

Lab No.:4375930Description / Location:Yellow Carpet Mastic; Second Floor

Client No.: PKP-0711-A47 Floor At TopOfStairsFromFirstInLibrary

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Lab No.: 4375931 Description / Location: White Wall Texture; Second Floor

Client No.: PKP-0711-A48 Wall Outside Mechanical Room In Library

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Lab No.: 4375932 Description / Location: White Wall Texture; Second Floor

Client No.: PKP-0711-A49 CornerWallOutside MechanicalRmInLibrary

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC–Trace)

represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be

used as a confirming technique. Regulatory Limit is based upon the sample matrix.

Analysis Performed By: L. Solebello



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated Report Date: 7/30/2011

11901 Business Blvd., Ste 208

Eagle River AK 99577-7701 **Project:** Pitkas Point School

**Project No.:** 7032-01

247780

Report No:

**BULK SAMPLE ANALYSIS SUMMARY** 

Lab No.: 4375933 Description / Location: Tan Stair Tread; First Floor

Client No.: PKP-0711-A50 Steps From Kitchen To Mechanical Rm

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

PC 1.7 Chrysotile None Detected None Detected PC 98.3

Lab No.: 4375934 Description / Location: Brown Mastic; First Floor

Client No.: PKP-0711-A51 Steps From Kitchen To Mechanical Rm

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Lab No.: 4375935 Description / Location: Off-White Joint Compound; SecondLevelS.

Client No.: PKP-0711-A52

Type

% Non-Asbestos Fibrous Material Type % Non-Fibrous Material

Wall Of Storage Area At Top Of Stairs From

None Detected None Detected None Detected None Detected 100

Lab No.: 4375936 Description / Location: Off-White Joint Compound; SecondLevelMech

Client No.: PKP-0711-A53 RmAtTopOfStairsFromKitchen,AboveBoiler

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

this report shan not be reproduced except in fair, without written approval by the taboratory.

Analytical Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC-Trace) represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be

used as a confirming technique. Regulatory Limit is based upon the sample matrix.

Analysis Performed By: L. Solebello

**Date:** 7/30/2011

% Asbestos



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

100

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated **Report Date:** 7/30/2011

11901 Business Blvd., Ste 208

99577-7701 Pitkas Point School Eagle River AK **Project:** 

> **Project No.:** 7032-01

247780

Report No:

White Joint Compound; Second Floor

**BULK SAMPLE ANALYSIS SUMMARY** 

Lab No .: 4375937

**Description / Location:** Client No.: PKP-0711-A54 Inside Office At N.EndOfLibrary, E.Wall

% Asbestos % Non-Asbestos Fibrous Material % Non-Fibrous Material Type Type

None Detected None Detected None Detected None Detected

White Wall Texture; Second Floor 4375938 Lab No.: **Description / Location:** 

PKP-0711-A54a Outside Wall Of Center Office Client No.:

% Asbestos % Non-Asbestos Fibrous Material % Non-Fibrous Material Type Type

None Detected None Detected None Detected None Detected 100

4375939 White/Tan Ceiling Tile; 12x12 Lab No .: **Description / Location:** 

Client No.: PKP-0711-A55 Mechanical Cabin; ShopBldg, NWC orner Rm

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

50 None Detected None Detected Cellulose

White Joint Compound; Mechanical Cabin Lab No .: 4375940 **Description / Location:** 

ShopBldg,NWCornerRm Of BldgAtDoorway PKP-0711-A56 Client No.:

% Asbestos Type % Non-Asbestos Fibrous Material % Non-Fibrous Material Type

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method: EPA 600/R-93/116

(PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC-Trace) **Comments:** 

represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be

used as a confirming technique. Regulatory Limit is based upon the sample matrix.

**Analysis Performed By:** L. Solebello



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated Report Date: 7/30/2011

11901 Business Blvd., Ste 208

Eagle River AK 99577-7701 **Project:** Pitkas Point School

**Project No.:** 7032-01

247780

Report No:

**BULK SAMPLE ANALYSIS SUMMARY** 

Lab No.: 4375941 Description / Location: Black Tar Paper; Mechanical Cabin

Client No.: PKP-0711-A57 Edge Of Cabin Roof At SW Corner Of Bldg

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected 60 Cellulose 40

Lab No.: 4375942 Description / Location: Green/Black Shingle;MechanicalCabin

Client No.: PKP-0711-A58 Edge Of Cabin Roof At SW Corner Of Bldg

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected 40 Cellulose 60

Lab No.: 4375943 Description / Location: White Joint Compound; Mechanical Cabin

Client No.: PKP-0711-A59 Shop Bldg, SW Room, East Wall

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Lab No.: 4375943 Description / Location: Off-White Joint Compound Layer No.: 2

Client No.: PKP-0711-A59 Shop Bldg, SW Room, East Wall

% AsbestosType% Non-Asbestos Fibrous MaterialType% Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC-Trace) represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable

represents this limit of quantitation. (PC-1 race) means that asbestos was detected but is not quantitable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based upon the sample matrix.

ased as a comming resimilate. Togatatory 2 mile is based upon the sample matrix

Analysis Performed By: L. Solebello



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

% Non-Fibrous Material

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated Report Date: 7/30/2011

11901 Business Blvd., Ste 208

Eagle River AK 99577-7701 **Project:** Pitkas Point School

**Project No.:** 7032-01

247780

Report No:

**BULK SAMPLE ANALYSIS SUMMARY** 

Lab No.:4375944Description / Location:Pink/Tan FloorTile;12x12;MechanicalCabin

Client No.: PKP-0711-A60 Shop Bldg Floor Of SW Classroom

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected Trace Cellulose 100

Lab No.:4375944Description / Location:Black/Yellow MasticLayer No.:2

Client No.: PKP-0711-A60 Shop Bldg Floor Of SW Classroom

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

PC 3.1 Chrysotile None Detected None Detected PC 96.9

Lab No.: 4375945 Description / Location: Pink/Tan FloorTile;12x12;MechanicalCabin

Client No.: PKP-0711-A61 Shop Bldg Floor At Ski Storage Room

% Asbestos Type % Non-Asbestos Fibrous Material Type

None Detected None Detected Trace Cellulose 100

Lab No.: 4375945 Description / Location: Yellow/Brown Mastic Layer No.: 2

Client No.: PKP-0711-A61 Shop Bldg Floor At Ski Storage Room

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC-Trace) represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small

asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based upon the sample matrix.

Analysis Performed By: L. Solebello



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated Report Date: 7/30/2011

11901 Business Blvd., Ste 208

Eagle River AK 99577-7701 **Project:** Pitkas Point School

**Project No.:** 7032-01

247780

Report No:

**BULK SAMPLE ANALYSIS SUMMARY** 

Lab No.: 4375946 Description / Location: White/TanCeiling Tile; 12x12; Mechanical

Client No.: PKP-0711-A62 Cabin; Shop Bldg, Ski Storeoom

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected 90 Cellulose 10

Lab No.: 4375947 Description / Location: Tan Gasket; Mechanical Cabin

Client No.: PKP-0711-A63 Shop Bldg,Boiler RoomAtS.EndOfBldg

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected 30 Cellulose 60

10 Fibrous Glass

Lab No.: 4375948 Description / Location: White/Tan Sheetrock; Mechanical Cabin

Client No.: PKP-0711-A64 Shop Bldg,At S.End Of Bldg

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected 10 Cellulose 90

Lab No.: 4375949 Description / Location: White Joint Compound; Mechanical Cabin

Client No.: PKP-0711-A65 Shop Bldg At S.End Of Bldg

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC-Trace)

represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be

used as a confirming technique. Regulatory Limit is based upon the sample matrix.

Analysis Performed By: L. Solebello



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285

Local: 856-231-9449 Fax: 856-231-9818

Client: EHS Alaska Incorporated Report Date: 7/30/2011

11901 Business Blvd., Ste 208

Eagle River AK 99577-7701 **Project:** Pitkas Point School

**Project No.:** 7032-01

247780

Report No:

**BULK SAMPLE ANALYSIS SUMMARY** 

Lab No.: 4375950 Description / Location: White Joint Compound; Mechanical Cabin

Client No.: PKP-0711-A66 Shop Bldg, East Wall Of South Room

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected 100

Lab No.:4375950Description / Location:Off-White Joint CompoundLayer No.:2

Client No.: PKP-0711-A66 Shop Bldg, East Wall Of South Room

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Lab No.: 4375951 Description / Location: White Joint Compound; Mechanical Cabin

Client No.: PKP-0711-A67 ShopBldgPartitionWallBtwnBathrm&SkiStore

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Lab No.: 4375951 Description / Location: Off-White Joint Compound Layer No.: 2

Client No.: PKP-0711-A67 ShopBldgPartitionWallBtwnBathrm&SkiStore

% Asbestos Type % Non-Asbestos Fibrous Material Type % Non-Fibrous Material

None Detected None Detected None Detected None Detected 100

Accreditation NIST-NVLAP No. 101165-0 NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government

This report shall not be reproduced except in full, without written approval of the laboratory.

Analytical Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC-Trace) represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable

layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be

used as a confirming technique. Regulatory Limit is based upon the sample matrix.

Analysis Performed By: L. Solebello



9000 Commerce Parkway, Ste B Mount Laurel, NJ 08054 Toll Free 877-428-4285 Local: 856-231-9449

Fax: 856-231-9818

**Client:** EHS Alaska Incorporated **Report Date:** 7/30/2011

11901 Business Blvd., Ste 208

Eagle River ΑK 99577-7701

**Project:** Pitkas Point School

247780

**Project No.:** 7032-01

Report No:

## **BULK SAMPLE ANALYSIS SUMMARY**

White Insulation; Mechanical Cabin Lab No .: 4375952 **Description / Location:** Client No.: PKP-0711-A68 Shop Bldg, Fire Door At Boiler Room

% Asbestos Type % Non-Asbestos Fibrous Material % Non-Fibrous Material Type

PC Trace None Detected None Detected PC 92.8 Chrysotile

PC Trace Crocidolite PC 7.2 Amosite

Accreditation **NIST-NVLAP No. 101165-0** NY-DOH No. 11021 AIHA-LAP, LLC No. 100188

> This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory.

**Analytical Method:** 

EPA 600/R-93/116

**Comments:** 

(PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. Quantification at <0.25% by volume is possible with this method. (PC-Trace) represents this limit of quantitation. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based upon the sample matrix.

**Analysis Performed By:** L. Solebello

## **APPENDIX B**

**Key Photos** 



Example of asbestos-containing sheet vinyl concealed under newer non-asbestos sheet vinyl and plywood in the Boy's Bathroom in the Main School Building.



Example of asbestos-containing wire insulation at a heat detector in the Janitor's Closet in the Main School Building.



Example of damaged asbestos-containing stair treads at stairway that leads from the Kitchen to the Mechanical Room in the Main School Building.



Typical stainless steel sink with asbestos-containing undercoating in the Main School Building.



Typical example of a thermostat with a mercury filled ampule in the Main School Building.



Damaged ceiling in the Main School Building Mechanical Room from active roof leaks above. Note bucket full of water that has overflowed causing more water damage.



Bucket full of water in Mechanical Room. Water has overflowed causing damage to the floor and adjacent walls. The wall to the left in the photo leads to the large classroom at the southeast corner of the Main School Building which has water damage from these leaks. The Kitchen is directly below where more water damage has occurred from these leaks.



Drip pan and white trash can in the background full of water in Mechanical Room in the Main School Building. These have overflowed and caused water damage to surrounding walls and floor. The source of the water appears to be from the roof leak above.



Close up of damaged wall above door leading to Kitchen in large classroom at southeast corner of Main School Building. Note the black mold and deteriorated gypsum board. The source of the water appears to be from the roof leak in the Mechanical Room above.



Damaged wall above door leading to Kitchen in large classroom at southeast corner of Main School Building. Note water staining and damaged gypsum board. The source of the water appears to be from the roof leak in the Mechanical Room above.



Example of damaged asbestos-containing floor tiles in the large classroom at the southeast corner of the Main School Building. Damage is caused by a combination of water damage, foot traffic, and abrasion from the doors being opened and closed.



Water damaged light fixture in Kitchen area in large classroom at the southeast corner of the Main School Building. The source of water appears to be from the leaking roof and overflowing catch buckets in the Mechanical Room above.



Standing water on countertop in Kitchen in the Main School Building. The source of the water appears to be from the roof leak in the Mechanical Room above.



Water leaking out of light fixture in Kitchen in the Main School Building. The source of the water appears to be from the roof leak in the Mechanical Room above.



Non-asbestos floor tile damaged by water leaks from above in Kitchen. The source of the water appears to be from the roof leak in the Mechanical Room above.



Daylight is visible through cracks at the wall/ceiling connection at the northeast corner of the Gym. Water has been intruding through these cracks causing damage to the ceiling, wall, and floor below.



Water damaged wall at northeast corner of Gym. Daylight is visible through cracks at the wall/ceiling connection.



Example of damaged asbestos-containing floor tiles at the northeast corner of the Gym in the Main School Building. Damage is caused by water leak from above.



Evidence of past leaking heat piping in classroom on north side of Main School Building. Note water droplets on pipe.



Further evidence of past leaking pipes in classroom on south side of Main School Building.



Small Mechanical Room in the 1984 addition. Note water stained floor and wall, and mineral build up on boiler flue. There did not appear to be an active leak at the time of inspection.



Asbestos-containing sink undercoating on Kitchen sink in Teacher Housing Unit 1. Teacher Housing Unit 2 similar.



Asbestos-containing window glazing compound on older window in Teacher Housing Unit 1. Teacher Housing Unit 2 similar.



Thermostat with mercury filled ampule in Teacher Housing Unit 1. Note mold on wood wall finish.



View of Living Room area in Teacher Housing Unit 1. Note extensive water damage and mold on virtually all surfaces.



View of Kitchen in Teacher Housing Unit 1. Note extensive water damage and mold on virtually all surfaces.



Typical bedroom in Teacher Housing Unit 1 with water damaged and moldy ceiling tiles and other surfaces.



Mushroom growing out of floor with mold on ceiling tile in a bedroom in Teacher Housing Unit 1.



Water damaged floors, walls, and ceiling with mold in a bedroom in Teacher Housing Unit 1. Note moisture on the inside face of the window glass.



Water damaged ceiling and walls with mold at boiler flue in Teacher Housing Unit 1.



Looking under sheet vinyl in Teacher Housing Unit 1. Note plywood subfloor saturated with water.



Thermostat with mercury filled ampule in Teacher Housing Unit 2.



PCB containing ballast in a fluorescent light fixture in the Kitchen in Teacher Housing Unit 2.



At first glance, Teacher Housing Unit 2 did not appear to have as extensive of a mold problem as Teacher Housing Unit 1. Closer examination revealed nearly the same level of fungal growth even though the ceiling tiles remained mostly intact.



Fungal growth on carpet, base trim, and wood paneling of cabinetry near the Kitchen in Teacher Housing Unit 2.



Fungal growth on plywood subfloor in Teacher Housing Unit 2. Note water saturated flooring materials and subfloor.



Fungal growth on cabinetry in Kitchen in Teacher Housing Unit 2.




Water damaged ceiling in a bedroom in Teacher Housing Unit 2. Note mold growth on ceiling tiles and walls.



Water damage and fungal growth on loose furniture in Teacher Housing Unit 2.



Condensation on boiler flue in Teacher Housing Unit 2. Note water damaged walls and ceiling and mold.



Boiler in Teacher Housing Unit 2. Note boiler drip pan is full of water, water damage to floors, walls, and ceiling, and the extensive mold growth.

## **APPENDIX C**

**Lead Analyzer Test Results** 

#### NITON XLp-300A, Serial No. 81530

No.	SITE	INSPECTOR	FLOOR	ROOM	COMPONENT	SUBSTRATE	CONDITION	COLOR	Duration	Time	Depth		Results	
NO.	3111	INSPECTOR	FLOOR	KOOWI	COMPONENT	SUBSTRATE	CONDITION	COLOR	Duration	Tillle	Index	LBP	mg/cm <sup>2</sup>	+/- ERROR
1	PITKAS POINT SCHOOL SITE	OTTOSEN	-	-	SHUTTER CAL	-	-	-	46.28	9/16/2015 19:18	-	-	5.8	0
2	TEACHER HOUSING UNIT #2	OTTOSEN	-	-	CALIBRATION CK	-	-	RED	21.12	9/16/2015 19:19	1.11	Positive	1.1	0.1
3	TEACHER HOUSING UNIT #2	OTTOSEN	-	-	CALIBRATION CK	-	-	RED	21.09	9/16/2015 19:20	2.77	Positive	1.2	0.1
4	TEACHER HOUSING UNIT #2	OTTOSEN	-	-	CALIBRATION CK	-	-	RED	21.1	9/16/2015 19:20	1.06	Positive	1	0.1
5	TEACHER HOUSING UNIT #2	OTTOSEN	FIRST	LIVING ROOM	WALL	WOOD	INTACT	WHITE	3.63	9/16/2015 19:21	1	Negative	0	0.02
6	TEACHER HOUSING UNIT #2	OTTOSEN	FIRST	KITCHEN	WALL	DRYWALL	INTACT	WHITE	3.6	9/16/2015 19:22	1	Negative	0.01	0.02
7	TEACHER HOUSING UNIT #2	OTTOSEN	FIRST	KITCHEN	COUNTERTOP	FORMICA	INTACT	YELLOW	3.63	9/16/2015 19:22	1	Negative	0.01	0.02
8	TEACHER HOUSING UNIT #2	OTTOSEN	FIRST	KITCHEN	CABINET	WOOD	INTACT	VARNISH	3.62	9/16/2015 19:23	1	Negative	0	0.02
9	TEACHER HOUSING UNIT #2	OTTOSEN	FIRST	HALLWAY	WALL	WOOD	INTACT	WHITE	4.22	9/16/2015 19:24	1	Negative	0	0.02
10	TEACHER HOUSING UNIT #2	OTTOSEN	FIRST	BATHROOM	FLOOR	VINYL	INTACT	YELLOW	6.02	9/16/2015 19:24	1	Negative	0	0.02
11	TEACHER HOUSING UNIT #2	OTTOSEN	FIRST	BATHROOM	WALL	MARLITE	INTACT	WHITE	4.81	9/16/2015 19:25	1	Negative	0	0.02
12	TEACHER HOUSING UNIT #2	OTTOSEN	FIRST	BATHROOM	COUNTERTOP	FORMICA	INTACT	WHITE	4.22	9/16/2015 19:25	1	Negative	0	0.02
13	TEACHER HOUSING UNIT #2	OTTOSEN	FIRST	BOILER ROOM	DOOR	METAL	INTACT	WHITE	3.64	9/16/2015 19:26	1	Negative	0	0.02
14	TEACHER HOUSING UNIT #2	OTTOSEN	FIRST	BOILER ROOM	BOILER	METAL	POOR	BLUE	7.86	9/16/2015 19:27	3.32	Negative	0.02	0.03
15	TEACHER HOUSING UNIT #2	OTTOSEN	FIRST	BEDROOM 03	BASEBOARD HEATER	METAL	INTACT	WHITE	5.43	9/16/2015 19:27	1	Negative	0	0.02
16	TEACHER HOUSING UNIT #2	OTTOSEN	FIRST	EXTERIOR	HANDRAIL	WOOD	POOR	BROWN	4.25	9/16/2015 19:29	1	Negative	0	0.02
17	TEACHER HOUSING UNIT #2	OTTOSEN	FIRST	EXTERIOR	SIDING	WOOD	POOR	BEIGE	3.63	9/16/2015 19:30	1	Negative	0	0.02
18	TEACHER HOUSING UNIT #2	OTTOSEN	FIRST	EXTERIOR	TRIM	WOOD	POOR	BROWN	4.23	9/16/2015 19:30	1	Negative	0	0.02
19	TEACHER HOUSING UNIT #2	OTTOSEN	FIRST	EXTERIOR	WINDOW TRIM	WOOD	POOR	BROWN	1.81	9/16/2015 19:31	1	Negative	0	0.02
20	TEACHER HOUSING UNIT #2	OTTOSEN	FIRST	EXTERIOR	SIDING	WOOD	POOR	BEIGE	3.62	9/16/2015 19:32	1	Negative	0	0.02
21	TEACHER HOUSING UNIT #1	OTTOSEN	FIRST	EXTERIOR	SIDING	WOOD	POOR	BEIGE	3.6	9/16/2015 19:34	1	Negative	0	0.02
22	TEACHER HOUSING UNIT #1	OTTOSEN	FIRST	EXTERIOR	TRIM	WOOD	POOR	BROWN	10.86	9/16/2015 19:35	1	Negative	0	0.02
23	TEACHER HOUSING UNIT #1	OTTOSEN	FIRST	EXTERIOR	HANDRAIL	WOOD	POOR	BROWN	3.59	9/16/2015 19:35	1	Negative	0	0.02
24	TEACHER HOUSING UNIT #1	OTTOSEN	FIRST	EXTERIOR	SIDING	WOOD	POOR	BEIGE	4.24	9/16/2015 19:36	1	Negative	0	0.02
25	TEACHER HOUSING UNIT #1	OTTOSEN	FIRST	ENTRY	DOOR	METAL	INTACT	WHITE	6.66	9/16/2015 19:37	1	Negative	0	0.02
26	TEACHER HOUSING UNIT #1	OTTOSEN	FIRST	ENTRY	DOOR TRIM	WOOD	INTACT	WHITE	4.22	9/16/2015 19:37	1	Negative	0	0.02
27	TEACHER HOUSING UNIT #1	OTTOSEN	FIRST	ENTRY	DOOR TRIM	WOOD	INTACT	WHITE	3.64	9/16/2015 19:37	1.2	Negative	0	0.02
28	TEACHER HOUSING UNIT #1	OTTOSEN	FIRST	LIVING ROOM	WALL	WOOD	INTACT	WHITE	3.02	9/16/2015 19:38	1	Negative	0	0.02
29	TEACHER HOUSING UNIT #1	OTTOSEN	FIRST	KITCHEN	WALL	DRYWALL	POOR	WHITE	3.03	9/16/2015 19:38	2.09	Negative	0.04	0.06
30	TEACHER HOUSING UNIT #1	OTTOSEN	FIRST	KITCHEN	WALL	DRYWALL	POOR	WHITE	3	9/16/2015 19:39	1	Negative	0	0.02
31	TEACHER HOUSING UNIT #1	OTTOSEN	FIRST	BATHROOM	COUNTERTOP	FORMICA	INTACT	YELLOW	3.61	9/16/2015 19:40	1	Negative	0	0.02
32	TEACHER HOUSING UNIT #1	OTTOSEN	FIRST	BATHROOM	SINK	CERAMIC	INTACT	WHITE	4.83	9/16/2015 19:41	1	Negative	0	0.02
33	TEACHER HOUSING UNIT #1	OTTOSEN	FIRST	BEDROOM 02	WALL	WOOD	INTACT	BROWN	2.41	9/16/2015 19:42	1	Negative	0	0.02
34	TEACHER HOUSING UNIT #1	OTTOSEN	FIRST	BEDROOM 03	WINDOW TRIM	WOOD	INTACT	VARNISH	4.82	9/16/2015 19:43	1	Negative	0	0.02
35	TEACHER HOUSING UNIT #1	OTTOSEN	FIRST	HALLWAY	WALL	WOOD	INTACT	WHITE	3.02	9/16/2015 19:43	1	Negative	0	0.02
36	PITKAS POINT MAIN SCHOOL	OTTOSEN	-	-	CALIBRATION CK	-	-	RED	26.51	9/16/2015 19:48	1.11	Positive	1.1	0.1
37 38	PITKAS POINT MAIN SCHOOL	OTTOSEN	-	-	CALIBRATION CK CALIBRATION CK	-		RED	21.07	9/16/2015 19:48	2.74	Positive	1.2	0.1
<b>38</b>	PITKAS POINT MAIN SCHOOL	OTTOSEN OTTOSEN	-	-		-	-	RED	<b>21.06</b> 48.2	9/16/2015 19:49	1.09	Positive	<b>1.1</b> 6.45	0.1
4 <b>0</b>	PITKAS POINT MAIN SCHOOL PITKAS POINT MAIN SCHOOL	OTTOSEN	-	-	SHUTTER CAL  CALIBRATION CK	-	-	RED	48.2 21.1	9/17/2015 12:07 9/17/2015 12:09	1.09	Positive	1.1	0 <b>0.1</b>
41	PITKAS POINT MAIN SCHOOL	OTTOSEN	-	-	CALIBRATION CK	-	-	RED	21.1	9/17/2015 12:09	2.48	Positive	1.1	0.1
42	PITKAS POINT MAIN SCHOOL	OTTOSEN	-	-	CALIBRATION CK	-	-	RED	21.07	9/17/2015 12:09	1.08	Positive	1.1	0.1
43	PITKAS POINT MAIN SCHOOL	OTTOSEN	SECOND	OFFICE	WALL	DRYWALL	INTACT	BLUE	3.6	9/17/2015 12:11	1.08	Negative	0	0.02
44	PITKAS POINT MAIN SCHOOL	OTTOSEN	SECOND	HALLWAY	WALL	DRYWALL	INTACT	BEIGE	3.6	9/17/2015 12:11	1	Negative	0	0.02
45	PITKAS POINT MAIN SCHOOL	OTTOSEN	SECOND	HALLWAY	WINDOW TRIM	WOOD	INTACT	BROWN	3.62	9/17/2015 12:12	1	Negative	0	0.02
46	PITKAS POINT MAIN SCHOOL	OTTOSEN	SECOND	HALLWAY	WINDOW SILL	WOOD	INTACT	BROWN	3.6	9/17/2015 12:12	1	Negative	0	0.02
47	PITKAS POINT MAIN SCHOOL	OTTOSEN	SECOND	HALLWAY	WINDOW CASING	WOOD	INTACT	BROWN	3.6	9/17/2015 12:13	1	Negative	0	0.02
48	PITKAS POINT MAIN SCHOOL	OTTOSEN	SECOND	SERVER	WINDOW CASING WINDOW TRIM	WOOD	INTACT	WHITE	3.02	9/17/2015 12:14	1	Negative	0	0.02
49	PITKAS POINT MAIN SCHOOL	OTTOSEN	SECOND	SERVER	WALL	DRYWALL	INTACT	WHITE	4.84	9/17/2015 12:14	1	Negative	0	0.02
50	PITKAS POINT MAIN SCHOOL	OTTOSEN	SECOND	SERVER	DOOR	WOOD	INTACT	WHITE	2.99	9/17/2015 12:14	1	Negative	0	0.02
51	PITKAS POINT MAIN SCHOOL	OTTOSEN	SECOND	SERVER	DOOR TRIM	WOOD	INTACT	WHITE	3.6	9/17/2015 12:15	1	Negative	0	0.02
52	PITKAS POINT MAIN SCHOOL	OTTOSEN	SECOND	LIBRARY	WALL	DRYWALL	INTACT	WHITE	5.4	9/17/2015 12:15	1	Negative	0	0.02
53	PITKAS POINT MAIN SCHOOL	OTTOSEN	SECOND	LIBRARY	DOOR	METAL	INTACT	BROWN	6.01	9/17/2015 12:16	1.31	Negative	0.01	0.02
54	PITKAS POINT MAIN SCHOOL	OTTOSEN	SECOND	LIBRARY	DOOR TRIM	METAL	INTACT	BROWN	4.21	9/17/2015 12:16	1.3	Negative	0.01	0.02
55	PITKAS POINT MAIN SCHOOL	OTTOSEN	SECOND	MECHANICAL	TANK	METAL	INTACT	BROWN	3.61	9/17/2015 12:17	3.73	Negative	0.01	0.03
56	PITKAS POINT MAIN SCHOOL	OTTOSEN	SECOND	STORAGE	WALL	DRYWALL	INTACT	BLUE	4.21	9/17/2015 12:23	1	Negative	0.01	0.02
י מכ										J,, 15 15 12.25				

	0.55									_	Depth		Results	
No.	SITE	INSPECTOR	FLOOR	ROOM	COMPONENT	SUBSTRATE	CONDITION	COLOR	Duration	Time	Index	LBP	mg/cm <sup>2</sup>	+/- ERROR
58	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	GYM	DOOR TRIM	METAL	INTACT	BROWN	3.6	9/17/2015 12:24	1	Negative	0	0.02
59	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	BOY'S BATHROOM	HAND DRYER	CERAMIC	INTACT	RED	3.63	9/17/2015 12:25	1.97	Positive	14.6	2.5
60	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	CLASSROOM	DOOR TRIM	METAL	INTACT	BROWN	3	9/17/2015 12:26	1	Negative	0	0.02
61	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	CLASSROOM	DOOR	METAL	INTACT	ORANGE	2.99	9/17/2015 12:27	1.93	Negative	0.6	0.2
62	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	VESTIBULE	DOOR	METAL	INTACT	BLUE	3.61	9/17/2015 12:27	1	Negative	0	0.02
63	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	CLASSROOM	DOOR TRIM	METAL	INTACT	BROWN	3.58	9/17/2015 12:27	1	Negative	0	0.02
64	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	CLASSROOM	WALL	MARLITE	INTACT	YELLOW	3.02	9/17/2015 12:28	3.21	Negative	0.02	0.06
65	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	CLASSROOM	WALL	DRYWALL	INTACT	WHITE	3	9/17/2015 12:28	3.21	Negative	0.01	0.04
66	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	KITCHEN	CABINET	FORMICA	INTACT	ORANGE	9.03	9/17/2015 12:30	1.14	Positive	1.2	0.1
67	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	HALLWAY	STAIR RISER	WOOD	INTACT	BROWN	3.03	9/17/2015 12:31	1	Negative	0	0.02
68	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	GYM	ROLLUP DOOR	METAL	INTACT	BROWN	3.6	9/17/2015 12:31	1	Negative	0	0.02
69	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	GYM	DOOR	METAL	INTACT	BROWN	4.21	9/17/2015 12:31	1	Negative	0	0.02
70	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	GYM	DOOR TRIM	METAL	INTACT	BROWN	3.62	9/17/2015 12:32	1.06	Negative	0	0.02
71	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	GYM	FLOD-UP TABLE	FORMICA	INTACT	ORANGE	3.62	9/17/2015 12:32	5.96	Negative	0.04	0.14
72	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	GYM	TRIM	WOOD	INTACT	BROWN	3.64	9/17/2015 12:33	3.6	Negative	0.02	0.05
73	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	HALLWAY	LOCKER	METAL	INTACT	BLUE	3.6	9/17/2015 12:34	10	Negative	-0.37	1.04
74	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	CLASSROOM	WALL	MARLITE	INTACT	WHITE	3.6	9/17/2015 12:34	1	Negative	0	0.02
75	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	CLASSROOM	WAINSCOT	WOOD	INTACT	WHITE	3.01	9/17/2015 12:35	1	Negative	0	0.02
76	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	CLASSROOM	WINDOW TRIM	WOOD	INTACT	BROWN	3.61	9/17/2015 12:35	1	Negative	0	0.02
77	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	CLASSROOM	WINDOW SILL	WOOD	POOR	WHITE	4.21	9/17/2015 12:36	1.72	Negative	0	0.02
78	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	CLASSROOM	WINDOW CASING	WOOD	POOR	WHITE	3.61	9/17/2015 12:36	1	Negative	0	0.02
79	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	EXTERIOR	HANDRAIL	WOOD	POOR	BROWN	4.22	9/17/2015 12:38	1.39	Negative	0.3	0.08
80	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	EXTERIOR	SIDING	WOOD	FAIR	GREY	3.61	9/17/2015 12:38	1	Negative	0	0.02
81	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	EXTERIOR	TRIM	WOOD	FAIR	GREY	3.62	9/17/2015 12:39	1	Negative	0	0.02
82	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	EXTERIOR	BEAM	METAL	FAIR	BROWN	3.6	9/17/2015 12:40	1	Negative	0	0.02
83	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	EXTERIOR	SUPPORT	METAL	INTACT	BROWN	4.23	9/17/2015 12:41	1.18	Negative	0	0.02
84	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	EXTERIOR	THERMOSIPHON	METAL	POOR	WHITE	3.03	9/17/2015 12:48	5.08	Negative	0.02	0.07
85	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	EXTERIOR	PILING	METAL	POOR	WHITE	3.61	9/17/2015 12:50	1	Negative	0	0.02
86	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	EXTERIOR	TRIM	WOOD	POOR	WHITE	3.02	9/17/2015 12:51	1	Negative	0	0.02
87	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	EXTERIOR	TANK	METAL	POOR	GREY	3.61	9/17/2015 12:51	2.93	Negative	0.07	0.1
88	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	EXTERIOR	STAIR RISER	METAL	POOR	RED	3.6	9/17/2015 12:52	1.17	Negative	0.03	0.04
89	PITKAS POINT MAIN SCHOOL	OTTOSEN	FIRST	EXTERIOR	HANDRAIL	METAL	POOR	RED	3.62	9/17/2015 12:52	1.32	Negative	0.03	0.04
90	PITKAS POINT MAIN SCHOOL	OTTOSEN	-	-	CALIBRATION CK	-	-	RED	21.02	9/17/2015 12:56	1.05	Positive	1	0.1
91	PITKAS POINT MAIN SCHOOL	OTTOSEN	-	-	CALIBRATION CK	-	-	RED	21.08	9/17/2015 12:57	2.74	Positive	1.2	0.1
92	PITKAS POINT MAIN SCHOOL	OTTOSEN	-	-	CALIBRATION CK	-	-	RED	21.11	9/17/2015 12:57	1.04	Positive	1	0.1

#### Table Heading Descriptions:

LBP:

Duration: This is the nominal time in seconds that each sample was analyzed.

Depth Index: Indicates the relative depth of the lead. A Depth Index (DI) of less than 1.5 indicates lead very near the surface layer of paint. A DI between 1.5 and 4.0 indicates moderately covered lead. A DI greater than 4.0 indicates the lead paint is deeply buried beneath multiple layers of paint.

Results are shown as positive (POS  $\geq$  1.0 mg/cm²), inconclusive (INC) or negative (NEG < 1.0 mg/cm²). The results are based on the combined results of the K and L shell readings. L shell and K shell readings are not provided, but are available. Positive results are shown in bold print.

mg/cm2: This is the testing results produced by the NITON XLp-300A instrument in milligrams of lead per square centimeter (mg/cm²). The EPA defines lead based paint as paint containing lead at 1.0 mg/cm² or greater. A negative number is a result of an internal computation made by the instrument and should be interpreted as zero. Even though paint may be termed negative (less than 1.0 mg/cm²) by EPA definition, disturbance of the paint may still be regulated by OSHA under 29 CFR 1926.62. Where lead is present at any level, appropriate engineering controls, work practices and personal protective equipment should be used until a negative exposure assessment can be determined. <LOD indicates that the lead present was less than the limits of detection of the instrument (very little or no lead present).

VOID: This indicates that the test was intentionally terminated by the operator due to operator error (e.g. - operator moved analyzer while testing).

Substrate: Where ceramic is shown as a substrate, lead content is typically from the glazing on the tile unless the tile is painted.

#### PITKAS POINT SCHOOL LEAD SCREENING SUMMARY

No.	SITE	INSPECTOR	FLOOR	ROOM	COMPONENT	SUBSTRATE	CONDITION	COLOR	Duration	Time	Depth Index		Results	;
NO.	SITE	INSPECTOR	FLOOR	ROOW	COMPONENT	SUBSTRATE	CONDITION	COLOR	Duration	Time	Depth index	LBP	mg/cm <sup>2</sup>	+/-Error
	PITKAS SCHOOL	LINDEKE							106.46	7/18/2011 7:15			4.23	0
	PITKAS SCHOOL	LINDEKE			CALIBRATION CK				20.76	7/18/2011 7:17	1.06	Positive	1	0.1
3	PITKAS SCHOOL	LINDEKE			CALIBRATION CK				20.45	7/18/2011 7:18	1.01	Positive	1	0.1
4	PITKAS SCHOOL	LINDEKE			CALIBRATION CK				22.3	7/18/2011 7:19	1.05	Positive	1	0.1
5	PITKAS SCHOOL	LINDEKE	FIRST	ENTRY	DOOR	METAL	INTACT	BROWN	20.46	7/18/2011 7:22	2.49	Negative	0	0.02
6	PITKAS SCHOOL	LINDEKE	FIRST	ENTRY	WALL	DRYWALL	INTACT	WHITE	20.41	7/18/2011 7:23	2.07	Negative	0	0.02
	PITKAS SCHOOL		FIRST	ENTRY	DOOR	METAL	INTACT	BLUE	20.42	7/18/2011 7:24	3.56	Negative	0.01	0.02
	PITKAS SCHOOL		FIRST	HALL	LOCKER	METAL	INTACT	BLUE	20.09	7/18/2011 7:26	10	Negative	0.04	0.36
	PITKAS SCHOOL		FIRST	HALL	WALL	DRYWALL	INTACT	WHITE	20.72	7/18/2011 7:27	3.07	Negative	0.01	0.02
	PITKAS SCHOOL		FIRST	HALL	FLOOR	CERAMIC	INTACT	BEIGE	21.33	7/18/2011 7:29	2.98	Negative	0.01	0.02
	PITKAS SCHOOL		FIRST	BATHROOM	WALL	CERAMIC	INTACT	BEIGE	20.38	7/18/2011 7:30	2.14	Negative	0.01	0.02
	PITKAS SCHOOL	LINDEKE	FIRST	HALL	DOOR TRIM	METAL	INTACT	BROWN	20.35	7/18/2011 7:32	1	Negative	0	0.02
13	PITKAS SCHOOL		FIRST	CLASSROOM	WINDOW CASING	WOOD	INTACT	BROWN	20.39	7/18/2011 7:34	2.15	Negative	0	0.02
	PITKAS SCHOOL		FIRST	CLASSROOM	CABINET	PLASTIC	INTACT	BROWN	20.42	7/18/2011 7:35	1.07	Negative	0.08	0.02
	PITKAS SCHOOL		FIRST	CLASSROOM	WALL	DRYWALL	INTACT	WHITE	8.04	7/18/2011 7:37	2.02	Negative	0	0.02
	PITKAS SCHOOL		FIRST	CLASSROOM	WALL	DRYWALL	INTACT	WHITE	20.36	7/18/2011 7:38	2.83	Negative	0	0.02
	PITKAS SCHOOL		FIRST	GYM	DOOR	METAL	INTACT	ORANGE	20.73	7/18/2011 7:40	1.77	Negative	0.5	0.1
	PITKAS SCHOOL		FIRST	BATHROOM	WALL	WOOD	INTACT	WHITE	20.74	7/18/2011 7:41	3.34	Negative	0.01	0.02
	PITKAS SCHOOL		FIRST	BATHROOM	WALL	METAL	INTACT	ORANGE	21.03	7/18/2011 7:42	1.07	Negative	0.29	0.03
	PITKAS SCHOOL		FIRST	BATHROOM	SINK	CERAMIC	INTACT	WHITE	20.38	7/18/2011 7:44	2.97	Negative	0.05	0.03
			FIRST	JANITOR CLOSET	SINK		INTACT	WHITE	21.04	7/18/2011 7:46	1.97	Positive		1.2
			FIRST	HALL	DOOR	METAL	INTACT	GRAY	20.44	7/18/2011 7:47	5.78	Negative	0.01	0.02
	PITKAS SCHOOL		FIRST	CLASSROOM	RADIATOR	METAL	INTACT	WHITE	20.34	7/18/2011 7:50	1.58	Negative	0.06	0.02
	PITKAS SCHOOL		FIRST	CLASSROOM	DOOR	METAL	INTACT	ORANGE	20.69	7/18/2011 7:52	1.62	Negative	0.4	0.1
			FIRST	KITCHEN	CABINET	PLASTIC	INTACT	ORANGE	20.68	7/18/2011 7:54	1.19	Positive	1.2	0.1
			FIRST	KITCHEN	PIPE	METAL	INTACT	BROWN	20.44	7/18/2011 7:56	1.4	Positive	3.3	0.4
	PITKAS SCHOOL		SECOND	ATTIC	DOOR	WOOD	INTACT	ORANGE	20.75	7/18/2011 7:58	1.14	Negative	0.4	0.1
	PITKAS SCHOOL		SECOND	ATTIC	PIPE	METAL	INTACT	BROWN	20.72	7/18/2011 7:59	1.5	Positive	3.2	0.4
			FIRST	EXTERIOR	EXT. WALL	WOOD	INTACT	GRAY	21.03	7/18/2011 8:02	4.03	Negative		0.02
			FIRST	EXTERIOR	HAND RAIL	WOOD	INTACT	BROWN	20.76	7/18/2011 8:04	1.72	Negative	0.6	0.1
	PITKAS SCHOOL	LINDEKE	TANK FARM	EXTERIOR	TANK		INTACT	WHITE	20.43	7/18/2011 8:14	4.42	Negative	0.07	0.04
	PITKAS SCHOOL	LINDEKE	TANK FARM	EXTERIOR	TANK	METAL	INTACT	WHITE	25.11	7/18/2011 8:15	6.47	Negative		0.06
	PITKAS SCHOOL	LINDEKE	TANK FARM	EXTERIOR	TANK	METAL	INTACT	WHITE	20.75	7/18/2011 8:16	2.15	Negative	0.01	0.02
	PITKAS SCHOOL	LINDEKE	TANK FARM	EXTERIOR	TANK	METAL	INTACT	BLUE	20.44	7/18/2011 8:17	1.77	Negative	0.07	0.02
	PITKAS SCHOOL	LINDEKE	TANK FARM	EXTERIOR	TANK	METAL	INTACT	BLUE	20.42	7/18/2011 8:19	1.36	Negative	0.01	0.02
	PITKAS SCHOOL		MAINT CABIN	UTILITY	WALL	WOOD	INTACT	BROWN	11.13	7/18/2011 9:26	1.19	Negative	0.11	0.03
	PITKAS SCHOOL		MAINT CABIN	UTILITY	WALL	WOOD	INTACT	BLUE	11.41	7/18/2011 9:27	2.49	Negative	0	0.02
	PITKAS SCHOOL		MAINT CABIN	UTILITY	WALL	DRYWALL	INTACT	WHITE	11.13	7/18/2011 10:01	1.64	Negative	0	0.02
	PITKAS SCHOOL		MAINT CABIN	UTILITY	DOOR	WOOD	INTACT	BROWN	10.81	7/18/2011 10:01	2.19	Negative	0	0.02
	PITKAS SCHOOL		MAINT CABIN	UTILITY	WALL	DRYWALL	INTACT	BLUE	13.55	7/18/2011 10:02	5.5	Negative		0.03
		LINDEKE			CALIBRATION CK				20.69	7/18/2011 10:23	1.07	Positive	1	0.1
		LINDEKE			CALIBRATION CK				20.39	7/18/2011 10:23	1.06	Positive	1	0.1
43	PITKAS SCHOOL	LINDEKE			CALIBRATION CK				21.63	7/18/2011 10:24	1.01	Positive	1	0.1

Table Heading Descriptions:

Duration: This is the nominal time in seconds that each sample was analyzed.

Depth Index: Indicates the relative depth of the lead. A Depth Index (DI) of less than 1.5 indicates lead very near the surface layer of paint. A DI between 1.5 and 4.0

indicates moderately covered lead. A DI greater than 4.0 indicates the lead paint is deeply buried beneath multiple layers of paint.

LBP: Results are shown as positive (POS > 1.0 mg/cm²), inconclusive (INC) or negative (NEG < 1.0 mg/cm²). The results are based on the combined results of the K and L shell readings. L shell and K shell readings are not provided, but are available upon request. Positive results are in bold print.

Pitkas Point School Page 1 of 2

#### PITKAS POINT SCHOOL LEAD SCREENING SUMMARY

mg/cm<sup>2</sup>:

This is the testing results produced by the NITON XLi-303AW instrument in milligrams of lead per square centimeter (mg/cm²). The EPA defines lead based paint as paint containing lead at 1.0 mg/cm² or greater. A negative number is a result of an internal computation made by the instrument and should be interpreted as zero. Even though paint may be termed negative (less than 1.0 mg/cm²) by EPA definition, disturbance of the paint may still be regulated by OSHA under 29 CFR 1926.62. Where lead is present at any level, appropriate engineering controls, work practices and personal protective equipment should be used until a negative exposure assessment can be determined.

VOID:

This indicates that the test was intentionally terminated by the operator due to operator error (e.g. - operator moved analyzer while testing).


Substrate:

Where ceramic is shown as a substrate, lead content is typically from the glazing on the tile unless the tile is painted.

Pitkas Point School

## **APPENDIX D**


**Drawings of Sample Locations** 





LOWER YUKON SCHOOL DISTRICT PITKAS POINT SCHOOL SITE PITKAS POINT, ALASKA SITE PLAN




DRAWN: CTO	DATE:
CHECK: RAF	09/16/2015
FILE #:	DWG.NO:









**LEGEND** LXX LEAD TEST LOCATION

LXX LEAD TEST CLASSIFIED AS LEAD BASED PAINT

REFER TO TESTING SUMMARY IN REPORT FOR FULL DETAILS.

**LOWER YUKON SCHOOL DISTRICT** 

PITKAS POINT SCHOOL SITE PITKAS POINT, ALASKA ASBESTOS & LEAD SAMPLE LOCATIONS

TEACHER HOUSING UNIT #2

NTS




**LEGEND** 

AXX ASBESTOS TEST LOCATION

AXX LAB TEST RESULTS POSITIVE FOR ASBESTOS REFER TO TESTING SUMMARY IN REPORT FOR FULL DETAILS. ALL SAMPLES HAVE PKPTH0915— PREFIX.



DRAWN: CTO CHECK: RAF	
FILE #:	DWG.NO:
7395-SL	C-5




LOWER YUKON SCHOOL DISTRICT PITKAS POINT
MAIN SCHOOL 1st FLOOR
ASBESTOS SAMPLE LOCATIONS



DRAWN: <b>MJL</b>	DATE:
CHECK: <b>RAF</b>	7-18-11
FILE #:	DWG.NO:

7032-SL C-1




LOWER YUKON SCHOOL DISTRICT PITKAS POINT
MAIN SCHOOL 2nd FLOOR
ASBESTOS SAMPLE LOCATIONS



DRAWN: <b>MJL</b>	DATE:
CHECK: RAF	7-18-11
FILF #:	DWG.N

7032-SL | C-2



#### LEGEND

LXX LEAD TEST LOCATION

LXX LEAD TEST CLASSIFIED AS LEAD-BASED PAINT


REFER TO TESTING SUMMARY IN REPORT FOR FULL DETAILS.

LOWER YUKON SCHOOL DISTRICT PITKAS POINT
MAIN SCHOOL 1st FLOOR
LEAD TESTING LOCATIONS



DRAWN: MJL DATE: CHECK: RAF 7-18-11

FILE #: DWG.NO: **7032-SL C-3** 





#### LEGEND

LXX LEAD TEST LOCATION

LXX LEAD TEST CLASSIFIED AS LEAD-BASED PAINT

REFER TO TESTING SUMMARY IN REPORT FOR FULL DETAILS.

LOWER YUKON SCHOOL DISTRICT PITKAS POINT
MAIN SCHOOL 2nd FLOOR
LEAD TESTING LOCATIONS



DRAWN: <b>MJL</b>	DATE:
CHECK: RAF	7-18-11
E11 E #	0110

FILE #: DWG.NO: **7032-SL C-4** 

### **APPENDIX E**

Order of Magnitude Cost Estimate

#### **Teacher Housing Unit #1**

Teacher Housing Unit #1 is in disrepair and should not be entered by unprotected workers. There is extensive fungal growth within the unit caused by various forms of water intrusion noted in the Hazardous Materials Assessment. Due to the extensive fungal growth EHS proposes two options for the unit:

- 1. Completely demolish the unit.
- 2. Completely renovate the unit which would include removal of all existing equipment, finishes, plywood subfloor, plywood ceiling, roofing, etc. After removal of all of these items the contractor would need to inspect for any other water damaged structure and replace items as necessary to complete renovation work.
- 3. There were materials that were assumed to contain asbestos due to site conditions and the limited nature of this survey. Those materials should be investigated as part of a renovation or demolition design effort.

#### **Teacher Housing Unit #2**

Teacher Housing Unit #2 is in disrepair and should not be entered by unprotected workers. There is extensive fungal growth within the unit caused by various forms of water intrusion noted in the Hazardous Materials Assessment. Due to the extensive fungal growth EHS proposes two options for the unit:

- 1. Completely demolish the unit.
- 2. Completely renovate the unit which would include removal of all existing equipment, finishes, plywood subfloor, plywood ceiling, roofing, etc. After removal of all of these items the contractor would need to inspect for any other water damaged structure and replace items as necessary to complete renovation work.
- There were materials that were assumed to contain asbestos due to site conditions and the limited nature of this survey. Those materials should be investigated as part of a renovation or demolition design effort.

#### **Main School Building**

The Main School Building is generally in fair condition with only a few areas of water damage noted, and a few areas of damaged asbestos-containing materials noted. Prior to building re-occupancy the following minimum actions are recommended:

- 1. Repair sources of water intrusion from various locations on the roof, exterior siding, and leaking piping.
- 2. Abate damaged asbestos-containing materials.

#### Assumptions made by estimate:

- 1. Mobilization costs are only for portable abatement equipment and supplies.
- 2. All non-asbestos-containing materials will be disposed of at the St. Mary's landfill at no charge.
- 3. All asbestos-containing materials will be shipped back to Anchorage and disposed of at the Anchorage Regional Landfill.
- No waste stream will be considered hazardous by TCLP testing and will be disposed of locally.
- 5. Complete demolition of Teacher Housing Units #1 & #2 would add an additional 75% to costs listed in the estimate, which does not include any costs to mobilize heavy equipment.

- 6. Costs do not include any incidental work which may arise from unforeseen conditions discovered during demolition.
- 7. No replacement costs are included, only abatement of hazards.

## HAZARDOUS MATERIALS REMOVAL COST ESTIMATE PITKAS POINT SCHOOL SITE

**PROJECT:** Pitkas Point School Site Hazmat Assessment **PROJECT NO** EHS-7395

LOCATION: Pitkas Point, Alaska CLIENT: Shannon & Wilson

ESTIMATED BY: Chris Ottosen - EHS Alaska,	Inc.	DATE:	11/05/15
BASIC QUANTITY COSTS:			
MATERIAL:	QTY UNIT	UNIT COST	TOTAL COST
TEACHER HOUSING UNIT #1			
SINK WITH UNDERCOAT	1 EA @	\$80.00	\$80
WINDOWS WITH PUTTY	120 SF @	\$4.50	\$540
BOILER (ASSUMED)	1 EA @	\$1,500.00	\$1,500
VERMICULITE (ASSUMED)	40 CY @	\$80.00	\$3,200
ROOFING TARS & SEALANTS (ASSUMED)	1,410 SF @	\$1.50	\$2,115
MERCURY LAMPS	16 EA @	\$1.00	\$16
MERCURY THERMOSTATS	1 EA @	\$10.00	\$10
MOLD RELATED REMOVAL	1 EA @	\$15,000.00	\$15,000
TEACHER HOUSING UNIT #2			
SINK WITH UNDERCOAT	1 EA @	\$80.00	\$80
WINDOWS WITH PUTTY	120 SF @	\$4.50	\$540
BOILER (ASSUMED)	1 EA @	\$1,500.00	\$1,500
VERMICULITE (ASSUMED)	40 CY @	\$80.00	\$3,200
ROOFING TARS & SEALANTS (ASSUMED)	1,410 SF @	\$1.50	\$2,115
PCB BALLAST	2 EA @	\$25.00	\$50
MERCURY LAMPS	13 EA @	\$1.00	\$13
MERCURY THERMOSTATS	1 EA @	\$10.00	\$10
MOLD RELATED REMOVAL	1 EA @	\$15,000.00	\$15,000
MAIN SCHOOL BUILDING			
FLOOR TILE & MASTIC	1,900 SF @	\$4.50	\$8,550
STAIR TREAD	40 SF @	\$5.00	\$200
ROOFING TARS & SEALANTS (ASSUMED)	8,900 SF @	\$2.50	\$22,250
MERCURY LAMPS	250 EA @	\$1.00	\$250
MOLD RELATED REMOVAL	1 EA @	\$5,000.00	\$5,000
TOTAL QUANTITY COS	STS:		\$81,219
BASIC TASK COSTS:			
PROJECT DESIGNER FEE:	1 EA @	\$500	\$500
MOBILIZATION / DEMOB:	1 LOT	\$5,000	\$5,000
TRAVEL TO SITE :	5 EA @	\$600	\$3,000
RENTAL TRUCKS - SMALL EQUIPMENT:	1 LOT	\$8,000	\$8,000
CREW PER DIEM:	12 DAYS @	\$310	\$18,600
LEAD EXPOSURE ASSESSMENT:	1 EA @	\$1,500	\$1,500
AIR MONITORING:	12 DAYS @	\$600	\$7,200
TCLP TESTING:	5 EA @	\$200	\$1,000
DISPOSAL COSTS, ASBESTOS:	2 TONS @	\$500	\$1,000
DISPOSAL COSTS, MERCURY:	2 BBLS @	\$600	\$1,200
DISPOSAL COST, PCB:	1 BBLS @	\$600.00	\$600
TOTAL TASK COSTS:			\$47,600

HAZARDOUS MATERIALS REMOVAL COST ESTIMATE PITKAS POINT SCHOOL SITE									
PROJECT: LOCATION: ESTIMATED BY:	Pitkas Point School Site Hazmat As Pitkas Point, Alaska Chris Ottosen - EHS Alaska, Inc.	ssessment	PROJECT NO CLIENT: DATE:	O EHS-7395 Shannon & 11/05/15	. Wilson				
	TOTAL BASIC COSTS: LOCATION ADJUSTMENT: CONTINGENCY: TOTAL BASIC COST ADJUSTI	INDEX = PERCEN		1.50 15	\$128,819 \$193,229 \$28,984 \$222,213				
OTHER COSTS:									
INSURANCE	3.	5 PCT			\$7,800				
BONDING	3.	5 PCT			\$7,800				
OFFICE OVERH	EAD 10.	0 PCT			\$22,200				
PROFIT	20.	0 PCT			\$44,400				
	TOTAL OTHER COSTS:				\$82,200				
-	TOTAL ESTIMATED REMOVA	AL & DISP	OSAL COST :	-	\$304,413				



#### APPENDIX E

COFFMAN ENGINEERS, PITKA'S POINT SCHOOL – STRUCTURAL INTEGRITY
ASSESSMENT



January 25, 2016

Trevor Crosby Shannon & Wilson, Inc. 5430 Fairbanks Street, Suite 3 Anchorage, Alaska 99518

Project: Pitka's Point School Pitka's Point, Alaska CEI Project #150880

Subject: PITKA'S POINT SCHOOL – STRUCTURAL INTEGRITY ASSESSMENT

#### **Scope of Work:**

Coffman Engineers has been tasked with performing a structural integrity assessment of the Teacher Housing Buildings #1 and #2 and the main school building at Pitka's Point School site in Pitka's Point, Alaska. The overall purpose of the structural integrity assessment of the selected buildings is to determine if the structures can be used as residential buildings in their current condition. If the buildings cannot be safely used in their present condition, the following assessment will be used to develop recommendations and costs to repair the structures and/or a recommendation to demolish the building(s). Due to the unknown condition of the three buildings, Coffman Engineers participated in an overnight site visit to Saint Mary's and Pitka's Point to visually assess the structures to determine if the buildings are safe for re-use in their existing condition, can be repaired, or if they should be demolished.

The site visit was completed by a Coffman representative, Structural Engineer Sean Lamb, along with Trevor Crosby (Shannon & Wilson) and Chris Ottosen (EHS-Alaska, Inc.). Trevor was responsible for soil sampling and overall site evaluation for environmental contamination, while Chris was responsible for evaluating the selected buildings for hazardous materials.

#### **Housing Building #1 Assessment:**

Housing Building #1 is a one story wood framed building with a footprint of 24'x38' (approximately 912 square feet). The following outlines the construction details of the building (also noted on S-1):

- Foundation: (15) 6x6 timber posts founded on stacked timber pads.
- Floors: Plywood floor sheathing over 2x10 floor joists spanning north-south spaced @ 2'-0"o.c. with the bottom side of the floor covered by a plywood soffit. The major floor supports consist of (3) 2x10's spanning east-west at the edges and center of the building, bearing on the 6x6 foundation posts.
- Walls: 2x6 stud framing @ 16"o.c. with T111 plywood siding. Interior wall finish is wood paneling over a vapor barrier.
- Roof: Wood trusses (assumed) at an unknown spacing. Roof diaphragm is assumed to be plywood sheathing, which is covered by metal roofing. Ceiling is covered by a plywood soffit.

#### **General Observations:**

The building was only observed from the exterior due to the presence of extreme mold growth on the interior. Per Chris Ottosen's direction, the building was not to be entered without the use of a respirator, therefore Sean was unable to enter the building for interior observation. Chris Ottosen was able to access the interior of the building with the use of a respirator. Based on his observations, he did not note any

major areas of water damage along the walls, ceiling, or floor. However, no destructive testing was performed and the condition of concealed structural roof, wall, and floor framing is unknown.

Based on exterior observation, the primary building appeared to be in sound structural condition with no major water damage noted. The following deficiencies were noted:

- Windows and doors do not appear to be weather tight.
- The boardwalk, stairs and entry landing are experiencing some water damage/rot and missing stair treads.
- Areas of the T111 paneling, covering the perimeter of the breezeway between the ground and floor soffit, have experienced water damage. In addition, the paneling blocks air flow beneath the building. Replace the T111 paneling with chain link fence or similar.

#### Recommendations for Re-use of Building:

Based on the visual observations made, Housing Building #1 appears to be structurally sound. However, in order to bring the building up to a livable condition the entire interior of the unit would need to be remediated due to the presence of extreme mold infestation, and re-constructed using new interior architectural finishes. New windows and exterior doors are also recommended.

#### **Estimated Cost of Building Repairs:**

•	Remove and replace two new exterior doors	\$5,500
•	Remove and replace six new windows	\$9,000
•	Renovate interior with new finishes (arch, elec, mech, plumbing)	\$114,000
•	Remove and replace stairs and boardwalk	\$12,000
•	Remove and replace skirting with chain-link	\$7,000
•	Small tool equipment rental – 45 days	\$4,500
•	Vehicle Rental – 45 days	\$9,000
•	Mobilization of Equipment to/from Job Site	\$20,000
•	Contractor Travel – 8 roundtrip airline tickets	\$8,000
•	Contractor Room & Board – 45 days	\$24,500
•	25% Contingency	\$53,500+/-
		\$267,000**

#### \*\* Notes:

- 1) Interior mold/water damage remediation/abatement costs are not included in the above estimate.
- 2) The estimated cost of building repairs is based on the visual observations made during the site visit and include a 25% contingency based on unknown conditions. The extent of repairs should be determined once a contractor is involved and able to expose the concealed spaces. Once the extent of damage is known, an accurate estimated cost of repairs may be developed.

#### Conclusion:

Based on the estimated cost of repair and additional cost of remediation (refer to EHS-Alaska's findings), we recommend Housing Building #1 be demolished. In the interim period, the building should remain condemned for occupation.

#### **Housing Building #2 Assessment:**

Housing Building #2 is a one story wood framed building with a footprint of 24'x38' (approximately 912 square feet). The following outlines the construction details of the building (also noted on S-1):

• Foundation: (15) 6x6 timber posts founded on stacked timber pads.

- Floors: Plywood floor sheathing over 2x10 floor joists spanning north-south spaced @ 2'-0"o.c. with the bottom side of the floor covered by a plywood soffit. The major floor supports consist of (3) 2x10's spanning east-west at the edges and center of the building, bearing on the 6x6 foundation posts.
- Walls: 2x6 stud framing @ 16"o.c. with T111 plywood siding. Interior wall finish is wood paneling over a vapor barrier.
- Roof: Wood trusses (assumed) at an unknown spacing. Roof diaphragm is assumed to be plywood sheathing, which is covered by metal roofing. Ceiling is covered by a plywood soffit.

#### General Observations:

The building was only observed from the exterior due to the presence of heavy mold growth on the interior. Per Chris Ottosen's direction, the building was not to be entered without the use of a respirator, therefore Sean was unable to enter the building for interior observation. Chris Ottosen was able to access the interior of the building with the use of a respirator. He was able to access the interior of the building with the use of a respirator. Based on his observations, he did not note any major areas of water damage along the walls, ceiling, or floor. However, no destructive testing was performed and the condition of concealed structural roof, wall, and floor framing is unknown.

Based on exterior observation, the primary building appeared to be in sound structural condition with no major water damage noted. The following deficiencies were noted:

- Windows and doors do not appear to be weather tight.
- The boardwalk, stairs and entry landing are experiencing some water damage/rot and missing stair treads.
- Areas of the T111 paneling, covering the perimeter of the breezeway between the ground and floor soffit, have experienced water damage. In addition, the paneling blocks air flow beneath the building. Replace the T111 paneling with chain link fence or similar.

#### Recommendations for Re-use of Building:

Based on the visual observations made, Housing Building #2 appears to be structurally sound. However, in order to bring the building up to a livable condition the entire interior of the unit would need to be remediated due to the presence of extreme mold infestation, and re-constructed using new interior architectural finishes. New windows and exterior doors are also recommended.

#### **Estimated Cost of Building Repairs:**

	new cost of zumumg repumst	
•	Remove and replace two new exterior doors	\$5,500
•	Remove and replace six new windows	\$9,000
•	Renovate interior with new finishes (arch, elec, mech, plumbing)	\$114,000
•	Remove and replace stairs and boardwalk	\$12,000
•	Remove and replace skirting with chain-link	\$7,000
•	Small tool equipment rental – 45 days	\$4,500
•	Vehicle Rental – 45 days	\$9,000
•	Mobilization of Equipment to/from Job Site	\$20,000
•	Contractor Travel – 8 roundtrip airline tickets	\$8,000
•	Contractor Room & Board – 45 days	\$24,500
•	25% Contingency	\$53,500+/-
		\$267,000**
		,,

#### \*\* Notes

1) Interior mold/water damage remediation/abatement costs are not included in the above estimate.

2) The estimated cost of building repairs is based on the visual observations made during the site visit, and include a 25% contingency based on unknown conditions. The extent of repairs should be determined once a contractor is involved and able to expose the concealed spaces. Once the extent of damage is known, an accurate estimated cost of repairs may be developed.

#### Conclusion:

Based on the estimated cost of repair and additional cost of remediation/abatement (refer to EHS-Alaska's findings), we recommend Housing Building #2 be demolished. In the interim period, the building should remain condemned for occupation.

#### **Main School Building Assessment:**

The main school building consists of an original high school building designed and built around 1979-1980; a major addition around 1984 and two smaller additions.

The original high school has a first floor area of approximately 4,320sf and a second floor mechanical/storage area with a footprint of approximately 1,120sf. The original high school houses a gymnasium, kitchen, two storage rooms, two bathrooms, one large classroom with a small kitchen used for Home Economics, and a smaller classroom labeled as a Vocational Education room. A 285sf cold storage room was added to the southeast corner of the building at an unknown date. A 168sf addition was also added to the west end of the Vocational Education room which occupies the original entry way landing.

Another addition was built onto the high school around 1984. The addition has a first floor area of approximately 2,180sf and a second floor area of approximately 2,120sf. The first floor of the addition is occupied by three classrooms, a bathroom, a corridor to access the existing high school, and a stairway to the second floor. The second floor of the addition is occupied by a library, boiler room, storage room, and office spaces.

The original high school building is timber construction founded on wood piles. The following is an outline of the original building construction:

- Foundation: 10" wood piles with thermosyphons strapped to their sides.
  - O The original wood piles at the north edge are no longer in use. The north 5-1/8"x16-1/2" glulam beam (GLB) is now supported by (7) W10x39 (approx.) members located near each of the original pile locations. The W10's are supported by metal brackets attached to the 5-1/8"x16-1/2" GLB located approximately 15'-0" to the south, and by a series of (7) 6"φ steel piles capped by a W10 support beam approximately 1'-0" to the north. The piles are not equipped with thermosyphons. However, settlement is not apparent along the north edge.
  - O The original wood piles at the south edge are no longer in use. The north 5-1/8"x16-1/2" GLB is now supported by (7) W10x39 (approx.) members located near each of the original pile locations. The W10's are supported by brackets at the 5-1/8"x16-1/2" GLB located approximately 11'-0" to the north, and by a series of (7) 6"φ steel piles capped by a W10 support beam located approximately 1'-0" to the south. The piles include three sets with cross braces, due to an increased pile height from grade. The piles are not equipped with thermosyphons. The piles along the south edge have experienced visual settlement, which occurs along the south wall of the Academic room.
- 1<sup>st</sup> Floor: 14" TJI-45 @ 24"o.c. with 3/4" plywood sheathing covered by 3/8" plywood underlayment and a 3/8" plywood soffit.

- 2<sup>nd</sup> Floor: 12" TJI-45 (at varying spacing) with 3/4" plywood sheathing covered by 3/8" plywood underlayment.
- Walls: 2x6 studs or 2-1/2"x7-1/2" mini-lams @ 24"o.c. with 1/2" plywood siding.
- Roof: 14" or 20" TJI-45 @ 24"o.c. covered by 3/4" plywood sheathing.

The 1984 building addition is timber construction founded on steel pipe piles. The following is an outline of the building addition's construction:

- Foundation: 10"φ steel pipe piles with integral thermosyphons by Arctic Foundations, Inc.
- 1<sup>st</sup> Floor: 20" TJI-45 @ 16"o.c. with 3/4" plywood sheathing covered by 3/8" plywood underlayment, and a 1/2" plywood soffit.
- 2<sup>nd</sup> Floor: 26" TJI-45 @ 16"o.c. with 3/4" plywood sheathing covered by 3/8" plywood underlayment.
- Walls: 2x6 studs @ 12" & 16"o.c. or 2x10's @ 12"o.c. at the corridor south wall, with 1/2" plywood siding.
- Roof: Pre-manufactured wood trusses @ 24"o.c. covered by 1/2" plywood sheathing.

#### General Observations:

The building was observed from the exterior and interior. Based on observation, the building appears to be in good overall structural condition, with a few areas of local damage and settlement. Observation of architectural finishes and components is not included in this scope of work. The following deficiencies were noted:

- Original High School Building Exterior:
  - o Several through bolts are missing at the wood pile cap brackets under the building.
  - o Several of the GLB's appear to have rolled slightly from their vertical position at the wood pile caps under the building.
  - o The stair at the north edge of the building, located at the northeast corner of the library, has an intermediate landing supported by knee braces bolted into shear tabs welded to a steel pile. One of the shear tabs has deformed, resulting in a cracked weld to the pile. The pile is not equipped with a thermosiphon.
  - o T111 siding is missing at the top of the wall in the northeast corner of the gymnasium. The missing siding has resulted in water entering the building wall.
  - o The stairs at the east walkway are not present.
  - o Settlement/movement of the building is apparent along the roof line at the east edge of the building.
  - O The 285sf cold storage room addition, located at the southeast corner of the building, is currently condemned for entry/access. The addition consists of floor framing fastened to the main building's perimeter glulam beam with joist hangers. The east end of the addition was originally supported by two rows of wood posts & beams. However, the original wood post & beam supports settled (no longer in contact with the floor framing) and have been replaced by a single set of steel pipe posts and glulam beam. The steel pipe posts are not equipped with thermosyphons and appear to be experiencing settlement. As a result of the settlement the addition has pulled away from the main building and become unstable.
  - Settlement/movement of the building is apparent along the south edge of the Academic room. The settlement appears to be occurring at the south row of steel pipe replacement piles which are not equipped with thermosyphons.
  - The original entry landing at the west side of the building has been infilled to create an
    extension off of the Academic room. The general construction of the addition is poor.
    The flashing/weather proofing details between the main building appear to be failing and
    allowing water to enter the building.

- o The stairs at the west entry to the main building, next to the addition to the Academic room, are not present.
- 1984 Building Addition Exterior:
  - O The stair at the main entry, located at the west side of the building, is missing the top stair tread. In addition, the wood framing at the perimeter of the main entry landing has experienced water damage.
  - o The remainder of the exterior of the 1984 building addition appears to be in good condition.
- Original High School Building Interior:
  - General note: the interior of all surfaces are covered by architectural finishes.
     Observations made were visual only, with no destructive measures taken to verify the condition of concealed spaces.
  - O The exterior siding is missing at the northeast corner of the gymnasium. As a result, water has been able to enter the wall. Daylight is visible at the top of the wall since the intersection of the wall and ceiling sheetrock has been damaged. The 3/8" plywood floor underlayment at the northeast corner of the gymnasium is experiencing water damage/rot. The extent of water infiltration into the first floor system is unknown. A layer of plastic sheeting vapor barrier is present beneath the underlayment and may have prevented water from entering the main floor framing.
  - o The wall at the east side of the gymnasium appears to have experienced movement, resulting in large cracks in the sheetrock.
  - O Active leaks are present in the kitchen. The leaks are a result of an active roof leak in the mechanical room above. The 3/8" plywood floor underlayment appears to have bubbled at the leak locations. The extent of water infiltration into the first floor system is unknown. A layer of plastic sheeting is present beneath the underlayment and may have prevented water from entering the main floor framing.
  - Water damage is present at the wall above the door between the Academic room and kitchen. The water damage is a result of an active roof leak in the mechanical room above the kitchen.
  - o Cracks are present in the ceiling of the Vocational Education room. The cracks are likely the result of the pile settlement which has occurred at the south edge of the building.
  - O The second floor mechanical room has experienced significant water damage. Water appears to be entering the room at the roof penetration around the mechanical exhaust stacks. Standing water is present on the floor, and the plywood floor surface has experienced water damage/rot. The extent of damage to the floor framing members is unknown.
- 1984 Building Addition Interior:
  - General note: the interior of all surfaces are covered by architectural finishes.
     Observations made were visual only, with no destructive measures taken to verify the condition of structure within concealed spaces.
  - o Small water stains are present at the classroom hallway.
  - O Small cracks are present at the sheetrock seams of the walls and ceilings of classrooms first floor classrooms (1-3).
  - o The floor carpet at classroom 3 is stained directly beneath a suspected leak at the ceiling above. The ceiling directly above the floor stain is damaged in the form of a failed taped sheetrock joint. The leak is suspected to be the result of a heating pipe leak, but could not be verified.
  - o Large cracks are present in the sheetrock ceiling of the second floor library. One large crack is at the top of the stairs and spans north-south. The other large crack is at the north half of the room and spans east-west, located at the midspan between the north load

bearing wall and the glulam support at the middle of the room. The cracks are presumed to be the result of pile settlement.

o The remainder of interior of the 1984 building addition appears to be in good condition.

#### Recommendations for Re-use of Building:

Based on the visual observations made, the main school building appears to be in good overall structural condition and re-use of the building is an option. However, we recommend deficiencies noted above be addressed to convert the building for residential use. Specifically, shims shall be installed at the pile caps to level the building. In addition, the building shall be weather proofed and damage due to water infiltration should be repaired. We recommend the cold storage room be removed/demolished or releveled and strengthened with new piles/girders.

	ea ana sirenginenea with hew phos ghadis.	
•	Install shim kits at pile caps	\$53,000
•	Install new thermosyphons at north & south edges (typical of 14)	\$134,000
•	Install stairs at west entry of original high school building	\$10,000
•	Repair west entry stairs to 1984 building addition	\$5,000
•	Repair siding/framing at northeast corner of gymnasium	\$18,000
•	Repair cold storage room	\$38,000
•	Repair Voc. Ed room extension	\$5,000
•	Repair mechanical room roof and floor framing	\$76,000
•	Equipment Rental Man-lift & Crane – 60 days	\$66,000
•	Vehicle Rental – 60 days	\$12,000
•	Mobilization of Equipment to/from Job Site	\$50,000
•	Contractor Travel – 6 roundtrip airline tickets	\$6,000
•	Contractor Room & Board – 60 days, 4-man crew	\$42,000
•	50% Contingency	\$258,000
		\$773,000**

#### \*\* Notes:

- 1) Interior mold/water damage remediation/abatement, architectural, mechanical, and electrical scope of work is not included in the above estimate.
- 2) The estimated cost of building repairs is based on the visual observations made during the site visit, and include a 50% contingency based on unknown conditions. The extent of repairs should be determined once a contractor is involved and able to expose the concealed spaces. Once the extent of damage is known, an accurate estimated cost of repairs may be developed.

#### Conclusion:

The main school building appears to be in good overall structural condition. We recommend the above building repairs be completed to convert the building for residential use. We believe the above information accurately reflects the activities that were performed during the site visit. Please feel free to share this document with all appropriate parties. If there are any questions or clarifications regarding this report please feel free to contact a Coffman representative directly.

Sincerely,

COFFMAN ENGINEERS, INC.


Sean Lamb, PE, SE


Civil/Structural Engineering

Will Veelman, PE, SE

Principal, Civil/Structural Engineering

## **Plans with Photo Callouts**





# **School Photos**



1. North Elevation



2. Missing Exterior Siding – NE Corner Gymnasium



3. East Side of School



4. Cold Storage Room



5. Cold Storage Room – Separation of Structure From Existing Building



6. South Elevation



7. Roof Deformation



8. South Wall of Academic Room



9. View Looking NE



10. Foundation Modification at North Edge of Original Building - 1



11. Foundation Modification at North Edge of Original Building - 2



12. Rolled GLB & Missing Pile Saddle Bolts



13. Foundation Modification at South Edge of Original Building - 1



14. Steel Pipe Pile Foundation at Addition



15. Cracked Weld at Stair Connection



16. Gymnasium



17. Water Damage at Wall of NE Corner of Gymnasium



18. Water Damage at Floor of NE Corner of Gymnasium



19. Cracks at East Wall of Gymnasium



20. Active Leak at Ceiling of Kitchen



21. Academic Room



22. Water Damage at NE Corner of Academic Room



23. Vocational Education Room



24. Mechanical Room Roof Leak - 2



25. Mechanical Room Roof Leak - 3



26. Mechanical Room Roof Leak - 1



27. Water Stain at Corridor 103



28. Ceiling Water Damage at Corridor 106



29. Ceiling Sheetrock Damage at Library Entry

30. Ceiling Sheetrock Damage at North Half of Library – 1



31. Ceiling Sheetrock Damage at North Half of Library

## **Housing Photos**







33. Housing Units #1 & #2



34. Housing Units #1





35. Housing Unit #1a

36. Stair #1



37. Housing Unit #1b





38. Housing Unit #2

39. Stair #2



40. Typical Housing Unit Foundation

### SHANNON & WILSON, INC.

# APPENDIX F CONCEPTUAL SITE MODEL

### **HUMAN HEALTH CONCEPTUAL SITE MODEL GRAPHIC FORM**

Site: Pitkas Point School Site, Pitkas Point, Alaska	Instructions: Follow the numbered directions below. Do not consider contaminant concentrations or engineering/land								
Completed By: Shannon & Wilson Date Completed: January 2016		use controls when describing path		tify the rece		(5)		ted by	each
(1) Check the media that could be directly affected by the release. For each medium identified in (1), follow the top arrow and check possible transport mechanisms. Check additional media under (1) if the media acts as a secondary source.	(3) Check all exposure media identified in (2).	(4) Check all pathways that could be complete. The pathways identified in this column must agree with Sections 2 and 3 of the Human Health CSM Scoping Form.	"F" t futu <b>C</b>	osure pathwa for future rec re receptors, current	eptors, or "I" fo & Fu	"C/F" fo for insign uture	or both nificant Rec	currer expos cept	nt and sure.
Media Transport Mechanisms    J	Exposure Media	Exposure Pathway/Route	Residents	Commercial or Site Visitors	Construction	Farmers or subsista	Subsistence cong	Other	
Runoff or erosion check surface water		cidental Soil Ingestion	C/F	C/F C/F	C/F				
Uptake by plants or animals check biota	soil D	ermal Absorption of Contaminants from Soil							
Other (list):	l In	halation of Fugitive Dust							
Subsurface   Migration to groundwater   Check groundwater   Check groundwater   Check groundwater   Check groundwater   Check groundwater   Check air   Check air   Check biota   Check groundwater   Check groundwater	groundwater D	ermal Absorption of Contaminants in Groundwater halation of Volatile Compounds in Tap Water	F	F F	F				
Direct release to groundwater check groundwater			- <i>-</i> -		- /-				
Ground- water  Volatilization check air Flow to surface water body check surface water		halation of Outdoor Air		C/F C/F		-			
Flow to sediment check sediment		halation of Indoor Air	C/F	C/F C/F	C/F	-			
Uptake by plants or animals check biota Other (list):	III In	halation of Fugitive Dust							
Direct release to surface water check surface water	\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \	gestion of Surface Water	C/F	C/F C/F	C/F				
Surface Volatilization check air	surface water Do	ermal Absorption of Contaminants in Surface Water							
Water Sedimentation check sediment Uptake by plants or animals check biota	In	halation of Volatile Compounds in Tap Water							
Other (list):  Direct release to sediment check sediment	sediment	irect Contact with Sediment							
Sediment	□ biota □ In	ngestion of Wild or Farmed Foods							

Print Form

### Human Health Conceptual Site Model Scoping Form

Site Name:	Pitkas Point School Site, Pitkas Point, Alaska			
File Number:	ADEC File ID: 2444.57.001			
Completed by:	Shannon & Wilson			
about which exposummary text about characterization v	be used to reach agreement with the sure pathways should be further invout the CSM and a graphic depicting work plan and updated as needed in structions: Follow the italicized instructions	estigated dur exposure pa ater reports.	ring site characto hthways should b	erization. From this information
1. General In Sources (check p	formation: potential sources at the site)			
USTs		☐ Vehicles	S	
⊠ ASTs		☐ Landfills	S	
☐ Dispensers/fue	pensers/fuel loading racks			
⊠ Drums		Other:		
Release Mechan	isms (check potential release mecha	nisms at the	site)	
⊠ Spills	⊠ Direct discharge			
⊠ Leaks	aks   Burning			
		Other:		
Impacted Media	(check potentially-impacted media	at the site)	,	
⊠ Surface soil (0	0-2 feet bgs*)	⊠ Groundy	water	
⊠ Subsurface so	il (>2 feet bgs)	<b>⊠</b> Surface	water	
⊠ Air		☐ Biota		
☐ Sediment		☐ Other:		
Receptors (check	receptors that could be affected by	contamination	on at the site)	
Residents (adu	sidents (adult or child)   Site visitor			
	l or industrial worker   Trespasser			
⊠ Construction v	vorker	⊠ Recreational user		
Subsistence ha	arvester (i.e. gathers wild foods)	Farmer		
☐ Subsistence co	onsumer (i.e. eats wild foods)	Other:		

2.	<b>Exposure Pathways:</b> (The answers to the following quexposure pathways at the site. Check each box where the	-				
a)	Direct Contact -  1. Incidental Soil Ingestion					
	Are contaminants present or potentially present in surface soil b (Contamination at deeper depths may require evaluation on a sit		ne ground surface?			
	If the box is checked, label this pathway complete:	Complete				
	Comments:					
	2. Dermal Absorption of Contaminants from Soil Are contaminants present or potentially present in surface soil b (Contamination at deeper depths may require evaluation on a sit		ne ground surface? ⊠			
	Can the soil contaminants permeate the skin (see Appendix B in					
	If both boxes are checked, label this pathway complete:	Incomplete				
	Comments:					
	Appendix B compounds have not been documented in the soil on the pro-	operty.				
b)	Ingestion -  1. Ingestion of Groundwater					
	Have contaminants been detected or are they expected to be detected or are contaminants expected to migrate to groundwater in the fi	_	×			
	Could the potentially affected groundwater be used as a current source? Please note, only leave the box unchecked if DEC has dwater is not a currently or reasonably expected future source of to 18 AAC 75.350.	letermined the ground-	X			
	If both boxes are checked, label this pathway complete:	Complete				
	Comments:					

### 2. Ingestion of Surface Water Have contaminants been detected or are they expected to be detected in surface water, $\overline{X}$ or are contaminants expected to migrate to surface water in the future? Could potentially affected surface water bodies be used, currently or in the future, as a $\overline{\times}$ drinking water source? Consider both public water systems and private use (i.e., during residential, recreational or subsistence activities). *If both boxes are checked, label this pathway complete:* Complete Comments: Contaminants could potentially be discharged directly into or migrate to the nearby surface drinking water source. 3. Ingestion of Wild and Farmed Foods Is the site in an area that is used or reasonably could be used for hunting, fishing, or harvesting of wild or farmed foods? Do the site contaminants have the potential to bioaccumulate (see Appendix C in the guidance document)? Are site contaminants located where they would have the potential to be taken up into biota? (i.e. soil within the root zone for plants or burrowing depth for animals, in groundwater that could be connected to surface water, etc.) If all of the boxes are checked, label this pathway complete: Incomplete Comments: c) Inhalation-1. Inhalation of Outdoor Air Are contaminants present or potentially present in surface soil between 0 and 15 feet below the ground surface? (Contamination at deeper depths may require evaluation on a site specific basis.)

 $\overline{X}$ 

Are the contaminants in soil volatile (see Appendix D in the guidance document)?

 $\overline{\times}$ 

*If both boxes are checked, label this pathway complete:* 

Complete

#### Comments:

Appendix D compounds (petroleum hydrocarbon constituents) are present in impacted soil on the Property.

#### 2. Inhalation of Indoor Air

Are occupied buildings on the site or reasonably expected to be occupied or placed on the site in an area that could be affected by contaminant vapors? (within 30 horizontal or vertical feet of petroleum contaminated soil or groundwater; within 100 feet of non-petroleum contaminated soil or groundwater; or subject to "preferential pathways," which promote easy airflow like utility conduits or rock fractures)

 $\overline{X}$ 

Are volatile compounds present in soil or groundwater (see Appendix D in the guidance document)?

 $\overline{\times}$ 

If both boxes are checked, label this pathway complete:

Complete

#### Comments:

Appendix D compounds (petroleum hydrocarbon constituents) are present in impacted soil on the Property. Several buildings on the Property are elevated on pilings. The exposure pathway for inhalation of indoor air is likely mitigated in these structures based on the airflow between the building and ground surface.

3.	Additional Exposure Pathways: (Although there are no definitive questions provide these exposure pathways should also be considered at each site. Use the guidelines provide determine if further evaluation of each pathway is warranted.)	
De	ermal Exposure to Contaminants in Groundwater and Surface Water	
	Dermal exposure to contaminants in groundwater and surface water may be a complete path Climate permits recreational use of waters for swimming.  Climate permits exposure to groundwater during activities, such as construction.  Groundwater or surface water is used for household purposes, such as bathing or cl.  Generally, DEC groundwater cleanup levels in 18 AAC 75, Table C, are assumed to be propathway.	eaning.
	Check the box if further evaluation of this pathway is needed:	
C	omments:	
ln	halation of Volatile Compounds in Tap Water	
	<ul> <li>Inhalation of volatile compounds in tap water may be a complete pathway if:</li> <li>The contaminated water is used for indoor household purposes such as showering, washing.</li> <li>The contaminants of concern are volatile (common volatile contaminants are listed guidance document.)</li> </ul>	<u> </u>
	Generally, DEC groundwater cleanup levels in 18 AAC 75, Table C, are assumed to be propathway.	otective of this
C	Check the box if further evaluation of this pathway is needed: omments:	

#### **Inhalation of Fugitive Dust**

Inhalation of fugitive dust may be a complete pathway if:

- Nonvolatile compounds are found in the top 2 centimeters of soil. The top 2 centimeters of soil are likely to be dispersed in the wind as dust particles.
- O Dust particles are less than 10 micrometers (Particulate Matter PM<sub>10</sub>). Particles of this size are called respirable particles and can reach the pulmonary parts of the lungs when inhaled.
- O Chromium is present in soil that can be dispersed as dust particles of any size.

Generally, DEC direct contact soil cleanup levels in Table B1 of 18 AAC 75 are protective of this pathway because it is assumed most dust particles are incidentally ingested instead of inhaled to the lower lungs. The inhalation pathway only needs to be evaluated when very small dust particles are present (e.g., along a dirt roadway or where dusts are a nuisance). This is not true in the case of chromium. Site specific cleanup levels will need to be calculated in the event that inhalation of dust containing chromium is a complete pathway at a site.

Check the box if further evaluation of this pathway is needed:	
Comments:	_
Direct Contact with Sediment	
This pathway involves people's hands being exposed to sediment, such as during some recording or industrial activity. People then incidentally ingest sediment from normal hand-to-mouth addition, dermal absorption of contaminants may be of concern if the the contaminants are skin (see Appendix B in the guidance document). This type of exposure should be investig Climate permits recreational activities around sediment.  The community has identified subsistence or recreational activities that would resure sediment, such as clam digging.	h activities. In able to permeate the sated if:
Generally, DEC direct contact soil cleanup levels in 18 AAC 75, Table B1, are assumed to contact with sediment.	be protective of direct
Check the box if further evaluation of this pathway is needed:	
Comments:	7

#### APPENDIX A

#### BIOACCUMULATIVE COMPOUNDS OF POTENTIAL CONCERN

Organic compounds are identified as bioaccumulative if they have a BCF equal to or greater than 1,000 or a log K<sub>ow</sub> greater than 3.5. Inorganic compounds are identified as bioaccumulative if they are listed as such by EPA (2000). Those compounds in Table B-1 of 18 AAC 75.341 that are bioaccumulative, based on the definition above, are listed below.

Aldrin	DDT	Lead
Arsenic	Dibenzo(a,h)anthracene	Mercury
Benzo(a)anthracene	Dieldrin	Methoxychlor
Benzo(a)pyrene	Dioxin	Nickel
Benzo(b)fluoranthene	Endrin	PCBs
Benzo(k)fluoranthene	Fluoranthene	
Cadmium	Heptachlor	Pyrene
Chlordane	Heptachlor epoxide	Selenium
Chrysene	Hexachlorobenzene	Silver
Copper	Hexachlorocyclopentadiene	Toxaphene
DDD	Indeno(1,2,3-c,d)pyrene	Zinc
DDE		

Because BCF values can relatively easily be measured or estimated, the BCF is frequently used to determine the potential for a chemical to bioaccumulate. A compound with a BCF greather than 1,000 is considered to bioaccumulate in tissue (EPA 2004b).

For inorganic compounds, the BCF approach has not been shown to be effective in estimating the compound's ability to bioaccumulate. Information available, either through scientific literature or site-specific data, regarding the bioaccumulative potential of an inorganic site contaminant should be used to determine if the pathway is complete.

The list was developed by including organic compounds that either have a BCF equal to or greater than 1,000 or a  $\log K_{ow}$  greater than 3.5 and inorganic compounds that are listed by the United States Environmental Protection Agency (EPA) as being bioaccumulative (EPA 2000).

The list was developed by including organic compounds that either have a BCF equal to or greater than 1,000 or a  $\log$  Kow greater than 3.5 and inorganic compounds that are listed by the United States Environmental Protection Agency (EPA) as being bioaccumulative (EPA 2000). The BCF can also be estimated from a chemical's physical and chemical properties. A chemical's octanol-water partitioning coefficient (Kow) along with defined regression equations can be used to estimate the BCF. EPA's Persistent, Bioaccumulative, and Toxic (PBT) Profiler (EPA 2004) can be used to estimate the BCF using the Kow and linear regressions presented by Meylan et al. (1996). The PBT Profiler is located at http://www.pbtprofiler.net/. For compounds not found in the PBT Profiler, DEC recommends using a log  $K_{ow}$  greater than 3.5 to determine if a compound is bioaccumulative.

#### APPENDIX B

#### SOIL CONTAMINANTS EVALUATED FOR DERMAL EXPOSURE

Soil contaminants are evaluated for dermal exposure when a specific absorption factor is available (EPA, 2004c). If specific absorption factors are not available, chemicals with a Henry's constant below 1 x 10<sup>-5</sup> atm-m<sup>3</sup>/mol and molecular weight below 400 g/mol are evaluated as semi volatile organic compounds. It is generally thought volatile compounds evaporate from skin before significant absorption occurs and are addressed through the inhalation exposure pathway. Compounds with a molecular weight greater than 400 g/mol are considered too large to be absorbed through the skin.

2-Amino-4,6-Dinitrotoluene	2,4-Dichlorophenol	Methoxychlor
4-Amino-2,6-Dinitrotoluene	Dieldrin	Mercury (Methyl)
Acenaphthene	Diethyl phthalate	1-Methylnaphthalene
Acenaphthylene	2,4-Dimethylphenol	2-Methylnaphthalene
Aldrin	Dimethyl phthalate	2-Methylphenol (o-cresol)
Anthracene	1,2-Dinitrobenzene	3-Methylphenol (m-cresol)
Arsenic	1,3-Dinitrobenzene	4-Methylphenol (p-cresol)
Benzo(a)anthracene	1,4-Dinitrobenzene	Naphthalene
Benzo(b)fluoranthene	2,4-Dinitrophenol	Nitroglycerin
Benzo(k)fluoranthene	2,4-Dinitrotoluene	Nitroguanidine
Benzoic Acid	2,6-Dinitrotoluene	n-Nitrosodiphenylamine
Benzo(g,h,i)perylene	1,4-Dioxane	n-Nitroso-di-n-propylamine
Benzo(a)pyrene	2,3,7,8-TCDD (Dioxin)	2-Nitrotoluene
Bis(2-ethylhexyl)phthalate	Diphenylamine	3-Nitrotoluene
Butanol	Endrin	4-Nitrotoluene
Butyl Benzyl Phthalate	Ethylene glycol	Octahydro-1,3,5,7-tetranitro-1,3,5,7-
		tetrazocine (HMX)
Cadmium	Fluoranthene	Pentachlorophenol
Carbazole	Fluorene	Phenanthrene
Carbon Disulfide	Heptachlor	Phenol
Chlordane	Heptachlor epoxide	PCB
p-Chloroaniline	Hexachlorobenzene	Propylene glycol
2-Chloronaphthalene	Hexachloro-1,3-butadiene	Pyrene
Chrysene	alpha-Hexachlorocyclohexane	Tributyltin (as Tributyltin Oxide)
DDD	beta-Hexachlorocyclohexane	2,4,5-Trichlorophenol
DDE	gamma-Hexachlorocyclohexane	2,4,6-Trichlorophenol
DDT	Hexachlorocyclopentadiene	2,4,5-TP
Dibenzo(a,h)anthracene	Hexachloroethane	1,3,5-Trinitrobenzene
Di-n-butyl phthalate	Hexahydro-1,3,5-trinitro-1,3,5-	2,4,6-Trinitrophenylmethylnitramine
	triazine (RDX)	(Tetryl)
Di-n-octyl phthalate	Hydrazine	2,4,6-Trinitrotoluene (TNT)
2,4-D	Indeno(1,2,3-c,d)pyrene	
3,3-Dichlorobenzidine	Isophorone	

#### APPENDIX C

#### BIOACCUMULATIVE COMPOUNDS OF POTENTIAL CONCERN

Organic compounds are identified as bioaccumulative if they have a BCF equal to or greater than 1,000 or a log K<sub>ow</sub> greater than 3.5. Inorganic compounds are identified as bioaccumulative if they are listed as such by EPA (2000). Those compounds in Table B-1 of 18 AAC 75.341 that are bioaccumulative, based on the definition above, are listed below.

Aldrin	DDT	Mercury
Arsenic	Dibenzo(a,h)anthracene	Methoxychlor
Benzo(a)anthracene	Dieldrin	Nickel
Benzo(a)pyrene	Dioxin	PCBs
Benzo(b)fluoranthene	Endrin	Pyrene
Benzo(k)fluoranthene	Fluoranthene	Selenium
Cadmium	Heptachlor	Silver
Chlordane	Heptachlor epoxide	Toxaphene
Chrysene	Hexachlorobenzene	Zinc
Copper	Hexachlorocyclopentadiene	
DDD	Indeno(1,2,3-c,d)pyrene	
DDE	Lead	

Because BCF values can relatively easily be measured or estimated, the BCF is frequently used to determine the potential for a chemical to bioaccumulate. A compound with a BCF greater than 1,000 is considered to bioaccumulate in tissue (EPA 2004b).

For inorganic compounds, the BCF approach has not been shown to be effective in estimating the compound's ability to bioaccumulate. Information available, either through scientific literature or site-specific data, regarding the bioaccumulative potential of an inorganic site contaminant should be used to determine if the pathway is complete.

The list was developed by including organic compounds that either have a BCF equal to or greater than 1,000 or a log  $K_{\rm ow}$  greater than 3.5 and inorganic compounds that are listed by the United States Environmental Protection Agency (EPA) as being bioaccumulative (EPA 2000). The BCF can also be estimated from a chemical's physical and chemical properties. A chemical's octanol-water partitioning coefficient ( $K_{\rm ow}$ ) along with defined regression equations can be used to estimate the BCF. EPA's Persistent, Bioaccumulative, and Toxic (PBT) Profiler (EPA 2004) can be used to estimate the BCF using the  $K_{\rm ow}$  and linear regressions presented by Meylan et al. (1996). The PBT Profiler is located at http://www.pbtprofiler.net/. For compounds not found in the PBT Profiler, DEC recommends using a log  $K_{\rm ow}$  greater than 3.5 to determine if a compound is bioaccumulative.

#### APPENDIX D

#### **VOLATILE COMPOUNDS OF POTENTIAL CONCERN**

A chemical is identified here as sufficiently volatile and toxic for further evaluation if the Henry's Law constant is  $1 \times 10^{-5}$  atm-m<sup>3</sup>/mol or greater, the molecular weight is less than 200 g/mole (EPA 2004a), and the vapor concentration of the pure component posed an incremental lifetime cancer risk greater than  $10^{-6}$  or a non-cancer hazard quotient of 0.1, or other available scientific data indicates the chemical should be considered a volatile. Chemicals that are solid at typical soil temperatures and do not sublime are generally not considered volatile.

Acetone	Mercury (elemental)
Benzene	Methyl bromide (Bromomethane)
Bis(2-chloroethyl)ether	Methyl chloride (Chloromethane)
Bromodichloromethane	Methyl ethyl ketone (MEK)
Bromoform	Methyl isobutyl ketone (MIBK)
n-Butylbenzene	Methylene bromide
sec-Butylbenzene	Methylene chloride
tert-Buytlbenzene	1-Methylnaphthalene
Carbon disulfide	2-Methylnaphthalene
Carbon tetrachloride	Methyl tert-butyl ether (MTBE)
Chlorobenzene	Naphthalene
Chlorodibromomethane (Dibromochloromethane)	Nitrobenzene
Chloroethane	n-Nitrosodimethylamine
Chloroform	n-Propylbenzene
2-Chlorophenol	Styrene
1,2-Dichlorobenzene	1,1,2,2-Tetrachloroethane
1,3-Dichlorobenzene	Tetrachloroethylene (PCE)
1,4-Dichlorobenzene	Toluene
Dichlorodifluoromethane	1,2,4-Trichlorobenzene
1,1-Dichloroethane	1,1,1-Trichloroethane
1,2-Dichloroethane	1,1,2-Trichloroethane
1,1-Dichloroethylene	Trichloroethylene (TCE)
cis-1,2-Dichloroethylene	2,4,6-Trichlorophenol
trans-1,2-Dichloroethylene	1,2,3-Trichloropropane
1,2-Dichloropropane	1,1,2-Trichloro-1,2,2-trifluoroethane (Freon-113)
1,3-Dichloropropane	Trichlorofluoromethane (Freon-11)
Ethylbenzene	1,2,4-Trimethylbenzene
Ethylene dibromide (1,2-Dibromoethane)	1,3,5-Trimethylbenzene
Hexachlorobenzene	Vinyl acetate
Hexachloro-1,3-butadiene	Vinyl chloride (Chloroethene)
Hexachlorocyclopentadiene	Xylenes (total)
Hexachloroethane	GRO (see note 3 below)
Hydrazine	DRO (see note 3 below)
Isopropylbenzene (Cumene)	RRO (see note 3 below)

#### APPENDIX G

## IMPORTANT INFORMATION ABOUT YOUR GEOTECHNICAL/ENVIRONMENTAL REPORT

Attachment to and part of Report 32-1-17747-001

Date: January 2016

To: Alaska Department of Environmental

Conservation

Re: Site Assessment, Pitkas Point School Site,

Pitkas Point

## IMPORTANT INFORMATION ABOUT YOUR GEOTECHNICAL/ENVIRONMENTAL REPORT

#### CONSULTING SERVICES ARE PERFORMED FOR SPECIFIC PURPOSES AND FOR SPECIFIC CLIENTS.

Consultants prepare reports to meet the specific needs of specific individuals. A report prepared for a civil engineer may not be adequate for a construction contractor or even another civil engineer. Unless indicated otherwise, your consultant prepared your report expressly for you and expressly for the purposes you indicated. No one other than you should apply this report for its intended purpose without first conferring with the consultant. No party should apply this report for any purpose other than that originally contemplated without first conferring with the consultant.

#### THE CONSULTANT'S REPORT IS BASED ON PROJECT-SPECIFIC FACTORS.

A geotechnical/environmental report is based on a subsurface exploration plan designed to consider a unique set of project-specific factors. Depending on the project, these may include: the general nature of the structure and property involved; its size and configuration; its historical use and practice; the location of the structure on the site and its orientation; other improvements such as access roads, parking lots, and underground utilities; and the additional risk created by scope-of-service limitations imposed by the client. To help avoid costly problems, ask the consultant to evaluate how any factors that change subsequent to the date of the report may affect the recommendations. Unless your consultant indicates otherwise, your report should not be used: (1) when the nature of the proposed project is changed (for example, if an office building will be erected instead of a parking garage, or if a refrigerated warehouse will be built instead of an unrefrigerated one, or chemicals are discovered on or near the site); (2) when the size, elevation, or configuration of the proposed project is altered; (3) when the location or orientation of the proposed project is modified; (4) when there is a change of ownership; or (5) for application to an adjacent site. Consultants cannot accept responsibility for problems that may occur if they are not consulted after factors which were considered in the development of the report have changed.

#### SUBSURFACE CONDITIONS CAN CHANGE.

Subsurface conditions may be affected as a result of natural processes or human activity. Because a geotechnical/environmental report is based on conditions that existed at the time of subsurface exploration, construction decisions should not be based on a report whose adequacy may have been affected by time. Ask the consultant to advise if additional tests are desirable before construction starts; for example, groundwater conditions commonly vary seasonally.

Construction operations at or adjacent to the site and natural events such as floods, earthquakes, or groundwater fluctuations may also affect subsurface conditions and, thus, the continuing adequacy of a geotechnical/environmental report. The consultant should be kept apprised of any such events, and should be consulted to determine if additional tests are necessary.

#### MOST RECOMMENDATIONS ARE PROFESSIONAL JUDGMENTS.

Site exploration and testing identifies actual surface and subsurface conditions only at those points where samples are taken. The data were extrapolated by your consultant, who then applied judgment to render an opinion about overall subsurface conditions. The actual interface between materials may be far more gradual or abrupt than your report indicates. Actual conditions in areas not sampled may differ from those predicted in your report. While nothing can be done to prevent such situations, you and your consultant can work together to help reduce their impacts. Retaining your consultant to observe subsurface construction operations can be particularly beneficial in this respect.

Page 1 of 2 1/2015

#### A REPORT'S CONCLUSIONS ARE PRELIMINARY.

The conclusions contained in your consultant's report are preliminary because they must be based on the assumption that conditions revealed through selective exploratory sampling are indicative of actual conditions throughout a site. Actual subsurface conditions can be discerned only during earthwork; therefore, you should retain your consultant to observe actual conditions and to provide conclusions. Only the consultant who prepared the report is fully familiar with the background information needed to determine whether or not the report's recommendations based on those conclusions are valid and whether or not the contractor is abiding by applicable recommendations. The consultant who developed your report cannot assume responsibility or liability for the adequacy of the report's recommendations if another party is retained to observe construction.

#### THE CONSULTANT'S REPORT IS SUBJECT TO MISINTERPRETATION.

Costly problems can occur when other design professionals develop their plans based on misinterpretation of a geotechnical/environmental report. To help avoid these problems, the consultant should be retained to work with other project design professionals to explain relevant geotechnical, geological, hydrogeological, and environmental findings, and to review the adequacy of their plans and specifications relative to these issues.

#### BORING LOGS AND/OR MONITORING WELL DATA SHOULD NOT BE SEPARATED FROM THE REPORT.

Final boring logs developed by the consultant are based upon interpretation of field logs (assembled by site personnel), field test results, and laboratory and/or office evaluation of field samples and data. Only final boring logs and data are customarily included in geotechnical/environmental reports. These final logs should not, under any circumstances, be redrawn for inclusion in architectural or other design drawings, because drafters may commit errors or omissions in the transfer process.

To reduce the likelihood of boring log or monitoring well misinterpretation, contractors should be given ready access to the complete geotechnical engineering/environmental report prepared or authorized for their use. If access is provided only to the report prepared for you, you should advise contractors of the report's limitations, assuming that a contractor was not one of the specific persons for whom the report was prepared, and that developing construction cost estimates was not one of the specific purposes for which it was prepared. While a contractor may gain important knowledge from a report prepared for another party, the contractor should discuss the report with your consultant and perform the additional or alternative work believed necessary to obtain the data specifically appropriate for construction cost estimating purposes. Some clients hold the mistaken impression that simply disclaiming responsibility for the accuracy of subsurface information always insulates them from attendant liability. Providing the best available information to contractors helps prevent costly construction problems and the adversarial attitudes that aggravate them to a disproportionate scale.

#### READ RESPONSIBILITY CLAUSES CLOSELY.

Because geotechnical/environmental engineering is based extensively on judgment and opinion, it is far less exact than other design disciplines. This situation has resulted in wholly unwarranted claims being lodged against consultants. To help prevent this problem, consultants have developed a number of clauses for use in their contracts, reports and other documents. These responsibility clauses are not exculpatory clauses designed to transfer the consultant's liabilities to other parties; rather, they are definitive clauses that identify where the consultant's responsibilities begin and end. Their use helps all parties involved recognize their individual responsibilities and take appropriate action. Some of these definitive clauses are likely to appear in your report, and you are encouraged to read them closely. Your consultant will be pleased to give full and frank answers to your questions.

The preceding paragraphs are based on information provided by the ASFE/Association of Engineering Firms Practicing in the Geosciences, Silver Spring, Maryland

Page 2 of 2 1/2015